# Task ET-WIN-PNNL-FY13-01\_5.3: Database of Low-e Storm Window Energy Performance across U.S. Climate Zones

September 2013

#### DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or Battelle Memorial Institute. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PACIFIC NORTHWEST NATIONAL LABORATORY

operated by

BATTELLE

for the


UNITED STATES DEPARTMENT OF ENERGY

under Contract DE-AC05-76RL01830

Printed in the United States of America

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831-0062; ph: (865) 576-8401 fax: (865) 576-5728 email: reports@adonis.osti.gov

Available to the public from the National Technical Information Service 5301 Shawnee Rd., Alexandria, VA 22312
ph: (800) 553-NTIS (6847)
email: orders@ntis.gov <a href="mailto-shape-shap



# Task ET-WIN-PNNL-FY13-01\_5.3: **Database of Low-e Storm Window Energy Performance across U.S. Climate Zones**

KA Cort, Project Lead TD Culp<sup>1</sup>

September 2013

Prepared for the U.S. Department of Energy under Contract DE-AC05-76RL01830

Pacific Northwest National Laboratory Richland, Washington 99352

<sup>1</sup> Birch Point Consulting, LLC, La Crosse, Wisconsin.

## **Summary**

The energy savings and cost effectiveness of installing low-emissivity (low-e) storm windows over existing windows in residential homes was evaluated across a broad range of U.S. climate zones. This work expands upon previous case studies, as well as modeling analysis performed in support of the state of Pennsylvania's efforts to add low-e storm windows to its list of "priority" Weatherization Assistance Program measures. Calculations of energy savings and cost effectiveness of low-e storm windows were conducted with two software platforms: the National Energy Audit Tool (NEAT) used by weatherization programs and RESFEN software used to compare the annual energy performance of different window options in single-family homes.

Both exterior and interior low-e storm windows/panels installed in conjunction with three different primary window types were evaluated in 22 different cities across all eight International Energy Conservation Code climate zones. Both regular low-e glass and solar control low-e glass, which decreases solar heat gain in addition to decreasing heat transfer through the glass, were included in the analysis. The NEAT analysis used 39 model homes, and the RESFEN analysis used 2 model homes.

Low-e storm windows were found to always be cost effective when installed over single-pane windows and double-pane, metal-framed windows in climate zones 3 through 8. The savings-to-investment ratio (SIR) ranged from 1.2 to 3.2 across the different locations analyzed. The average source energy savings ranged from 21 to 36% with a simple payback period of 3.7 to 10.2 years across climate zones 3 through 8. The use of solar-control, low-e storm windows is recommended in climate zone 3, and may also be considered in warmer parts of zone 4 where cooling degree days exceed heating degree days. The use of regular low-e storm windows is recommended in zones 4 through 8.

Low-e storm windows also were found to "qualify" as weatherization cost-effective measures (based on SIR greater than 1) and would therefore be recommended for installation over double-pane wood or vinyl-framed windows in climate zones 6 through 8, and in eastern parts of zone 5 where higher heating fuel costs exist. The SIR ranged from 1.1 to 1.9 across the different locations analyzed. The average source energy savings ranged from 16 to 19% with a simple payback period of 9 to 11 years.

All analyses were conducted assuming the model home was heated either with a natural gas furnace or electric heat pump depending on location. A sensitivity analysis was performed to examine the impact on the SIR when the assumed heating equipment, fuel sources, fuel costs, and baseline air leakage of the primary window were changed. When propane heating, electrical-resistance heating, or higher than average heating fuel costs are present, the SIR for installing a low-e storm windows increases. The SIR also is significantly higher for installations over primary windows with higher air leakage than what was assumed in this study (3 cfm/ft² for single-pane base windows, 1 cfm/ft² for double-pane base windows).

In addition, the incremental cost for using low-e glass versus clear glass was found to be cost effective in all climate zones over all window types with an average payback period of 2 to 4 years. This indicates that, when a homeowner chooses to install a storm window or interior window panel for reasons other than just energy savings (e.g., increased comfort, noise reduction, window protection, reduced air leakage, etc.), the use of low-e glass is recommended regardless of location.

# **Acronyms and Abbreviations**

AFUE annual fuel utilization efficiency

DOE U.S. Department of Energy

HSPF heating seasonal performance factor

IECC International Energy Conservation Code
LBNL Lawrence Berkeley National Laboratory

Low-e low emissivity
Mcf 1000 cubic feet

NEAT National Energy Audit Tool

RECS Residential Energy Consumption Survey

SEER seasonal energy efficiency ratio

SHGC solar heat gain coefficient
SIR savings-to-investment ratio

# Contents

| Sum  | mary   | iii |
|------|--|-----|
| Acre | onyms and Abbreviations  | v   |
| 1.0  | Introduction and Background  | 1   |
| 2.0  | NEAT Analysis of Low-e Storm Windows                                 | 3   |
|      | 2.1 NEAT Analysis and Methodology                                    | 3   |
|      | 2.2 NEAT Results   | 6   |
| 3.0  | RESFEN Analysis of Low-e Storm Windows                               | 11  |
|      | 3.1 RESFEN Analysis Background and Methodology                       | 11  |
|      | 3.2 RESFEN Results   | 14  |
| 4.0  | Conclusions and Recommendations Based on the NEAT and RESFEN Results | 23  |
| 5.0  | References   | 25  |
| App  | endix A – NEAT Calculation Results for Each City                     | A.1 |
| App  | endix B – RESFEN 6 Modeling Assumptions                              | B.1 |
| App  | endix C – RESFEN Calculation Results                                 | C.1 |

# **Figures**

| 2.1 | IECC Climate Zone Map  |
|-----|--|
| 2.2 | Effect of Natural Gas Price on the SIR of Low-e Storm Windows in Chicago   |
| 2.3 | Effect of Existing Window Air Tightness on the SIR of Low-e Storm Windows in Pittsburgh, Pennsylvania  |
| 4.1 | Overall Recommended Regions for the Use of Low-e Storm Windows Installed Over Single-Pane Windows and Double-Pane Metal-Framed Windows and the Location of Cities Included in this Analysis. |
| 4.2 | Overall Recommended Regions for Use of Low-e Storm Windows Installed Over Double-Pane, Wood/Vinyl-Framed Windows   |
|     |  |
|     | Tables   |
| 2.1 | Average SIR for Low-e Storm Windows Calculated by NEAT   |
| 2.2 | Percent Site Energy Savings, SIR, and Simple Payback for Low-e Storm Windows in a Representative Wood-Framed Home as Calculated by NEAT  |
| 3.1 | Properties for Storm Panels over Wood Base Windows   |
| 3.2 | Properties of Storm Panels over Metal Base Windows   |
| 3.3 | HVAC Source Energy Savings for Low-e Storm Windows and Panels as Calculated by RESFEN – Smaller Older 1-Story Home   |
| 3.4 | HVAC Energy Cost Savings of Exterior Low–e Storm Windows over Single–Pane Wood Windows as Calculated by RESFEN – Smaller Older 1–Story Home  |
| 3.5 | HVAC Source Energy Savings for Low-e Storm Windows and Panels as Calculated by RESFEN – Larger, Newer, Two-Story Home  |
| 3.6 | HVAC Energy Cost Savings of Exterior Low-e Storm Windows over Single-Pane Wood Windows as Calculated by RESFEN – Larger, Newer, Two-Story Home   |
| 3.7 | Overall Average Savings and Payback Period by Climate Zone. Results in climate zones 1–3 are for solar control low–e   |
| 3.8 | Effect of Different Mounting Methods for Installing Exterior Storm Windows over Metal-Framed, Double-Pane Windows in Boston, Massachusetts   |

## 1.0 Introduction and Background

This report describes work conducted in support of the Emerging Technologies Low-e Storm Windows Task 5.3: Create a Database of U.S. Climate-Based Analysis for Low-e Storm Windows. The scope of the overall effort is to develop a database of energy savings and cost effectiveness of low-emissivity (low-e) storm windows/panels in residential homes across a broad range of U.S. climates. The database expands upon previous calculations for Pennsylvania's Weatherization Assistance Program and storm window case studies to develop regionally based savings information for additional locations and climates. This report and calculations will be made publicly available through the Building America Solution Center and other outreach activities. This research can provide U.S. Department of Energy (DOE), national and regional utilities, and state weatherization programs with important data showing the potential energy savings low-e storm windows can contribute to energy retrofits in existing buildings.

A series of laboratory tests have proven that standard low-e storm windows save energy at the component level. The performance improvements have been validated with field tests and case studies supported by DOE's Emerging Technologies team. The combination of results from these laboratory and field tests, as well as the data collected as part of these previous efforts, helped inform the National Energy Audit Tool (NEAT) and RESFEN modeling assumptions used in this study. These case studies have been summarized in the report entitled *Task Plan in Support of Emerging Technology Task ET-WIN-PNNL-FY13-01\_5.1: Create a Database of U.S. Climate-Based Analysis for Low-e Storm Windows*, which was completed in an earlier phase of this overall modeling task (Hefty et. al. 2013).

In addition to the field tests and case studies, prior calculations of potential energy savings included a DOE-funded joint effort for the state of Pennsylvania using NEAT to support adding low-e storm windows to the state's weatherization measure priority list, and previous calculations performed by Birch Point Consulting under DOE Office of Energy Efficiency and Renewable Energy award #DE-EE0004015 using RESFEN software to estimate savings in different cities. Developed by Oak Ridge National Laboratory for DOE's Office of Weatherization and Intergovernmental Programs, NEAT is the primary approved software designated for state weatherization programs. RESFEN is a DOE-based building simulation program developed by Lawrence Berkeley National Laboratory (LBNL) that was specifically designed to compare the annual energy performance of different fenestration options in single-family homes, and it is used as the basis of the ENERGY STAR® program for windows, doors, and skylights. It is valuable to have calculations from both platforms to address the different audiences that will use the data (utilities, weatherization programs, federal energy-efficiency programs, consumers, etc.). Gaps in both existing data sets were identified, and additional NEAT and RESFEN analyses were proposed, specifically adding cities to cover additional U.S. climate zones, and including data for low-e storm windows installed over additional primary window types (single or double pane, wood or metal frame, etc.) The purpose of this database effort and documentation report is to fill in these gaps by modeling low-e storm window performance over a broad range of climate zones with a variety of baseline model home characteristics. This report provides a summary of the final results of the NEAT and RESFEN calculations, including general observations and recommendations regarding the use of low-e storm windows and panels.

\_

<sup>&</sup>lt;sup>1</sup> Joint effort between DOE's BTP and DOE's Office of Weatherization and Intergovernmental Programs (OWIP), Pennsylvania's Department of Community and Economic Development, LBNL, Energetics, and Birch Point Consulting.

## 2.0 NEAT Analysis of Low-e Storm Windows

During 2010 and 2011, an analysis was conducted to help the state of Pennsylvania determine the energy savings potential of adding the installation of low-e storm windows to its weatherization measure priority list. This was a joint effort of DOE, the Pennsylvania Department of Community and Economic Development, Energetics, LBNL, and Birch Point Consulting.

The prior NEAT analysis included four cities across Pennsylvania, 37 model home types, and two primary window types (single-pane wood frame, and double-pane metal frame). The 37 model homes were selected from a data set, prepared by Dalhoff Associates with the intention of covering a wide range of older existing housing commonly encountered in weatherization programs. Different insulation scenarios were included for the following home types: detached masonry, semi-detached masonry, rowhouse masonry, detached wood frame (e.g., slab, crawl space, unconditioned basement, conditioned basement, etc.), cape-cod wood frame, semi-detached wood frame, row-house wood frame, and exposed floor (Dalhoff 2010).

The primary result of the NEAT analysis that examined a particular weatherization measure comes in the form of savings-to-investment ratio (SIR), because a SIR greater than 1 is required to qualify as a weatherization measure using state and federal funding. NEAT also can be used to provide estimates of site energy savings, rankings relative to other weatherization measures, and the maximum cost that a weatherization measure could be while still producing a SIR greater than 1. Simple payback also can be calculated; although, in the case of storm windows, only part of the air-infiltration savings is captured in the storm window listing within the NEAT<sup>1</sup> calculation results (provided in Appendix A). Therefore, either a portion of the overall home air-infiltration savings also needs to be credited to storm windows in the calculation, or the payback period will be somewhat overstated.

The analysis for Pennsylvania showed that low-e storm windows would qualify as a cost-effective weatherization measure. The SIR values ranged from 1.4 to 2.2 when low-e storm windows were used over single-pane, wood-framed windows and ranged from 1.3 to 2.1 when they were used over double-pane, metal-framed windows. As a result, the state of Pennsylvania added low-e storm windows to its weatherization measure selection priority list for single-family homes in 2010 (Zalis et al. 2010; Krigger 2011).

### 2.1 NEAT Analysis and Methodology

The NEAT analysis presented in this report expands on the previous weatherization work to cover more locations in different states and climates. As outlined below, the same general methodology used in for Pennsylvania was used for this expanded coverage.

\_

<sup>&</sup>lt;sup>1</sup> NEAT simulates heating, cooling, and air infiltration reductions separately and attributes whole home reductions in air infiltration to a number of different air-sealing weatherization measures. Based on case studies summarized in Hefty et. al. (2013), whole home air leakage can be reduced by an average of 10 to 15% just by adding storm windows, and when combined with other weatherization measures, the whole home leakage is reduced by 20 to 40%. Therefore, assigning an estimate of one-third of air-infiltration reductions (which was assumed in this study) to be attributed to storm windows most likely underestimates the full infiltration benefits of storm windows and would be considered a conservative attribution.

- NEAT calculations were run for a total of 20 cities across seven International Energy Conservation Code (IECC) climate zones (no weather files were available in NEAT format for climate zone 8, which is only found in northern Alaska). Figure 2.1 is a map of IECC climate zones and the locations of cities included in this analysis. The cities are listed out in Table 2.1 and Table 2.2.
- Low-e storm windows were evaluated based on installations of three different primary window types (i.e., single-pane wood or vinyl frame, double-pane wood or vinyl frame, and double-pane metal frame, all with clear glass). This adds clear double-pane wood and double-pane vinyl windows to the windows addressed in the Pennsylvania NEAT analysis. Single-pane metal windows were not included, but because the SIR will always be higher, they will be qualified as weatherization measures where single-pane wood/vinyl windows or double-pane metal windows are used. This is because the single-pane, metal-framed window will have the worst U-factor (i.e., heat transfer coefficient) of all the primary window types, and therefore, the relative improvement in U-factor and energy performance from adding a low-e storm window will be even higher than with the other primary window types.




Figure 2.1. IECC Climate Zone Map

- The method used in this analysis was different from the Pennsylvania NEAT analysis as follows:
  - The latest NEAT version (i.e., 8.9.0.5 released in February 2012) was used. This version includes updated fuel escalation rates and updated prices for other weatherization measures.
  - Two additional homes were added to the data set that was used in the Pennsylvania NEAT analysis (Dalhoff 2010) to capture a broader range of insulation levels. This resulted in total of 39 model homes, where the two additional homes are assumed to have insulation throughout the

- home (R11 walls, R19 attic, R11 floor) and one is characterized as a wood-frame, vented crawl space home, while the other is a masonry home.
- For the set of homes used in the Pennsylvania NEAT analysis (Dalhoff 2010), only one-quarter of the floor space was assumed to be air conditioned using less efficient room/window air-conditioner units, and no air conditioning was used in the rest of the home. These characteristics are typical of weatherization homes in Pennsylvania and many other locations, but data from the DOE Residential Energy Consumption Survey (RECS) show that it is more common to have central air conditioning in the Midwest, South-Central, and Southern regions (DOE-EIA 2009). Therefore, the homes were modified to include a central air conditioner (SEER 8) in climate zones 1 through 3 as well as in the warmer zone 4 locations where cooling degree days exceed heating degree days (i.e., Raleigh, North Carolina, Washington, D.C.).
- RECS data also show that heat pumps are more common than natural gas furnaces in southern locations, so the homes were modified to use a heat pump with 6.8 HSPF in climate zones 1 and 2 and certain zone 3 locations rather than an 80% AFUE natural gas furnace (DOE-EIA 2009).
- The natural gas and electricity prices used were based on location using 2012 state average prices taken from the DOE Energy Information Administration *Natural Gas Monthly and Electric Power Monthly* reports (DOE-EIA 2013).
- The assumed storm window properties are described below:
  - Low-e Glass. Storm window properties were based on the characteristics of commercially available low-e storm windows. Standard low-e (0.157 emissivity, 0.75 center-of-glass solar heat gain coefficient [SHGC]) was evaluated in all zones. Solar-control low-e (0.166 emissivity, 0.54 center-of-glass SHGC) was evaluated in climate zones 1 through 3 and certain warmer locations in zone 4 where cooling degree days exceed heating degree days (Raleigh, North Carolina, and Washington D.C.).
  - Product Cost. Product and installation costs were primarily based on analysis performed as part of the Pennsylvania NEAT study (Dalhoff 2010). For this analysis, material costs were assumed to be \$7.85/ft² of window area, plus an average of \$30 per window was assumed for installation expenses. Do-it-yourself installations (which account for 80% of installations) cost only ~\$2 per window, whereas contractor installation can cost \$60 per window but will vary depending on location. A weighted average cost of \$14 per window could have been used based on this information (the Pennsylvania analysis assumed \$15 per window installation costs), but because of the high variability, a cost of \$30 was used to be conservative. If the lower installation cost is thought to be more applicable (e.g., for a utility program in which consumers will primarily do self-installation), the SIR results will further increase.
  - Lifetime. Twenty years for this study. Fifteen years was used initially in the Pennsylvania analysis, but based on updated information including manufacturer warranties, 20 years is more accurate (Cort 2013).

In addition to the main calculations, some additional runs were made to explore the impact of natural gas fuel pricing and different primary window air leakage levels. Overall, approximately 4240 model runs were performed.

#### 2.2 NEAT Results

The average SIR for using low-e storm windows installed over different primary window types in different cities/climate zones is shown in Table 2.1. NEAT SIR output is only provided for cities with SIRs greater than 1. Each value is the average SIR across the 39 different homes for that particular location and window type. The detailed SIR results for each city and home type are provided in Appendix A. The site energy percentage savings and simple payback period for a representative home are shown in Sensitivity: A sensitivity analysis was performed based on independent changes in single variables. In general, the largest variables affecting whether low-e storm windows are cost effective are location (climate), heating fuel cost, existing window tightness, and storm window cost. Factors that have less effect include home type, window area, and orientation.

Heating fuel price has a large impact on SIR—as much as location/climate, and more than home type. This is particularly noticeable in the Midwest and Rocky Mountains regions where the cost of natural gas has decreased in recent years and is much cheaper than in the Northeast and Southeast. State average natural gas prices vary significantly from approximately \$8 to \$16/Mcf (DOE-EIA 2013). As an example, Figure 2.2 shows the SIR as a function of natural gas price for low-e storm windows in one home type in Chicago. At the current low cost of \$8.22/Mcf, the SIR is 1.4, but it increases by approximately 0.3 for every \$2/Mcf increase in price (with a corresponding decrease in payback period).

Table 2.2, although simple payback should be viewed with a cautionary note. In the case of storm windows, only part of the air-infiltration savings are captured under the storm window listing within the NEAT results, so either a portion of the overall home air-infiltration savings needs to also be credited to storm windows in the calculation, or the payback period will be somewhat overstated. An estimate of the payback including the additional air-infiltration savings is also included.

The following general points and trends were observed:

- In climate zones 3 through 8, low-e storm windows are always cost effective (SIR >1) when installed over single-pane windows and double-pane, metal-framed windows. The SIR values range from 1.2 to 3.2 across the different locations analyzed.
- Low-e storm windows also can be cost effective when installed over double-pane wood or vinyl-framed windows in many locations of climate zones 3 through 8, but SIR values depends on the climate, local fuel cost, and storm window glass type. The SIR values range from 1.1 to 1.9 across the different locations analyzed.
- Under the following conditions, the SIR increases:
  - In colder climates

By using solar-control, low-e glass in warmer climates (zone 3 as well as warmer cities in zone 4 where cooling degree days exceed heating degree days)

- In locations with higher heating fuel costs
- Over existing windows that exhibit the highest air leakage.

<sup>1</sup> More detail on the structure and content of the NEAT can be found at the Weatherization Technical Assistance Center (<a href="http://www.waptac.org/">http://www.waptac.org/</a>) and in related manuals (Gettings 2006).

- In climate zones 1 and 2, storm windows with solar-control, low-e glass can be cost effective, although pragmatically, other low-cost, solar-control measures like solar screens and films will have higher SIR values.
- The analysis was performed with either a natural-gas furnace or electrical heat pump depending on location. For homes using propane or electrical resistance heating, the SIR of low-e storm windows will be even higher because the effective heating fuel cost and savings from using low-e storm windows will be higher. The reverse is also true; households with more efficient heating equipment and low heating fuel costs would likely have a relatively lower SIR resulting from storm window installations.

Table 2.1. Average SIR for Low-e Storm Windows Calculated by NEAT

Average SIR of Low-e Storm Windows Used Over Different Primary Window Types Solar Control Low-e Glass Standard Low-e Glass Single-Single-Pane, Double-Double-Pane, Pane, Double-Double-Pane, Wood- or Wood- or Wood- or Pane. Wood or Pane. Vinyl-Vinyl-Vinyl-Metal-Vinyl-Metal-Framed Climate Framed Framed Framed Framed Framed Window Window Window Zone City, State Window Window Window 7 Duluth, MN 1.3 2.1 2.0 6 A 3.2 1.9 Burlington, VT 3.1 6 A Minneapolis, MN 1.6 1.6 1.2 5 A Boston, MA 2.3 2.2 1.5 5 A Rochester, NY 2.8 2.6 1.8 5 A Pittsburgh, PA 1.8 1.7 1.2 5 A Chicago, IL 1.4 1.4 5 B Denver, CO 1.3 1.3 --5 B Boise, ID 1.2 1.3 4 A New York, NY 2.0 2.1 1.4 4 A Washington, DC 1.5 1.5 1.1 1.6 1.6 1.2 4 A Raleigh, NC 1.2 1.2 1.3 1.3 1.0 4 A Kansas City, MO  $1.5(1.7)^{(a)}$  $1.4(1.7)^{(a)}$  $1.0(1.2)^{(a)}$ 4 C Seattle, WA 1.4 1.4 3 A 1.2 1.2 Atlanta, GA 1.4 1.3 1.2 3 A Dallas, TX 1.3 1.5 1.5 1.3 1.2 2 A Jacksonville, FL 1.2 1.2 2 A Houston, TX 1.2 1.2 2 B Phoenix, AZ --\_\_ ----1.2 1 A Miami, FL 1.2 1.1

Gray cells not evaluated.

• Sensitivity: A sensitivity analysis was performed based on independent changes in single variables. In general, the largest variables affecting whether low-e storm windows are cost effective are location

<sup>--</sup> = SIR <1 under the assumed fuel and product costs.

<sup>(</sup>a) Second value for Kansas City shows whole home air conditioned versus one-quarter of floor area air conditioned.

(climate), heating fuel cost, existing window tightness, and storm window cost. Factors that have less effect include home type, window area, and orientation.

- Heating fuel price has a large impact on SIR—as much as location/climate, and more than home type. This is particularly noticeable in the Midwest and Rocky Mountains regions where the cost of natural gas has decreased in recent years and is much cheaper than in the Northeast and Southeast. State average natural gas prices vary significantly from approximately \$8 to \$16/Mcf (DOE-EIA 2013). As an example, Figure 2.2 shows the SIR as a function of natural gas price for low-e storm windows in one home type in Chicago. At the current low cost of \$8.22/Mcf, the SIR is 1.4, but it increases by approximately 0.3 for every \$2/Mcf increase in price (with a corresponding decrease in payback period).

**Table 2.2**. Percent Site Energy Savings, SIR, and Simple Payback for Low-e Storm Windows in a Representative Wood-Framed Home (Home code WFVC6<sup>1</sup>) as Calculated by NEAT

|                 |                  |                             |                          | me from Adding<br>d crawlspace, R1           |                             |                          |  |
|-----------------|------------------|-----------------------------|--------------------------|--|-----------------------------|--------------------------|--|
| -               |                  |                             | dard Low-e<br>Pane Wood/ | Glass<br>Vinyl Window                        |                             | Control Low<br>Pane Wood | v-e Glass<br>Vinyl Window                    |
| Climate<br>Zone | Location         | % Site<br>Energy<br>Savings | SIR                      | Simple<br>Payback in<br>Years <sup>(a)</sup> | % Site<br>Energy<br>Savings | SIR                      | Simple<br>Payback in<br>Years <sup>(a)</sup> |
| 7               | Duluth, MN       | 19%                         | 2.1                      | 7.3 (5.7)                                    |                             |                          |  |
| 6 A             | Burlington, VT   | 19%                         | 3.2                      | 4.8 (3.8)                                    |                             |                          |  |
| 6 A             | Minneapolis, MN  | 19%                         | 1.6                      | 9.4 (7.3)                                    |                             |                          |  |
| 5 A             | Boston, MA       | 21%                         | 2.3                      | 6.8 (5.2)                                    |                             |                          |  |
| 5 A             | Rochester, NY    | 20%                         | 2.8                      | 5.6 (4.4)                                    |                             |                          |  |
| 5 A             | Pittsburgh, PA   | 19%                         | 1.8                      | 8.3 (6.6)                                    |                             |                          |  |
| 5 A             | Chicago, IL      | 20%                         | 1.4                      | 11.6 (8.9)                                   |                             |                          |  |
| 5 B             | Denver, CO       | 18%                         | 1.3                      | 13.2 (9.8)                                   |                             |                          |  |
| 5 B             | Boise, ID        | 18%                         | 1.3                      | 12.3 (9.2)                                   |                             |                          |  |
| 4 A             | New York, NY     | 21%                         | 2.1                      | 7.1 (5.5)                                    |                             |                          |  |
| 4 A             | Washington, DC   | 18%                         | 1.5                      | 9.9 (7.8)                                    | 16%                         | 1.6                      | 9.3 (7.4)                                    |
| 4 A             | Raleigh, NC      | 16%                         | 1.2                      | 13.5 (10.6)                                  | 16%                         | 1.3                      | 12.3 (9.9)                                   |
| 4 A             | Kansas City, MO  | 18%                         | 1.7                      | 8.9 (7.1)                                    |                             |                          |  |
| 4 C             | Seattle, WA      | 22%                         | 1.4                      | 10.7 (8.4)                                   |                             |                          |  |
| 3 A             | Atlanta, GA      | 16%                         | 1.2                      | 12.4 (9.7)                                   | 16%                         | 1.4                      | 11.2 (9.0)                                   |
| 3 A             | Dallas, TX       | 13%                         | 1.3                      | 10.3 (8.1)                                   | 16%                         | 1.5                      | 8.5 (6.9)                                    |
| 2 A             | Jacksonville, FL |                             |                          |  | 12%                         | 1.2                      | 9.6 (7.7)                                    |
| 2 A             | Houston, TX      |                             |                          |  | 12%                         | 1.2                      | 9.5 (7.3)                                    |
| 2 B             | Phoenix, AZ      |                             |                          |  |                             |                          |  |
| 1 A             | Miami, FL        |                             |                          |  | 10%                         | 1.2                      | 9.7 (7.0)                                    |

Payback will be shorter for leakier primary windows, higher fuel costs, or propane and electrical resistance heating. -- = SIR <1 under the assumed fuel and product costs

Gray cells not evaluated.

(a) Second payback value in parentheses is if one-third of the air-infiltration cost savings is assigned to storm windows. This

8

Construction and product cos

<sup>&</sup>lt;sup>1</sup> WFVCS6 is the code for a wood-framed home with a vented crawl space.





Figure 2.2. Effect of Natural Gas Price on the SIR of Low-e Storm Windows in Chicago

The air tightness of the existing window also has a large impact on energy savings and whether the measure is cost effective. The leakier the existing window, the greater the SIR of adding lowe storm windows. NEAT defines five levels of air tightness for the existing window (very tight, tight, medium, loose, and very loose)¹ and provides descriptions to help the auditor assign the appropriate level (see Figure 2.3). The NEAT analysis was performed with a medium tightness, which should be conservative for most existing homes based on the NEAT definition. However, the SIR will increase (and the payback period will decrease) for existing windows that are leakier. As an example, Figure 2.3 shows the SIR for low-e storm windows as a function of existing window air tightness in one home type in Pittsburgh, Pennsylvania. With loose existing windows, which would not be uncommon in older homes, the SIR can increase by 0.8, and the payback period can decrease by over 2 years.

\_

<sup>&</sup>lt;sup>1</sup> Although specific measurable parameters (e.g., cfm/s.f.) are not associated with NEAT categories for air tightness, qualitative defintions are provided for auditing purposes. For example, "medium" tightness is described as "typical of older windows found in older homes." Deteriorating weatherstripping would be present, but no visible gaps. More information can be found in "Window Leakiness Guidelines" (ORNL 2009).



**Figure 2.3**. Effect of Existing Window Air Tightness on the SIR of Low-e Storm Windows in Pittsburgh, Pennsylvania

- The SIR of low-e storm windows does not heavily depend on home type. The percent energy savings will vary more based on the specific home, but the SIR is less sensitive. As seen in Appendix A, the SIR typically varies by only ±0.2 across all 39 home types for a given window type and city.
- Although counter-intuitive, window area does not affect the SIR significantly. Window area obviously affects the overall load, energy savings, and storm window cost, but because the cost and energy savings scale similarly with square footage, the SIR does not change much. When the window area was doubled in the WFVC6 home in Pittsburgh, the energy savings increased from 19 to 33% of the total home site energy use, but the SIR only changed from 1.9 to 1.8.
- The overall cost effectiveness does not vary dramatically with *orientation*. For the WFVC6 home in Pittsburgh, the SIR remained at 1.9 whether the home was oriented north/south (67% of glazing on the north and south) or oriented east/west. The cost effectiveness of windows on individual sides does vary because of the different beneficial or detrimental role of solar gain on the south versus west/east sides, but the overall SIR does not vary dramatically. (For example, the SIR for solar control low-e storm windows will be higher on the west and east sides than on the south side.)

Overall conclusions and recommendations based on both the NEAT and RESFEN analysis results are provided in Chapter 4.0.

### 3.0 RESFEN Analysis of Low-e Storm Windows

RESFEN is the standard software program used for calcuting the impact of windows on heating and cooling costs for new and existing residential homes. RESFEN allows you to enter housing characteristics (including window characteristics) and location information to represent the house type and climate zone of interest. RESFEN is frequently employed by utility energy-efficiency programs and ENERGY STAR to determine whether or not the residential fenestration performance of a given product is sufficient to meet program requirements.

### 3.1 RESFEN Analysis Background and Methodology

Birch Point Consulting performed previous unpublished RESFEN calculations in 2012 for two home types in 30 different cities across seven IECC climate zones. The two home types included an older, smaller, one-story 1800-ft² home, and a larger, newer, two-story 2300-ft² home. Exterior and interior low-e storm windows installed over one primary window type (single-pane, wood-frame window) were evaluated. In addition, some extra calculations were added in three cities for interior and exterior low-e storm windows installed over both single- and double-pane, wood- and metal-frame windows, and compared to ENERGY STAR® replacement windows.

Because RESFEN is commonly employed as an evaluation tool for energy-efficiency programs, this study expands and refines previous RESFEN calculations to examine low-e storm window performance using multiple house types and assuming a broad range of climate zones to help inform energy-efficiency programs of low-e storm window performance throughout the U.S. The primary output from the RESFEN analysis includes the percentage of whole house energy savings derived from installation of low-e storm windows, along with heating and cooling energy and cost savings. The payback period also can be calculated, but again, the simple payback should be viewed with a cautionary note, as it is not clear that the full effect of reduced air infiltration attributable to storm windows is accounted for in RESFEN.<sup>1</sup>

As part of this study, the RESFEN modeling expands upon previous calculations to cover all U.S. climate zones, add more primary window configurations, use updated U-factor and SHGC values for different storm window and primary window combinations, and update the calculation methodology to be consistent with that used in the ENERGY STAR® program for windows, doors, and skylights. The RESFEN analysis was conducted as outlined below.

- RESFEN calculations were run for the same cities as in the NEAT analysis shown in Figure 2.1, plus two additional cities in climate zones 7 and 8 in Alaska (Anchorage and Fairbanks). This is a total of 22 cities across all eight IECC climate zones.
- RESFEN version 6.0.16 was used, whereas the prior analysis used RESFEN version 5. RESFEN 6 is the version used to help establish criteria for the ENERGY STAR® program for windows, doors, and skylights. Several assumptions for the baseline building were updated as shown in Appendix B, although the general conclusions for relative window comparisons do not change substantially from version 5.

11

-

<sup>&</sup>lt;sup>1</sup> As with the NEAT analysis, it appears that default assumptions built into RESFEN may under estimate the infiltration reductions attributable to the installation of storm windows over primary windows.

- Two homes were modeled: a smaller, older, one-story 1700 ft<sup>2</sup> home, and a larger, newer, two-story 2800 ft<sup>2</sup> home. These two homes also are used in the analysis for the ENERGY STAR® program. The older home has minimal insulation, and the newer home is insulated to the 2006 IECC requirements. Details are shown in Appendix B for the one-story, wood-framed home representative of existing construction and the two-story, wood-framed home representative of new construction.
- Natural-gas heating was used in most cities, except a heat pump was used in climate zones 1 and 2 and certain zone 3 locations where RECS data show that heat pumps are more dominant (DOE-EIA 2009). Central air conditioning cooling was included in all locations.
- The natural-gas and electricity prices used were based on 2012 state average prices taken from the DOE Energy Information Administration Natural Gas Monthly and Electric Power Monthly reports (DOE-EIA 2013).
- The window area was assumed to be 15% of equally distributed floor area, which is the same as the analysis for the ENERGY STAR® program. This is 255 ft² for the smaller older one-story home, and 420 ft² for the larger newer two-story home, or approximately 17 and 28 windows, respectively.
- Both exterior and interior low-e storm windows and panels were evaluated when installed over three different primary window types (single-pane wood frame, double-pane wood frame, and double-pane metal frame, all with clear glass). Single-pane metal windows were not included, but will be qualified as weatherization measures for cases in which single-pane wood/vinyl windows or double-pane metal windows are used, because the energy savings and cost effectiveness will always be higher. This is because the single-pane, metal-framed window will have the worst U-factor (heat transfer coefficient) of all the primary window types; therefore, the relative improvement in U-factor and energy performance from adding a low-e storm window will be even higher than with the other primary window types.
- Standard low-e glass was modeled in all locations. In addition, solar-control low-e glass also was modeled in southern locations (climate zones 1 through 3, and certain warmer zone 4 locations where cooling degree days exceed heating degree days). The SHGC of the solar control low-e glass was 27% lower than the standard low-e glass. Solar-control low-e storm windows are designed for exterior application, so interior panels with solar-control low-e windows were not modeled. Clear glass storm windows also were modeled for comparison.
- To determine the U-factor and SHGC properties for use in the RESFEN analysis, an independent National Fenestration Rating Council-accredited simulation testing laboratory (Architectural Testing, Inc.) conducted detailed calculations of exterior and interior low-e panels installed over various primary windows using THERM and WINDOW software from LBNL (part of DOE Project DE-EE0004015). The resulting U-factor, SHGC, and Vermont (VT) numbers are shown in Table 3.1 and Table 3.2. This includes many combinations and window types, so the subset in **bold text** within the tables indicates that these window types were used with the RESFEN analysis.
- The most accurate method for modeling windows in RESFEN is to import the detailed solar angle dependent properties from WINDOW, rather than just inputting the simple U-factor and SHGC numbers. However, RESFEN and its underlying DOE2.1E software can only use generic frames rather than the detailed frame mounting modeled by Architectural Testing Inc. Therefore, after consultation with the RESFEN developers at LBNL, the window and solar angle properties were imported by creating windows with generic frames and adjusting the frame properties until the whole window U-factor and SHGC matched the same values shown in Table 3.1 and Table 3.2.

- Air leakage was modeled as 3 cfm/ft<sup>2</sup> for single-pane base windows, 1 cfm/ft<sup>2</sup> for double-pane base windows, 0.3 cfm/ft<sup>2</sup> with exterior storm windows installed, and 0.1 cfm/ft<sup>2</sup> with interior panels installed (Drumheller 2007).<sup>1</sup>
- For simple payback period calculations, the same product cost data was used as in the NEAT analysis. This is a product cost of \$7.85/ ft² of window area, plus \$30 per window for installation. To calculate the incremental payback period of low-e glass versus clear glass, a product cost of \$6.85/ ft² of window area was used for clear glass storm windows and panels, or 13% lower than the low-e storm window. The installation cost was the same (Cort 2013).

Overall, approximately 950 simulations were performed.

**Table 3.1**. Properties for Storm Panels over Wood Base Windows (window types in bold text were used as inputs in RESFEN modeling)

| Base Window                     | Storm Type                    | <b>U-Factor</b> | SHGC  | VT   |
|---------------------------------|-------------------------------|-----------------|---|------|
|                                 |                               | 0.88            | 0.61  | 0.66 |
|                                 | Clear, Exterior               | 0.47            | 0.54  | 0.57 |
| Wood Double Hung, Single Glazed | Clear, Interior               | 0.46            | 0.61  | 0.59 |
|                                 | Low-e, Exterior               | 0.36            | 0.46  | 0.52 |
|                                 | Low-e, Interior               | 0.34            | 0.61 0.54 0.54 0.54 0.46 0.50 0.57 0.49 0.51 0.42 0.47 0.64 0.58 0.56 0.50 0.52 0.60 0.53 0.54 0.46 | 0.54 |
| Wood Double Hung, Double Glazed |                               | 0.51            | 0.57  | 0.61 |
|                                 | Clear, Exterior               | 0.34            | 0.49  | 0.53 |
|                                 | Clear, Interior               | 0.32            | 0.51  | 0.55 |
|                                 | Low-e, Exterior               | 0.28            | 0.42  | 0.48 |
|                                 | Low-e, Interior               | 0.26            | 0.61 0.54 0.54 0.54 0.46 0.50 0.57 0.49 0.51 0.42 0.47 0.64 0.58 0.56 0.50 0.52 0.60 0.53 0.54 0.46 | 0.50 |
|                                 |                               | 0.87            | 0.64  | 0.69 |
|                                 | Clear, Exterior               | 0.46            | 0.58  | 0.62 |
| Wood Fixed, Single Glazed       | Clear, Interior               | 0.45            | 0.56  | 0.62 |
|                                 | Clear, Exterior   0.47   0.54 | 0.50            | 0.56  |      |
|                                 | Low-e, Interior               | 0.34            | 0.61 0.54 0.54 0.54 0.46 0.50 0.57 0.49 0.51 0.42 0.47 0.64 0.58 0.56 0.50 0.52 0.60 0.53 0.54 0.46 | 0.57 |
|                                 |                               | 0.47            | 0.60  | 0.64 |
| Vood Double Hung, Double Glazed | Clear, Exterior               | 0.32            | 0.53  | 0.57 |
|                                 | Clear, Interior               | 0.32            | 0.54  | 0.58 |
|                                 | Low-e, Exterior               | 0.27            | 0.46  | 0.52 |
|                                 | Low-e, Interior               | 0.25            | 0.61 0.54 0.54 0.54 0.46 0.50 0.57 0.49 0.51 0.42 0.47 0.64 0.58 0.56 0.50 0.52 0.60 0.53 0.54 0.46 | 0.53 |

\_

<sup>&</sup>lt;sup>1</sup> Specific air-tightness parameter assumptions are based on previous case studies, which measured cfm/s.f. results documented in Drumheller 2007.

**Table 3.2**. Properties of Storm Panels over Metal Base Windows (window types in bold text were used as inputs in RESFEN modeling)

| Base Window  | Storm Type      | <b>U-Factor</b> | SHGC | VT   |
|--|-----------------|-----------------|------|------|
| Aluminum Double Hung, Single Glazed  |                 | 1.12            | 0.61 | 0.65 |
| Worst case mounting  | Clear, Exterior | 0.67            | 0.56 | 0.58 |
| Thermally broken mounting (recommended)  | Clear, Exterior | 0.58            | 0.56 | 0.59 |
|  | Clear, Interior | 0.53            | 0.53 | 0.59 |
| Worst case mounting  | Low-e, Exterior | 0.57            | 0.47 | 0.53 |
| Thermally broken mounting (recommended)  | Low-e, Exterior | 0.44            | 0.48 | 0.54 |
|  | Low-e, Interior | 0.41            | 0.50 | 0.54 |
| Aluminum Double Hung, Double Glazed  |                 | 0.75            | 0.58 | 0.60 |
| Worst case mounting  | Clear, Exterior | 0.55            | 0.51 | 0.54 |
| Thermally broken mounting (recommended)  | Clear, Exterior | 0.45            | 0.52 | 0.55 |
|  | Clear, Interior | 0.41            | 0.51 | 0.55 |
| Worst case mounting  | Low-e, Exterior | 0.49            | 0.44 | 0.49 |
| Thermally broken mounting (recommended)  | Low-e, Exterior | 0.36            | 0.44 | 0.50 |
|  | Low-e, Interior | 0.32            | 0.47 | 0.50 |
| Aluminum Fixed, Single Glazed  |                 | 1.06            | 0.72 | 0.77 |
| Worst case mounting  | Clear, Exterior | 0.62            | 0.59 | 0.62 |
| Thermally broken mounting (recommended)  | Clear, Exterior | 0.55            | 0.61 | 0.65 |
|  | Clear, Interior | 0.51            | 0.60 | 0.66 |
| Worst case mounting  | Low-e, Exterior | 0.51            | 0.50 | 0.57 |
| Thermally broken mounting (recommended)  | Low-e, Exterior | 0.42            | 0.52 | 0.59 |
|  | Low-e, Interior | 0.38            | 0.56 | 0.60 |
| Aluminum Fixed, Double Glazed  |                 | 0.62            | 0.67 | 0.71 |
| Worst case mounting  | Clear, Exterior | 0.47            | 0.54 | 0.58 |
| Thermally broken mounting (recommended)  | Clear, Exterior | 0.40            | 0.56 | 0.60 |
|  | Clear, Interior | 0.36            | 0.57 | 0.61 |
| Worst case mounting  | Low-e, Exterior | 0.42            | 0.47 | 0.52 |
|  | Law a Entarion  | 0.33            | 0.48 | 0.55 |
| Thermally broken mounting (recommended Worst case mounting)  Thermally broken mounting (recommended Worst case mounting) | Low-e, Exterior | 0.55            | 0.40 | 0.55 |

#### 3.2 RESFEN Results

Table 3.3 through Table 3.6 show the energy savings results for using low-e storm windows installed over different primary window types in different cities/climate zones. Table 3.3 and Table 3.5 show the source energy savings for using low-e storm windows in the smaller, older, one-story home and the larger, newer, two-story home, respectively. Similarly, for the smaller, older, one-story home and the larger, newer, two-story home, Table 3.4 and Table 3.6 show the energy cost savings, simple payback period for the total storm window, and incremental simple payback period for using a low-e storm window versus a clear storm window. The detailed results for each city and home type are included in Appendix C.

Table 3.7 provides a summary of the overall average source energy savings and simple payback periods for each climate zone. The results are averaged over both home types, all cities modeled in each climate zone, and both interior and exterior low-e panels.

**Table 3.3**. HVAC Source Energy Savings for Low-e Storm Windows and Panels as Calculated by RESFEN – Smaller Older 1-Story Home

HVAC Source Energy Savings of Low-e Storm Windows Used Over Different Primary Window Types in Smaller, Older, One-Story Home

|                 |                  | •                | dard Low-e       |                  | Solar-Control, Low-e Glass |                  |                  |
|-----------------|------------------|------------------|------------------|------------------|----------------------------|------------------|------------------|
|                 |                  |                  | Double-          |                  | Single-                    | Double-          |                  |
|                 |                  | Single-Pane,     | Pane,            | Double-Pane,     | Pane,                      | Pane,            | Double-Pane,     |
| ~*·             |                  | Wood-            | Metal-           | Wood-            | Wood-                      | Metal-           | Wood-            |
| Climate<br>Zone | City, State      | Framed<br>Window | Framed<br>Window | Framed<br>Window | Framed<br>Window           | Framed<br>Window | Framed<br>Window |
|                 | •                |                  |                  |                  | Willdow                    | Willdow          | Willdow          |
| 8               | Fairbanks, AK    | 18–20%           | 12–13%           | 8–10%            |                            |                  |                  |
| 7               | Anchorage, AK    | 23–25%           | 15–17%           | 10–12%           |                            |                  |                  |
| 7               | Duluth, MN       | 24–26%           | 16–17%           | 10–13%           |                            |                  |                  |
| 6 A             | Burlington, VT   | 25–28%           | 17–18%           | 11-14%           |                            |                  |                  |
| 6 A             | Minneapolis, MN  | 25-28%           | 16-18%           | 12–13%           |                            |                  |                  |
| 5 A             | Boston, MA       | 28-30%           | 18-20%           | 12-15%           |                            |                  |                  |
| 5 A             | Rochester, NY    | 24–26%           | 16-17%           | 11-13%           |                            |                  |                  |
| 5 A             | Pittsburgh, PA   | 24–26%           | 16-17%           | 11-13%           |                            |                  |                  |
| 5 A             | Chicago, IL      | 25-27%           | 17-18%           | 12-13%           |                            |                  |                  |
| 5 B             | Denver, CO       | 24-27%           | 17-18%           | 11-13%           |                            |                  |                  |
| 5 B             | Boise, ID        | 25-27%           | 17-18%           | 12-13%           |                            |                  |                  |
| 4 A             | New York, NY     | 25-27%           | 16-18%           | 11-13%           |                            |                  |                  |
| 4 A             | Washington, DC   | 24–26%           | 16–17%           | 11-13%           | 22%                        | 14%              | 10%              |
| 4 A             | Raleigh, NC      | 19–21%           | 13-14%           | 9–10%            | 19%                        | 12%              | 8%               |
| 4 A             | Kansas City, MO  | 26–28%           | 17–19%           | 13-14%           | 26%                        | 16%              | 12%              |
| 4 C             | Seattle, WA      | 29–32%           | 20-22%           | 14–16%           |                            |                  |                  |
| 3 A             | Atlanta, GA      | 24–26%           | 16-17%           | 12-13%           | 25%                        | 17%              | 13%              |
| 3 A             | Dallas, TX:      |                  |                  |                  |                            |                  |                  |
|                 | Furnace          | 25%              | 16%              | 13%              | 26%                        | 18%              | 15%              |
|                 | Heat pump        | 21–22%           | 13–14%           | 12%              | 24%                        | 16%              | 15%              |
| 2 A             | Jacksonville, FL | 18–17%           | 11%              | 11–9%            | 23%                        | 16%              | 15%              |
| 2 A             | Houston, TX:     |                  |                  |                  |                            |                  |                  |
|                 | Furnace          | 21%              | 13%              | 12–11%           | 26%                        | 18%              | 17%              |
|                 | Heat pump        | 19–18%           | 11%              | 11-10%           | 24%                        | 16%              | 16%              |
| 2 B             | Phoenix, AZ      | 18–17%           | 12%              | 11–10%           | 23%                        | 17%              | 16%              |
| 1 A             | Miami, FL        | 13–11%           | 7–6%             | 10–7%            | 21%                        | 15%              | 17%              |

Notes:

Range of savings indicates exterior and interior low-e panels (first and second numbers, respectively).

Solar-control, low-e panels were modeled for exterior application only.

Installation over metal-framed window assumes thermally broken mounting.

Gray cells not evaluated.

**Table 3.4**. HVAC Energy Cost Savings of Exterior Low–e Storm Windows over Single–Pane Wood Windows as Calculated by RESFEN – Smaller Older 1–Story Home

HVAC Energy Cost Savings of Exterior Low-e Storm Windows in Smaller Older 1-Story home Standard Low-e Glass Solar Control Low-e Glass Over Single-Pane Wood Window Over Single–Pane Wood Window Simple Simple Payback for Payback for Simple Simple Climate **Energy Cost** Total Payback for Total Payback for **Energy Cost** Zone Location Savings Product (yrs) low-e (yrs) Savings Product (yrs) low-e (yrs) 8 Fairbanks, AK 4.7 2.7 \$537 (18%) 7 Anchorage, AK \$406 (23%) 6.2 3.4 7 Duluth, MN \$422 (24%) 6.0 3.6 6 A 3.8 Burlington, VT \$664 (25%) 2.2 6 A Minneapolis, MN 7.3 4.2 \$346 (25%) 5 A Boston, MA \$470 (28%) 5.3 3.3 4.9 2.7 5 A Rochester, NY \$510 (24%) 5 A Pittsburgh, PA \$375 (24%) 6.7 3.6 5 A Chicago, IL \$299 (25%) 8.4 4.7 5 B Denver, CO 10.5 5.3 \$239 (24%) 5 B Boise, ID 10.1 5.3 \$249 (25%) 4 A New York, NY \$418 (25%) 6.0 3.5 4 A Washington, DC \$352 (24%) 7.1 3.9 \$330 (22%) 7.6 5.8 4 A 9.3 4.9 \$255 (19%) 9.8 Raleigh, NC \$267 (20%) 6.6 4 A Kansas City, MO \$368 (27%) 6.8 3.8 \$350 (26%) 7.2 5.1 4 C Seattle, WA \$294 (29%) 8.5 4.7 3 A Atlanta, GA 9.6 4.9 9.9 \$263 (26%) \$255 (26%) 5.8 3 A Dallas, TX: 5.6 4.1 Furnace \$212 (25%) 11.8 \$229 (26%) 11.0 Heat pump \$174 (21%) 14.4 6.4 \$198 (24%) 12.7 4.0 2 A Jacksonville, FL 18.7 7.6 \$168 (23%) 15.0 \$135 (18%) 3.8 2 A Houston, TX: Furnace \$166 (22%) 15.1 6.6 \$197 (26%) 12.8 3.7 7.2 Heat pump \$143 (19%) 17.6 \$178 (24%) 14.1 3.6 2 B 4.5 Phoenix, AZ \$196 (18%) 12.8 \$247 (23%) 10.2 2.4 Miami, FL \$117 (13%) 7.3 \$183 (21%) 2.5 1 A 21.4 13.8

Notes:

Payback will be shorter for leakier primary windows, higher fuel costs, or propane and electrical resistance heating. Gray cells not evaluated.

**Table 3.5**. HVAC Source Energy Savings for Low-e Storm Windows and Panels as Calculated by RESFEN – Larger, Newer, Two-Story Home

HVAC Source Energy Savings of Low-e Storm Windows Used Over Different Primary Window Types in Larger Newer 2-story Home

|         |                  | Stan         | ard Low-e Glass  Solar Control Low-e Glass |              |         |                  |              |
|---------|------------------|--------------|--|--------------|---------|------------------|--------------|
|         |                  |              | Double-                                    |              | Single- |                  |              |
|         |                  | Single-Pane, | Pane,                                      | Double-Pane, | Pane,   | Double-<br>Pane, | Double-Pane, |
|         |                  | Wood-        | Metal-                                     | Wood-        | Wood-   | Metal-           | Wood-        |
| Climate | at a             | Framed       | Framed                                     | Framed       | Framed  | Framed           | Framed       |
| Zone    | City, State      | Window       | Window                                     | Window       | Window  | Window           | Window       |
| 8       | Fairbanks, AK    | 40–43%       | 28-30%                                     | 21–24%       |         |                  |              |
| 7       | Anchorage, AK    | 45–48%       | 32–35%                                     | 24–28%       |         |                  |              |
| 7       | Duluth, MN       | 46–50%       | 32-35%                                     | 24–28%       |         |                  |              |
| 6 A     | Burlington, VT   | 44–48%       | 31-34%                                     | 23-27%       |         |                  |              |
| 6 A     | Minneapolis, MN  | 44–47%       | 30-33%                                     | 23-26%       |         |                  |              |
| 5 A     | Boston, MA       | 45–49%       | 31-35%                                     | 24-27%       |         |                  |              |
| 5 A     | Rochester, NY    | 43-46%       | 30-32%                                     | 23-26%       |         |                  |              |
| 5 A     | Pittsburgh, PA   | 43-46%       | 30-33%                                     | 23-26%       |         |                  |              |
| 5 A     | Chicago, IL      | 44–47%       | 30-33%                                     | 23-26%       |         |                  |              |
| 5 B     | Denver, CO       | 47-50%       | 34-37%                                     | 26-30%       |         |                  |              |
| 5 B     | Boise, ID        | 45-48%       | 33-35%                                     | 25-28%       |         |                  |              |
| 4 A     | New York, NY     | 43-46%       | 29-32%                                     | 22-25%       |         |                  |              |
| 4 A     | Washington, DC   | 40-43%       | 28-31%                                     | 21-24%       | 39%     | 27%              | 20%          |
| 4 A     | Raleigh, NC      | 37–39%       | 25-27%                                     | 20-21%       | 36%     | 25%              | 20%          |
| 4 A     | Kansas City, MO  | 39-42%       | 27-29%                                     | 21-23%       | 39%     | 26%              | 20%          |
| 4 C     | Seattle, WA      | 49-53%       | 36-39%                                     | 28-32%       |         |                  |              |
| 3 A     | Atlanta, GA      | 36-38%       | 25-27%                                     | 20-21%       | 37%     | 25%              | 20%          |
| 3 A     | Dallas, TX:      |              |  |              |         |                  |              |
|         | Furnace          | 34–35%       | 23-24%                                     | 19%          | 36%     | 25%              | 21%          |
|         | Heat pump        | 31%          | 20–21%                                     | 18–17%       | 35%     | 25%              | 22%          |
| 2 A     | Jacksonville, FL | 27–26%       | 17%  | 16–14%       | 33%     | 24%              | 23%          |
| 2 A     | Houston, TX:     | 00.500       | 1007                                       | 4.50.4       | 0.407   | 2.12.            | 0.007        |
|         | Furnace          | 30–29%       | 19%  | 17–16%       | 34%     | 24%              | 23%          |
| 2 D     | Heat pump        | 27–26%       | 17%  | 17–15%       | 33%     | 24%              | 23%          |
| 2 B     | Phoenix, AZ      | 25–24%       | 18%  | 16–14%       | 32%     | 25%              | 23%          |
| 1 A     | Miami, FL        | 17–14%       | 9–8%                                       | 12–9%        | 27%     | 19%              | 22%          |

Notes:

Range of savings indicates exterior and interior low-e panels (first and second numbers, respectively).

Solar control low-e panels were modeled for exterior application only.

Installation over metal-framed window assumes thermally broken mounting.

Gray cells not evaluated.

**Table 3.6**. HVAC Energy Cost Savings of Exterior Low-e Storm Windows over Single-Pane Wood Windows as Calculated by RESFEN – Larger, Newer, Two-Story Home

HVAC Energy Cost Savings of Exterior Low-e Storm Windows in Larger, Newer, Two-Story Home Standard Low-e Glass Solar Control Low-e Glass Over Single-Pane Wood Window Over Single-Pane Wood Window Simple Simple Payback for Payback for Simple Simple Climate **Energy Cost** Total Payback for Total Payback for **Energy Cost** Zone Location Savings Product (yrs) low-e (yrs) Savings Product (yrs) low-e (yrs) 8 Fairbanks, AK 3.0 1.7 \$824 (40%) 7 Anchorage, AK \$619 (45%) 4.1 2.2 7 Duluth, MN \$645 (46%) 3.9 2.4 6 A Burlington, VT \$986 (45%) 2.5 1.5 6 A Minneapolis, MN 4.9 2.9 \$516 (43%) 5 A Boston, MA \$688 (45%) 3.7 2.2 5 A 1.9 Rochester, NY \$749 (42%) 3.4 5 A Pittsburgh, PA 4.6 2.5 \$547 (43%) 5 A Chicago, IL \$442 (43%) 5.7 3.2 5 B Denver, CO \$340 (45%) 7.4 3.8 5 B Boise, ID 6.9 3.6 \$363 (45%) 4 A 2.4 New York, NY \$615 (42%) 4.1 4 A Washington, DC \$508 (41%) 4.9 2.7 \$488 (39%) 5.1 3.4 4 A 3.6 \$362 (37%) 6.9 4.0 Raleigh, NC \$369 (38%) 6.8 4 A Kansas City, MO \$529 (41%) 4.7 2.6 \$512 (39%) 4.9 3.2 4 C Seattle, WA 5.9 3.2 \$425 (50%) 3 A \$410 (39%) Atlanta, GA 6.1 3.3 4.1 \$394 (38%) 6.4 3 A Dallas, TX: 7.9 3.9 7.5 3.1 Furnace \$317 (34%) \$334 (36%) Heat pump \$260 (31%) 9.7 4.4 \$292 (35%) 8.6 2.8 2 A Jacksonville, FL \$190 (27%) 13.2 5.7 \$234 (33%) 10.8 2.9 2 A Houston, TX: Furnace \$240 (30%) 10.5 4.9 \$278 (35%) 9.1 2.8 12.1 5.3 9.9 2.7 Heat pump \$208 (27%) \$254 (33%) 2 B 9.9 3.7 \$319 (32%) 7.9 1.9 Phoenix, AZ \$254 (26%) Miami, FL \$149 (17%) 6.0 \$234 (27%) 10.7 2.0 1 A 16.8

Notes:

Payback will be shorter for leakier primary windows, higher fuel costs, or propane and electrical resistance heating. Gray cells not evaluated.

**Table 3.7**. Overall Average Savings and Payback Period by Climate Zone. Results in climate zones 1–3 are for solar control low–e.

|      | Source Energy Savings |              |           |           | Simple Payback<br>for Total Product (years) |            |          | Incremental Simple Payback for Low-e (years) |             |  |
|------|-----------------------|--------------|-----------|-----------|---|------------|----------|--|-------------|--|
|      | Over Wood             | l Frame, Sir | igle Pane | Over Wood | d Frame, S                                  | ingle Pane | Over Woo | d Frame, S                                   | Single Pane |  |
| Zone | Average               | Min          | Max       | Average   | Min   | Max        | Average  | Min  | Max         |  |
| 8    | 30%                   | 18%          | 43%       | 3.7       | 2.8   | 4.7        | 2.0      | 1.5  | 2.7         |  |
| 7    | 36%                   | 23%          | 50%       | 4.8       | 3.6   | 6.2        | 2.6      | 1.9  | 3.6         |  |
| 6    | 36%                   | 25%          | 48%       | 4.5       | 2.4   | 7.3        | 2.5      | 1.2  | 4.2         |  |
| 5    | 36%                   | 24%          | 50%       | 6.2       | 3.2   | 10.5       | 3.3      | 1.7  | 5.3         |  |
| 4    | 34%                   | 19%          | 53%       | 6.0       | 3.8   | 9.3        | 3.2      | 2.1  | 4.9         |  |
| 3    | 31%                   | 24%          | 38%       | 8.5       | 5.2   | 12.7       | 4.0      | 2.8  | 5.8         |  |
| 2    | 28%                   | 23%          | 34%       | 11.2      | 7.9   | 15.0       | 3.0      | 1.9  | 3.8         |  |
| 1    | 24%                   | 21%          | 27%       | 12.2      | 10.7  | 13.8       | 2.3      | 2.0  | 2.5         |  |

|      | Source Energy Savings Over Metal Frame, Double Pane |     |     | Simple Payback<br>for Total Product (years)<br>Over Metal Frame, Double Pane |      |      | Incremental Simple Payback<br>for Low-e (years)<br>Over Metal Frame, Double Pane |     |     |
|------|---|-----|-----|--|------|------|--|-----|-----|
|      |   |     |     |  |      |      |  |     |     |
| Zone | Average   | Min | Max | Average  | Min  | Max  | Average  | Min | Max |
| 8    | 21%   | 12% | 30% | 6.2  | 4.7  | 7.7  | 2.0  | 1.6 | 2.5 |
| 7    | 25%   | 15% | 35% | 8.0  | 6.2  | 10.1 | 2.6  | 2.1 | 3.3 |
| 6    | 25%   | 16% | 34% | 7.5  | 4.0  | 12.4 | 2.5  | 1.4 | 3.9 |
| 5    | 25%   | 16% | 37% | 10.2   | 5.3  | 16.5 | 3.2  | 1.7 | 4.8 |
| 4    | 24%   | 13% | 39% | 9.8  | 6.5  | 15.0 | 3.1  | 2.1 | 4.4 |
| 3    | 21%   | 16% | 27% | 13.8   | 8.3  | 20.5 | 3.7  | 2.7 | 5.1 |
| 2    | 20%   | 16% | 25% | 17.4   | 11.0 | 23.4 | 2.9  | 1.7 | 3.7 |
| 1    | 17%   | 15% | 19% | 18.4   | 16.4 | 20.4 | 2.3  | 2.0 | 2.5 |

|      | Source                       | Energy Sav | /ings | Simple Payback<br>for Total Product (years) |      |      | Incremental Simple Payback for Low-e (years) |     |     |
|------|------------------------------|------------|-------|---|------|------|--|-----|-----|
|      | Over Wood Frame, Double Pane |            |       | Over Wood Frame, Double Pane                |      |      | Over Wood Frame, Double Pane                 |     |     |
| Zone | Average                      | Min        | Max   | Average                                     | Min  | Max  | Average                                      | Min | Max |
| 8    | 16%                          | 8%         | 24%   | 9.1   | 6.7  | 11.9 | 2.6  | 2.0 | 3.3 |
| 7    | 19%                          | 10%        | 28%   | 12.3  | 9.1  | 16.2 | 3.4  | 2.5 | 4.5 |
| 6    | 19%                          | 11%        | 27%   | 11.3  | 5.9  | 18.8 | 3.1  | 1.6 | 5.1 |
| 5    | 19%                          | 11%        | 30%   | 15.4  | 7.7  | 26.1 | 4.0  | 2.2 | 6.4 |
| 4    | 18%                          | 9%         | 32%   | 14.9  | 9.5  | 22.9 | 3.9  | 2.6 | 5.6 |
| 3    | 17%                          | 12%        | 22%   | 19.0  | 12.3 | 25.1 | 4.6  | 3.1 | 6.9 |
| 2    | 20%                          | 15%        | 23%   | 18.6  | 12.5 | 24.2 | 3.2  | 2.0 | 4.1 |
| 1    | 20%                          | 17%        | 22%   | 15.9  | 14.0 | 17.8 | 2.4  | 2.1 | 2.6 |

The definition of cost effectiveness will vary depending upon the consumer or program viewpoint, but one possible criterion is to use a return-on-investment of greater than 7 to 10%, which corresponds to a simple payback periods of 10 to 14 year or less. As shown in Table 3.4, Table 3.6, and Table 3.7, two types of simple payback period were calculated from the results to evaluate cost effectiveness. First, a simple payback period for the total storm window cost was calculated, including installation cost. Second, the incremental payback period for using low-e glass instead of clear glass was calculated. This is useful when the homeowner has chosen to install a storm window or panel for other reasons (e.g., increased comfort, noise reduction, window protection, reduced air leakage, etc.) regardless of the total product payback period, and it is the incremental payback period that is important in determining whether the homeowner uses low-e glass or clear glass. Nonetheless, the simple payback periods reported in Table 3.4, Table 3.6, and Table 3.7 for low-e storm windows are considerably shorter than payback periods for replacement windows, which are commonly over 25 years when including removal and installation costs.

Note that the energy use and costs calculated by RESFEN are for the whole home heating and cooling energy use, but do not include the energy use for hot water, appliances, lighting, and plug loads. Therefore, energy cost savings percentages should be applied directly to just the heating and cooling component a homeowner's utility bill, not to the overall bill.

The following general points and trends were observed:

- Low-e storm windows show significant percent energy savings across all climate zones. The total magnitude of the energy cost and savings is obviously more in the north where total home energy use is higher than in the south, and the payback period is commensurately shorter in the north than in the south.
- Regular low-e glass provides higher energy savings in climate zones 4 through 8, and solar control low-e provides higher energy savings in climate zones 1 through 3.
- The energy savings is highest for use of low-e storm windows installed over single-pane windows, followed by the metal-frame, double-pane windows, and the wood-frame, double-pane windows.
   Essentially, the lower performing the primary windows, the higher relative improvement from using low-e storm windows.
- Interior low-e panels showed slightly higher energy savings than exterior low-e storm windows, due to the somewhat lower U-factor and air leakage from using interior panels.
- The percent energy savings from using low-e storm windows is actually higher in the larger, newer, two-story home than in the smaller, older, one-story home, even though both homes have the same relative window area (15% of the conditioned floor area). This is because in the better-insulated, newer home, the primary windows become the weak link in the envelope and contribute relatively more to the overall energy use. As a result, improving the performance of the primary windows by adding a low-e storm window has a larger relative impact. Of course, it also is less likely to find single glazing in newer homes, although a significant amount of newer homes can have windows with double pane clear glass.
- The RESFEN energy savings are somewhat higher than the NEAT energy savings (e.g. 22 to 32% site energy savings for the RESFEN smaller, older, one-story home versus 16 to 22% for the NEAT WFVC6 home) due to differences in the model homes, but the relative trends are similar, and

the payback periods are similar (e.g. 3.8 to 11 years for the RESFEN smaller, older, one-story home versus 3.8 to 9.9 years for the NEAT WFVC6 home).

- While there is no specific cutoff criterion for cost effectiveness such as SIR >1 in the NEAT analysis for weatherization programs, the RESFEN results for payback period show the same general trends as the NEAT SIR results. Low-e storm windows are cost effective when installed over single-pane windows and double-pane, metal-framed windows in climate zones 3 through 8. Solar-control, low-e glass is more cost effective in climate zone 3, whereas regular low-e is more cost effective in zones 4 through 8.
- Low-e storm windows also are cost effective when installed over double-pane wood or vinyl-framed windows in climate zones 6 through 8, as well as zones 4 through 5 depending on the home type and local fuel cost.
- In climate zones 1 and 2, storm windows with solar-control, low-e glass can be cost effective, but should be evaluated on a case-by-case basis.
- The incremental cost for using low-e glass versus clear glass is always cost effective with short payback periods in *all* climate zones and over *all* window types. In other words, when a homeowner has already decided to install a storm window or interior panel, regardless of location, it should always be a low-e storm window or panel.
- The analysis was performed with either a natural-gas furnace or electrical heat pump depending on location. For homes using propane or electrical-resistance heating, the energy cost savings and cost effectiveness of low-e storm windows will be even higher, because the effective heating fuel cost and savings from using low-e storm windows will be higher.

Additionally, the effect of how exterior storm windows are mounted over metal-framed windows was examined. The detailed simulations used to determine the U-factor and SHGC values shown in Table 3.2 also examined different attachment methods. Both exterior storm windows mounted over wood frame windows and interior panels will be mounted to a nonmetal surface, therefore ensuring no thermal bridging effects. However, with exterior storm windows mounted over metal framed windows, the storm window can either be mounted to surrounding wood brick mold or a wood blind stop with no metal-to-metal contact, or it can be mounted directly to the metal window frame. The first "thermally broken" mounting method is the recommended practice. The latter method is still beneficial for improving the thermal performance and air leakage of the existing window, but some performance is sacrificed from the direct metal-to-metal thermal bridge.

To examine the magnitude of this effect, both mounting methods were included in the RESFEN analysis. Example results for Boston are shown in Table 3.8. While the exterior low-e storm window provides significant energy savings over metal-framed windows in both cases, mounting the storm window with direct metal-to-metal contact decreases the potential energy savings by about one-third and increases the payback period by 3 to 5 years. Therefore, it is recommended to provide thermally broken mounting with no metal-to-metal contact wherever possible.

**Table 3.8**. Effect of Different Mounting Methods for Installing Exterior Storm Windows over Metal-Framed, Double-Pane Windows in Boston, Massachusetts

|  | Smaller, Older, O                                     | One-Story Home                       | Larger, Newer, Two-Story Home                         |                                      |  |
|--|---|--------------------------------------|---|--------------------------------------|--|
|  | Thermally Broken Mounting (no metal-to-metal contact) | Direct Metal-to-<br>Metal Attachment | Thermally Broken Mounting (no metal-to-metal contact) | Direct Metal-to-<br>Metal Attachment |  |
| Energy Cost Savings                          | \$277 (18.0%)   | \$178 (11.6%)                        | \$395 (31.4%)   | \$262 (20.8%)                        |  |
| Simple Payback for<br>Total Product (years)  | 9.1   | 14.1                                 | 6.4   | 9.6                                  |  |
| Incremental Simple Payback for Low-e (years) | 2.9   | 4.7                                  | 2.0   | 3.1                                  |  |

# 4.0 Conclusions and Recommendations Based on the NEAT and RESFEN Results

Most weatherization assistance programs will only fund energy-efficient weatherization measures if they meet certain cost-effectiveness criteria, typically defined in terms of the savings-to-investment ratio (SIR), where installation of the energy-efficiency measure must yield an SIR greater than 1 to qualify for weatherization funding. Weatherization programs typically use the NEAT model to calculate SIR for weatherization measures. The RESFEN model was specifically designed to compare the annual energy performance of different fenestration options in single-family homes, and it is used as the basis of the ENERGY STAR® program for windows, doors, and skylights. This report provides calculations from both the NEAT and RESFEN modeling platforms to address the different audiences that will use the data (utilities, weatherization programs, federal energy-efficiency programs, consumers, etc.).

The definition of cost effectiveness will vary depending upon the consumer or program viewpoint. For the purposes of this report, the criteria used to determine and discuss cost-effective measures include the SIR measurement (i.e., SIR greater than 1) as well as simple payback periods, where a 10 to 14-year payback (or less) would be considered cost-effective. Using the SIR and these payback periods as the basis for measuring low-e storm window cost effectiveness, the results from both the NEAT and RESFEN analyses are generally consistent, and yield the following conclusions:

- Low-e storm windows are qualified as cost-effective weatherization measures (based on SIR greater than 1) and are recommended for installation over all single-pane windows and double-pane, metal-framed windows in climate zones 3 through 8. The use of solar-control low-e storm windows is recommended in climate zone 3, and may also be considered in warmer parts of zone 4 where cooling degree days exceed heating degree days. The use of regular low-e storm windows is recommended in zones 4 through 8, although solar-control low-e windows can sometimes be beneficial in specific applications even in northern zones (e.g., large west-facing windows in areas with hot summers).
- Low-e storm windows are also qualified as weatherization measures and recommended for installation over double-pane wood/vinyl-framed windows in climate zones 6 through 8, and in eastern parts of zone 5 where higher heating fuel costs exist. They will also be qualified as weatherization measures in more zones when propane or electrical-resistance heating are used, and where the primary window is particularly leaky (e.g. "loose" or "very loose" by NEAT definitions).
- The incremental cost for using low-e glass versus clear glass is always cost effective in all climate zones and over all window types. Therefore, when a homeowner has chosen to install a storm window or interior panel for reasons other than just energy savings (e.g., increased comfort, noise reduction, window protection, reduced air leakage, etc.), it should be a low-e storm window or panel regardless of location.
- Where exterior low-e storm windows are installed over metal-framed primary windows, the storm window should be mounted with no metal-to-metal contact where possible (i.e., a "thermally broken" installation).

#### Over Single-Pane Windows and Double-Pane Metal-Framed Windows:



**Figure 4.1**. Overall Recommended Regions for the Use of Low-e Storm Windows Installed Over Single-Pane Windows and Double-Pane Metal-Framed Windows and the Location of Cities Included in this Analysis.

#### **Over Double Pane Wood/Vinyl Framed Windows:**



**Figure 4.2**. Overall Recommended Regions for Use of Low-e Storm Windows Installed Over Double-Pane, Wood/Vinyl-Framed Windows. The region where low-e storm windows are recommended will be larger than shown for homes using propane or electrical resistance heating, or those that have particularly leaky windows. Points indicated on the map show the location of cities included in this analysis.

#### 5.0 References

K.A. Cort. 2013. Low-e Storm Windows: Market Assessment and Pathways to Market Transformation. PNNL-22565, Pacific Northwest National Laboratory, Richland, Washington.

Dalhoff G. 2010. *Development of a Measure Prioritization List for Pennsylvania*. Dalhoff Associates LLC, unpublished report for the Pennsylvania Department of Community and Economic Development, Harrisburg, Pennsylvania.

DOE-EIA. 2009. 2009 Residential Energy Consumption Survey: Housing Characteristics. U.S. Department of Energy/Energy Information Administration, Washington, D.C.

DOE-EIA. 2013. Natural Gas Prices: Monthly by state. Database available online at: <a href="http://www.eia.gov/dnav/ng/ng\_pri\_sum\_dcu\_nus\_m.htm">http://www.eia.gov/dnav/ng/ng\_pri\_sum\_dcu\_nus\_m.htm</a>. U.S. Department of Energy/Energy Information Administration, released June 28, 1013, Washington, D.C.

Drumheller SC, C Kohler, and S Minen. *Field Evaluation of Low-e Storm Windows*. 2007. LBNL-1940E, Lawrence Berkley National Laboratory, Berkeley, California.

Gettings M. 2006. *The Weatherization Assistant Users Manual for Administrative Features*. ORNL/TM-2005/236, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Hefty MG, TD Culp, and SH Widder. 2013. *Task Plan in Support of Emerging Technology Task ET-WIN-PNNL-FY13-01\_5.1: Create a Database of U.S. Climate-Based Analysis for Low-e Storm Windows*. PNNL-22307, Pacific Northwest National Laboratory, Richland, Washington.

Krigger J and W Van der Meer. 2011. *Weatherization Standards and Field Guide for Pennsylvania*. Published for the U.S. Department of Energy Weatherization Assistance Program and the Pennsylvania Department of Community and Economic Development, and Office of Energy Conservation and Weatherization, February 2011 Edition, Harrisburg, Pennsylvania.

Oak Ridge National Laboratory (ORNL). 2009. "Window Leakiness Guidelines." Oakridge National Laboratory Weatherization Support Program, May 2009. Available online at http://eber.ed.ornl.gov/pub/weatherization/Support%20Material/Window%20Leakiness.pdf

Quanta Technologies. 2013. 2012-13 Quarterly Reports prepared for U.S. Department of Energy under DOE EERE award #DE-EE0004015, Malvern, Pennsylvania.

Zalis W et al. 2010. Evaluation of Low-E Storm and R-5 Windows for Inclusion in Pennsylvania's Weatherization Priority List. Prepared by W Zalis, Energetics; T Culp, Birch Point Consulting; C Kohler, LBNL; and PM LaFrance, U.S. Department of Energy; for the Pennsylvania Department of Community and Economic Development, May 2010, Columbia, Maryland.

# Appendix A NEAT Calculation Results for Each City

#### Duluth MN Zone 7

Zone 7
HDD65 9818
CDD50 1536
Natural Gas (\$/Mcf, 2012 avg) \$7.97
Electricity (\$/kWh, 2012 avg) \$0.1137
Low-e Storms \$7.85/ft2 + \$30/window

SIR with different primary window types:

|    |                               | Single pane | Double pane | Double pane |
|----|-------------------------------|-------------|-------------|-------------|
|    | Home type                     | wood/vinyl  | metal       | wood/vinyl  |
| 1  | Exposed Floor 1               | 2.1         | 2.0         | 1.3         |
| 2  | Wood Frame Cape Cod 1 KW 1    | 2.1         | 2.0         | 1.4         |
| 3  | Wood Frame Cape Cod 2 KW 2    | 2.1         | 2.0         | 1.3         |
| 4  | Wood Frame Cape Cod 3 KW 3    | 2.1         | 2.0         | 1.3         |
| 5  | Wood Frame Cape Cod 4 KW 4    | 2.1         | 2.0         | 1.4         |
| 6  | Wood Frame Cape Cod 1 KW 5    | 2.1         | 2.0         | 1.3         |
| 7  | Masonry 1                     | 2.1         | 2.0         | 1.3         |
| 8  | Masonry 2                     | 2.1         | 2.0         | 1.3         |
| 9  | Masonry 3                     | 2.1         | 2.0         | 1.3         |
| 10 | Masonry 4                     | 2.1         | 2.1         | 1.3         |
| 11 | Masonry 5                     | 2.1         | 2.1         | 1.3         |
| 12 | Masonry 6                     | 2.1         | 2.1         | 1.3         |
| 13 | Row House Masonry 1           | 2.1         | 2.0         | 1.3         |
| 14 | Row House Masonry 2           | 2.1         | 2.0         | 1.3         |
| 15 | Row House Wood Frame 1        | 2.1         | 2.0         | 1.5         |
| 16 | Row House Wood Frame 2        | 2.1         | 2.0         | 1.3         |
| 17 | Semi Detached Masonry 1       | 2.1         | 2.0         | 1.3         |
| 18 | Semi Detached Masonry 2       | 2.1         | 2.2         | 1.3         |
| 19 | Semi Detached Wood Frame 1    | 2.1         | 2.0         | 1.4         |
| 20 | Semi Detached Wood Frame 2    | 2.1         | 2.0         | 1.3         |
| 21 | Wood Frm Cond Bsmt 1          | 2.1         | 2.0         | 1.3         |
| 22 | Wood Frm Cond Bsmt 2          | 2.1         | 2.0         | 1.3         |
| 23 | Wood Frm Cond Bsmt 3          | 2.1         | 2.0         | 1.3         |
| 24 | Wood Frm Cond Bsmt 4          | 2.1         | 2.1         | 1.3         |
| 25 | Wood Frm Slab 1               | 2.1         | 2.1         | 1.3         |
| 26 | Wood Frm Slab 2               | 2.2         | 2.1         | 1.3         |
| 27 | Wood Frm Slab 3               | 2.2         | 2.1         | 1.3         |
| 28 | Wood Frm Slab 4               | 2.2         | 2.1         | 1.3         |
| 29 | Wood Frm Uncon Bsmt 1         | 2.1         | 2.0         | 1.3         |
| 30 | Wood Frm Uncon Bsmt 2         | 2.1         | 2.0         | 1.3         |
| 31 | Wood Frm Uncon Bsmt 3         | 2.1         | 2.0         | 1.3         |
| 32 | Wood Frm Uncon Bsmt 4         | 2.1         | 2.0         | 1.3         |
| 33 | Wood Frm Uncon Bsmt 5         | 2.1         | 2.0         | 1.3         |
| 34 | Wood Frm Vented Crawl Space 1 | 2.1         | 2.0         | 1.3         |
| 35 | Wood Frm Vented Crawl Space 2 | 2.1         | 2.0         | 1.3         |
| 36 | Wood Frm Vented Crawl Space 3 | 2.1         | 2.0         | 1.3         |
| 37 | Wood Frm Vented Crawl Space 4 | 2.1         | 2.0         | 1.3         |
| 38 | Wood Frm Vented Crawl Space 5 | 2.1         | 2.0         | 1.3         |
| 39 | Wood Frm Vented Crawl Space 6 | 2.1         | 2.0         | 1.3         |

Average SIR Max SIR Min SIR

| 2.1 | 2.0 | 1.3 |
|-----|-----|-----|
| 2.2 | 2.2 | 1.5 |
| 2.1 | 2   | 1.3 |

| Other metrics:                     |         |  |  |
|------------------------------------|---------|--|--|
| Wood Frame Vented Crawl Space home |         |  |  |
| Single pane wood windows           |         |  |  |
|                                    |         |  |  |
| Annual cost savings                | \$189   |  |  |
| Measure Cost                       | \$1,386 |  |  |
| Simple Payback                     | 7.3     |  |  |
|                                    |         |  |  |
| Energy Savings (Mbtu/yr)           |         |  |  |
| Initial home heat+cool             | 124.6   |  |  |
| Storm savings                      | 23.8    |  |  |
| % reduction                        | 19%     |  |  |

if include 1/3 of air inf savings \$244

## Burlington VT Zone 6 HDD65

7771 2228 \$16.73 \$0.1731 CDD50 Natural Gas (\$/Mcf, 2012 avg) Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window

\$1.635

per therm

SIR with different primary window types:

|    |                               | Single pane | Double pane | Double pane |
|----|-------------------------------|-------------|-------------|-------------|
|    | Home type                     | wood/vinyl  | metal       | wood/vinyl  |
| 1  | Exposed Floor 1               | 3.2         | 3.0         | 1.8         |
| 2  | Wood Frame Cape Cod 1 KW 1    | 3.1         | 3.0         | 1.9         |
| 3  | Wood Frame Cape Cod 2 KW 2    | 3.1         | 3.0         | 1.8         |
| 4  | Wood Frame Cape Cod 3 KW 3    | 3.2         | 3.0         | 1.8         |
| 5  | Wood Frame Cape Cod 4 KW 4    | 3.2         | 3.0         | 1.8         |
| 6  | Wood Frame Cape Cod 1 KW 5    | 3.2         | 3.1         | 1.9         |
| 7  | Masonry 1                     | 3.3         | 3.1         | 1.9         |
| 8  | Masonry 2                     | 3.2         | 3.1         | 1.8         |
| 9  | Masonry 3                     | 3.2         | 3.1         | 1.8         |
| 10 | Masonry 4                     | 3.3         | 3.2         | 1.9         |
| 11 | Masonry 5                     | 3.3         | 3.2         | 1.9         |
| 12 | Masonry 6                     | 3.3         | 3.1         | 1.9         |
| 13 | Row House Masonry 1           | 3.1         | 3.0         | 2.0         |
| 14 | Row House Masonry 2           | 3.2         | 3.1         | 2.2         |
| 15 | Row House Wood Frame 1        | 3.1         | 3.0         | 2.1         |
| 16 | Row House Wood Frame 2        | 3.2         | 3.0         | 2.2         |
| 17 | Semi Detached Masonry 1       | 3.2         | 3.1         | 1.9         |
| 18 | Semi Detached Masonry 2       | 3.2         | 3.1         | 1.9         |
| 19 | Semi Detached Wood Frame 1    | 3.1         | 3.0         | 1.8         |
| 20 | Semi Detached Wood Frame 2    | 3.2         | 3.1         | 1.8         |
| 21 | Wood Frm Cond Bsmt 1          | 3.3         | 3.1         | 1.8         |
| 22 | Wood Frm Cond Bsmt 2          | 3.2         | 3.1         | 1.8         |
| 23 | Wood Frm Cond Bsmt 3          | 3.2         | 3.0         | 1.7         |
| 24 | Wood Frm Cond Bsmt 4          | 3.3         | 3.1         | 1.9         |
| 25 | Wood Frm Slab 1               | 3.3         | 3.1         | 1.9         |
| 26 | Wood Frm Slab 2               | 3.3         | 3.1         | 1.9         |
| 27 | Wood Frm Slab 3               | 3.3         | 3.2         | 1.9         |
| 28 | Wood Frm Slab 4               | 3.3         | 3.1         | 1.9         |
| 29 | Wood Frm Uncon Bsmt 1         | 3.2         | 3.0         | 1.8         |
| 30 | Wood Frm Uncon Bsmt 2         | 3.2         | 3.0         | 1.8         |
| 31 | Wood Frm Uncon Bsmt 3         | 3.2         | 3.1         | 1.8         |
| 32 | Wood Frm Uncon Bsmt 4         | 3.0         | 2.9         | 1.7         |
| 33 | Wood Frm Uncon Bsmt 5         | 3.2         | 3.1         | 1.9         |
| 34 | Wood Frm Vented Crawl Space 1 | 3.2         | 3.0         | 1.8         |
| 35 | Wood Frm Vented Crawl Space 2 | 3.2         | 3.1         | 1.8         |
| 36 | Wood Frm Vented Crawl Space 3 | 3.2         | 3.1         | 1.8         |
| 37 | Wood Frm Vented Crawl Space 4 | 3.2         | 3.1         | 1.8         |
| 38 | Wood Frm Vented Crawl Space 5 | 3.2         | 3.1         | 1.8         |
| 39 | Wood Frm Vented Crawl Space 6 | 3.2         | 3.1         | 1.8         |

Average SIR Max SIR Min SIR

| R | 3.2 | 3.1 | 1.9 |
|---|-----|-----|-----|
| R | 3.3 | 3.2 | 2.2 |
| R | 3.0 | 2.9 | 1.7 |

| Other metrics:<br>Wood Frame Vented Crawl Space h<br>Single pane wood windows | nome    |
|---|---------|
| Annual cost savings   | \$287   |
| Measure Cost  | \$1,386 |
| Simple Payback  | 4.8     |
| Energy Savings (Mbtu/yr)  |         |
| Initial home heat+cool  | 91.1    |
| Storm savings   | 17.1    |
| % reduction   | 19%     |

if include 1/3 of air inf savings \$368

Minneapolis MN Zone 6 HDD65 7981 CDD50 2680 Natural Gas (\$/Mcf, 2012 avg) Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window \$7.97 \$0.1137

\$0.779 per therm

SIR with different primary window types:

|    | i                             |             | rerent primary wi |             |
|----|-------------------------------|-------------|-------------------|-------------|
|    |                               | Single pane | Double pane       | Double pane |
|    | Home type                     | wood/vinyl  | metal             | wood/vinyl  |
| 1  | Exposed Floor 1               | 1.6         | 1.6               | 1.2         |
| 2  | Wood Frame Cape Cod 1 KW 1    | 1.6         | 1.7               | 1.5         |
| 3  | Wood Frame Cape Cod 2 KW 2    | 1.7         | 1.6               | 1.5         |
| 4  | Wood Frame Cape Cod 3 KW 3    | 1.6         | 1.6               | 1.1         |
| 5  | Wood Frame Cape Cod 4 KW 4    | 1.7         | 1.6               | 1.1         |
| 6  | Wood Frame Cape Cod 1 KW 5    | 1.7         | 1.7               | 1.5         |
| 7  | Masonry 1                     | 1.7         | 1.6               | 1.3         |
| 8  | Masonry 2                     | 1.6         | 1.6               | 1.3         |
| 9  | Masonry 3                     | 1.7         | 1.6               | 1.1         |
| 10 | Masonry 4                     | 1.7         | 1.6               | 1.3         |
| 11 | Masonry 5                     | 1.6         | 1.6               | 1.1         |
| 12 | Masonry 6                     | 1.7         | 1.6               | 1.3         |
| 13 | Row House Masonry 1           | 1.4         | 1.3               |             |
| 14 | Row House Masonry 2           | 1.4         | 1.3               |             |
| 15 | Row House Wood Frame 1        | 1.4         | 1.3               |             |
| 16 | Row House Wood Frame 2        | 1.4         | 1.3               |             |
| 17 | Semi Detached Masonry 1       | 1.7         | 1.6               | 1.3         |
| 18 | Semi Detached Masonry 2       | 1.7         | 1.6               | 1.3         |
| 19 | Semi Detached Wood Frame 1    | 1.6         | 1.6               | 1.2         |
| 20 | Semi Detached Wood Frame 2    | 1.7         | 1.6               | 1.2         |
| 21 | Wood Frm Cond Bsmt 1          | 1.6         | 1.6               | 1.1         |
| 22 | Wood Frm Cond Bsmt 2          | 1.7         | 1.6               | 1.3         |
| 23 | Wood Frm Cond Bsmt 3          | 1.7         | 1.6               | 1.2         |
| 24 | Wood Frm Cond Bsmt 4          | 1.7         | 1.6               | 1.1         |
| 25 | Wood Frm Slab 1               | 1.7         | 1.6               | 1.3         |
| 26 | Wood Frm Slab 2               | 1.7         | 1.6               | 1.3         |
| 27 | Wood Frm Slab 3               | 1.7         | 1.6               | 1.3         |
| 28 | Wood Frm Slab 4               | 1.7         | 1.6               | 1.1         |
| 29 | Wood Frm Uncon Bsmt 1         | 1.6         | 1.5               | 1.1         |
| 30 | Wood Frm Uncon Bsmt 2         | 1.7         | 1.6               | 1.2         |
| 31 | Wood Frm Uncon Bsmt 3         | 1.6         | 1.5               | 1.2         |
| 32 | Wood Frm Uncon Bsmt 4         | 1.6         | 1.5               | 1.2         |
| 33 | Wood Frm Uncon Bsmt 5         | 1.7         | 1.6               | 1.2         |
| 34 | Wood Frm Vented Crawl Space 1 | 1.6         | 1.5               | 1.1         |
| 35 | Wood Frm Vented Crawl Space 2 | 1.7         | 1.6               | 1.2         |
| 36 | Wood Frm Vented Crawl Space 3 | 1.6         | 1.5               | 1.2         |
| 37 | Wood Frm Vented Crawl Space 4 | 1.6         | 1.6               | 1.1         |
| 38 | Wood Frm Vented Crawl Space 5 | 1.7         | 1.6               | 1.2         |
| 39 | Wood Frm Vented Crawl Space 6 | 1.7         | 1.6               | 1.1         |

Average SIR Max SIR Min SIR

| 1.6 | 1.6 | 1.2 |
|-----|-----|-----|
| 1.7 | 1.7 | 1.5 |
| 1.4 | 1.3 | 1.1 |

| Other metrics:                     |         |  |
|------------------------------------|---------|--|
| Wood Frame Vented Crawl Space home |         |  |
| Single pane wood windows           |         |  |
|                                    |         |  |
| Annual cost savings                | \$147   |  |
| Measure Cost                       | \$1,386 |  |
| Simple Payback                     | 9.4     |  |
|                                    |         |  |
| Energy Savings (Mbtu/yr)           |         |  |
| Initial home heat+cool             | 98.1    |  |
| Storm savings                      | 18.3    |  |
| % reduction                        | 19%     |  |

if include 1/3 of air inf savings \$190

## Boston MA Zone 5 HDD65

5641 CDD50 2897 Natural Gas (\$/Mcf, 2011 avg) Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window \$13.81

\$0.1494

SIR with different primary window types:

(2012 average not available)

|    |                               | SIR WIth un | nerent primary wi | naon types: |
|----|-------------------------------|-------------|-------------------|-------------|
|    |                               | Single pane | Double pane       | Double pane |
|    | Home type                     | wood/vinyl  | metal             | wood/vinyl  |
| 1  | Exposed Floor 1               | 2.2         | 2.2               | 1.5         |
| 2  | Wood Frame Cape Cod 1 KW 1    | 2.2         | 2.1               | 1.5         |
| 3  | Wood Frame Cape Cod 2 KW 2    | 2.2         | 2.1               | 1.5         |
| 4  | Wood Frame Cape Cod 3 KW 3    | 2.2         | 2.1               | 1.5         |
| 5  | Wood Frame Cape Cod 4 KW 4    | 2.2         | 2.1               | 1.4         |
| 6  | Wood Frame Cape Cod 1 KW 5    | 2.3         | 2.2               | 1.5         |
| 7  | Masonry 1                     | 2.3         | 2.2               | 1.6         |
| 8  | Masonry 2                     | 2.3         | 2.2               | 1.5         |
| 9  | Masonry 3                     | 2.4         | 2.3               | 1.5         |
| 10 | Masonry 4                     | 2.3         | 2.2               | 1.6         |
| 11 | Masonry 5                     | 2.3         | 2.3               | 1.6         |
| 12 | Masonry 6                     | 2.3         | 2.3               | 1.5         |
| 13 | Row House Masonry 1           | 2.0         | 1.9               | 1.2         |
| 14 | Row House Masonry 2           | 2.0         | 1.9               | 1.2         |
| 15 | Row House Wood Frame 1        | 2.0         | 1.9               | 1.1         |
| 16 | Row House Wood Frame 2        | 2.3         | 2.0               | 1.2         |
| 17 | Semi Detached Masonry 1       | 2.3         | 2.2               | 1.6         |
| 18 | Semi Detached Masonry 2       | 2.4         | 2.3               | 1.5         |
| 19 | Semi Detached Wood Frame 1    | 2.2         | 2.1               | 1.4         |
| 20 | Semi Detached Wood Frame 2    | 2.3         | 2.2               | 1.5         |
| 21 | Wood Frm Cond Bsmt 1          | 2.3         | 2.2               | 1.5         |
| 22 | Wood Frm Cond Bsmt 2          | 2.3         | 2.2               | 1.5         |
| 23 | Wood Frm Cond Bsmt 3          | 2.3         | 2.2               | 1.5         |
| 24 | Wood Frm Cond Bsmt 4          | 2.3         | 2.2               | 1.5         |
| 25 | Wood Frm Slab 1               | 2.3         | 2.3               | 1.5         |
| 26 | Wood Frm Slab 2               | 2.4         | 2.3               | 1.5         |
| 27 | Wood Frm Slab 3               | 2.4         | 2.3               | 1.5         |
| 28 | Wood Frm Slab 4               | 2.4         | 2.3               | 1.5         |
| 29 | Wood Frm Uncon Bsmt 1         | 2.2         | 2.2               | 1.5         |
| 30 | Wood Frm Uncon Bsmt 2         | 2.3         | 2.2               | 1.4         |
| 31 | Wood Frm Uncon Bsmt 3         | 2.3         | 2.2               | 1.4         |
| 32 | Wood Frm Uncon Bsmt 4         | 2.3         | 2.2               | 1.5         |
| 33 | Wood Frm Uncon Bsmt 5         | 2.3         | 2.2               | 1.5         |
| 34 | Wood Frm Vented Crawl Space 1 | 2.2         | 2.2               | 1.5         |
| 35 | Wood Frm Vented Crawl Space 2 | 2.3         | 2.2               | 1.5         |
| 36 | Wood Frm Vented Crawl Space 3 | 2.3         | 2.2               | 1.5         |
| 37 | Wood Frm Vented Crawl Space 4 | 2.3         | 2.2               | 1.4         |
| 38 | Wood Frm Vented Crawl Space 5 | 2.3         | 2.2               | 1.4         |
| 39 | Wood Frm Vented Crawl Space 6 | 2.3         | 2.2               | 1.5         |

Average SIR Max SIR Min SIR

| ł | 2.3 | 2.2 | 1.5 |
|---|-----|-----|-----|
| ١ | 2.4 | 2.3 | 1.6 |
| 1 | 2.0 | 1.9 | 1.1 |

| Other metrics: Wood Frame Vented Crawl Space home Single pane wood windows |                       |
|--|-----------------------|
| Annual cost savings Measure Cost   | \$204<br>\$1,386      |
| Simple Payback   | \$1,386<br><b>6.8</b> |
| Energy Savings (Mbtu/yr)   |                       |
| Initial home heat+cool   | 68.4                  |
| Storm savings  | 14.7                  |
| % reduction  | 21%                   |

if include 1/3 of air inf savings \$265

## Rochester NY Zone 5

HDD65 6734 2406 \$13.71 \$0.1769 CDD50

(2012 average not available)

Natural Gas (\$/Mcf, 2011 avg) Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window

SIR with different primary window types:

|    |                               | Single pane | Double pane | Double pane |
|----|-------------------------------|-------------|-------------|-------------|
|    | Home type                     | wood/vinyl  | metal       | wood/vinyl  |
| 1  | Exposed Floor 1               | 2.7         | 2.6         | 1.8         |
| 2  | Wood Frame Cape Cod 1 KW 1    | 2.7         | 2.6         | 1.8         |
| 3  | Wood Frame Cape Cod 2 KW 2    | 2.7         | 2.6         | 1.9         |
| 4  | Wood Frame Cape Cod 3 KW 3    | 2.7         | 2.6         | 1.8         |
| 5  | Wood Frame Cape Cod 4 KW 4    | 2.7         | 2.6         | 1.9         |
| 6  | Wood Frame Cape Cod 1 KW 5    | 2.8         | 2.7         | 1.9         |
| 7  | Masonry 1                     | 2.8         | 2.7         | 1.9         |
| 8  | Masonry 2                     | 2.8         | 2.7         | 1.7         |
| 9  | Masonry 3                     | 2.7         | 2.6         | 1.8         |
| 10 | Masonry 4                     | 2.7         | 2.6         | 1.9         |
| 11 | Masonry 5                     | 2.7         | 2.6         | 1.9         |
| 12 | Masonry 6                     | 2.7         | 2.6         | 1.8         |
| 13 | Row House Masonry 1           | 2.8         | 2.3         | 1.3         |
| 14 | Row House Masonry 2           | 2.8         | 2.3         | 1.4         |
| 15 | Row House Wood Frame 1        | 2.7         | 2.3         | 1.4         |
| 16 | Row House Wood Frame 2        | 2.8         | 2.4         | 1.5         |
| 17 | Semi Detached Masonry 1       | 2.8         | 2.7         | 1.9         |
| 18 | Semi Detached Masonry 2       | 2.8         | 2.7         | 1.8         |
| 19 | Semi Detached Wood Frame 1    | 2.7         | 2.6         | 1.7         |
| 20 | Semi Detached Wood Frame 2    | 2.8         | 2.7         | 1.8         |
| 21 | Wood Frm Cond Bsmt 1          | 2.8         | 2.7         | 1.9         |
| 22 | Wood Frm Cond Bsmt 2          | 2.8         | 2.7         | 1.8         |
| 23 | Wood Frm Cond Bsmt 3          | 2.8         | 2.7         | 1.7         |
| 24 | Wood Frm Cond Bsmt 4          | 2.8         | 2.7         | 1.8         |
| 25 | Wood Frm Slab 1               | 2.8         | 2.7         | 1.9         |
| 26 | Wood Frm Slab 2               | 2.8         | 2.7         | 1.8         |
| 27 | Wood Frm Slab 3               | 2.8         | 2.7         | 1.8         |
| 28 | Wood Frm Slab 4               | 2.8         | 2.7         | 1.8         |
| 29 | Wood Frm Uncon Bsmt 1         | 2.7         | 2.6         | 1.8         |
| 30 | Wood Frm Uncon Bsmt 2         | 2.7         | 2.6         | 1.7         |
| 31 | Wood Frm Uncon Bsmt 3         | 2.8         | 2.7         | 1.7         |
| 32 | Wood Frm Uncon Bsmt 4         | 2.6         | 2.5         | 1.8         |
| 33 | Wood Frm Uncon Bsmt 5         | 2.8         | 2.7         | 1.8         |
| 34 | Wood Frm Vented Crawl Space 1 | 2.7         | 2.6         | 1.8         |
| 35 | Wood Frm Vented Crawl Space 2 | 2.7         | 2.6         | 1.8         |
| 36 | Wood Frm Vented Crawl Space 3 | 2.8         | 2.7         | 1.7         |
| 37 | Wood Frm Vented Crawl Space 4 | 2.8         | 2.7         | 1.7         |
| 38 | Wood Frm Vented Crawl Space 5 | 2.8         | 2.7         | 1.8         |
| 39 | Wood Frm Vented Crawl Space 6 | 2.8         | 2.7         | 1.7         |

Average SIR Max SIR Min SIR

| 2.8 | 2.6 | 1.8 |
|-----|-----|-----|
| 2.8 | 2.7 | 1.9 |
| 2.6 | 2.3 | 1.3 |

| Other metrics:                     |         |  |
|------------------------------------|---------|--|
| Wood Frame Vented Crawl Space home |         |  |
| Single pane wood windows           |         |  |
|                                    |         |  |
| Annual cost savings                | \$246   |  |
| Measure Cost                       | \$1,386 |  |
| Simple Payback                     | 5.6     |  |
|                                    |         |  |
| Energy Savings (Mbtu/yr)           |         |  |
| Initial home heat+cool             | 88.2    |  |
| Storm savings                      | 17.8    |  |
| % reduction                        | 20%     |  |

if include 1/3 of air inf savings \$315

## Pittsburgh PA Zone 5 HDD65

5968 2836 \$11.97 \$0.1282 CDD50 Natural Gas (\$/Mcf, 2012 avg) Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window

SIR with different primary window types:

|    |                               | Single pane | Double pane | Double pane |
|----|-------------------------------|-------------|-------------|-------------|
|    | Home type                     | wood/vinyl  | metal       | wood/vinyl  |
| 1  | Exposed Floor 1               | 1.8         | 1.7         | 1.3         |
| 2  | Wood Frame Cape Cod 1 KW 1    | 1.8         | 1.7         | 1.3         |
| 3  | Wood Frame Cape Cod 2 KW 2    | 1.9         | 1.8         | 1.3         |
| 4  | Wood Frame Cape Cod 3 KW 3    | 1.9         | 1.8         | 1.3         |
| 5  | Wood Frame Cape Cod 4 KW 4    | 1.9         | 1.8         | 1.1         |
| 6  | Wood Frame Cape Cod 1 KW 5    | 1.8         | 1.8         | 1.4         |
| 7  | Masonry 1                     | 1.9         | 1.8         | 1.2         |
| 8  | Masonry 2                     | 1.9         | 1.8         | 1.2         |
| 9  | Masonry 3                     | 1.9         | 1.8         | 1.2         |
| 10 | Masonry 4                     | 1.9         | 1.8         | 1.2         |
| 11 | Masonry 5                     | 1.9         | 1.8         | 1.2         |
| 12 | Masonry 6                     | 1.9         | 1.8         | 1.2         |
| 13 | Row House Masonry 1           | 1.6         | 1.5         |             |
| 14 | Row House Masonry 2           | 1.6         | 1.5         |             |
| 15 | Row House Wood Frame 1        | 1.5         | 1.5         |             |
| 16 | Row House Wood Frame 2        | 1.6         | 1.5         |             |
| 17 | Semi Detached Masonry 1       | 1.9         | 1.8         | 1.2         |
| 18 | Semi Detached Masonry 2       | 1.9         | 1.8         | 1.3         |
| 19 | Semi Detached Wood Frame 1    | 1.8         | 1.7         | 1.3         |
| 20 | Semi Detached Wood Frame 2    | 1.8         | 1.8         | 1.3         |
| 21 | Wood Frm Cond Bsmt 1          | 1.8         | 1.8         | 1.2         |
| 22 | Wood Frm Cond Bsmt 2          | 1.9         | 1.8         | 1.2         |
| 23 | Wood Frm Cond Bsmt 3          | 1.9         | 1.8         | 1.2         |
| 24 | Wood Frm Cond Bsmt 4          | 1.9         | 1.8         | 1.1         |
| 25 | Wood Frm Slab 1               | 1.9         | 1.8         | 1.2         |
| 26 | Wood Frm Slab 2               | 1.9         | 1.8         | 1.2         |
| 27 | Wood Frm Slab 3               | 1.9         | 1.8         | 1.2         |
| 28 | Wood Frm Slab 4               | 1.9         | 1.8         | 1.1         |
| 29 | Wood Frm Uncon Bsmt 1         | 1.8         | 1.7         | 1.3         |
| 30 | Wood Frm Uncon Bsmt 2         | 1.8         | 1.7         | 1.3         |
| 31 | Wood Frm Uncon Bsmt 3         | 1.8         | 1.7         | 1.3         |
| 32 | Wood Frm Uncon Bsmt 4         | 1.8         | 1.7         | 1.3         |
| 33 | Wood Frm Uncon Bsmt 5         | 1.8         | 1.7         | 1.3         |
| 34 | Wood Frm Vented Crawl Space 1 | 1.8         | 1.7         | 1.3         |
| 35 | Wood Frm Vented Crawl Space 2 | 1.8         | 1.7         | 1.3         |
| 36 | Wood Frm Vented Crawl Space 3 | 1.8         | 1.7         | 1.3         |
| 37 | Wood Frm Vented Crawl Space 4 | 1.8         | 1.7         | 1.2         |
| 38 | Wood Frm Vented Crawl Space 5 | 1.8         | 1.7         | 1.3         |
| 39 | Wood Frm Vented Crawl Space 6 | 1.9         | 1.8         | 1.2         |

Average SIR Max SIR Min SIR

| 2 | 1.8 | 1.7 | 1.2 |
|---|-----|-----|-----|
|   | 1.9 | 1.8 | 1.4 |
|   | 1.5 | 1.5 | 1.1 |

| Other metrics:<br>Wood Frame Vented Crawl Space h<br>Single pane wood windows | ome     |
|---|---------|
| Annual cost savings   | \$167   |
| Measure Cost  | \$1,386 |
| Simple Payback  | 8.3     |
| Energy Savings (Mbtu/yr)  |         |
| Initial home heat+cool  | 69.8    |
| Storm savings   | 13.6    |
| % reduction   | 19%     |

if include 1/3 of air inf savings \$211

#### Chicago IL

Zone 5

HDD65 6176 CDD50 3251

Natural Gas (\$/Mcf, 2012 avg) \$8.22 \$0.1137

Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window per therm

\$0.804

Only 400 ft2 room air conditioned

SIR with different primary window types:

### Whole home air conditioned

SIR with different primary window types:

|    |                               | SIR with different primary window types: |                      |                           |
|----|-------------------------------|--|----------------------|---------------------------|
|    | Home type                     | Single pane<br>wood/vinyl                | Double pane<br>metal | Double pane<br>wood/vinyl |
| 1  | Exposed Floor 1               | 1.4                                      | 1.6                  |                           |
| 2  | Wood Frame Cape Cod 1 KW 1    | 1.4                                      | 1.6                  |                           |
| 3  | Wood Frame Cape Cod 2 KW 2    | 1.4                                      | 1.6                  |                           |
| 4  | Wood Frame Cape Cod 3 KW 3    | 1.4                                      | 1.6                  |                           |
| 5  | Wood Frame Cape Cod 4 KW 4    | 1.4                                      | 1.6                  |                           |
| 6  | Wood Frame Cape Cod 1 KW 5    | 1.5                                      | 1.4                  |                           |
| 7  | Masonry 1                     | 1.5                                      | 1.4                  |                           |
| 8  | Masonry 2                     | 1.6                                      | 1.4                  |                           |
| 9  | Masonry 3                     | 1.5                                      | 1.4                  |                           |
| 10 | Masonry 4                     | 1.5                                      | 1.4                  |                           |
| 11 | Masonry 5                     | 1.5                                      | 1.4                  |                           |
| 12 | Masonry 6                     | 1.3                                      | 1.3                  |                           |
| 13 | Row House Masonry 1           | 1.1                                      | 1.0                  |                           |
| 14 | Row House Masonry 2           | 1.1                                      | 1.0                  |                           |
| 15 | Row House Wood Frame 1        | 1.3                                      | 1.4                  |                           |
| 16 | Row House Wood Frame 2        | 1.3                                      | 1.2                  |                           |
| 17 | Semi Detached Masonry 1       | 1.5                                      | 1.4                  |                           |
| 18 | Semi Detached Masonry 2       | 1.5                                      | 1.5                  |                           |
| 19 | Semi Detached Wood Frame 1    | 1.3                                      | 1.4                  |                           |
| 20 | Semi Detached Wood Frame 2    | 1.4                                      | 1.3                  |                           |
| 21 | Wood Frm Cond Bsmt 1          | 1.4                                      | 1.4                  |                           |
| 22 | Wood Frm Cond Bsmt 2          | 1.4                                      | 1.4                  |                           |
| 23 | Wood Frm Cond Bsmt 3          | 1.4                                      | 1.4                  |                           |
| 24 | Wood Frm Cond Bsmt 4          | 1.3                                      | 1.3                  |                           |
| 25 | Wood Frm Slab 1               | 1.4                                      | 1.4                  |                           |
| 26 | Wood Frm Slab 2               | 1.4                                      | 1.4                  |                           |
| 27 | Wood Frm Slab 3               | 1.4                                      | 1.4                  |                           |
| 28 | Wood Frm Slab 4               | 1.4                                      | 1.4                  |                           |
| 29 | Wood Frm Uncon Bsmt 1         | 1.4                                      | 1.5                  |                           |
| 30 | Wood Frm Uncon Bsmt 2         | 1.5                                      | 1.4                  |                           |
| 31 | Wood Frm Uncon Bsmt 3         | 1.4                                      | 1.6                  |                           |
| 32 | Wood Frm Uncon Bsmt 4         | 1.4                                      | 1.6                  |                           |
| 33 | Wood Frm Uncon Bsmt 5         | 1.4                                      | 1.6                  |                           |
| 34 | Wood Frm Vented Crawl Space 1 | 1.4                                      | 1.6                  |                           |
| 35 | Wood Frm Vented Crawl Space 2 | 1.5                                      | 1.4                  |                           |
| 36 | Wood Frm Vented Crawl Space 3 | 1.4                                      | 1.6                  |                           |
| 37 | Wood Frm Vented Crawl Space 4 | 1.3                                      | 1.6                  |                           |
| 38 | Wood Frm Vented Crawl Space 5 | 1.4                                      | 1.6                  |                           |
| 39 | Wood Frm Vented Crawl Space 6 | 1.4                                      | 1.3                  |                           |
|    |                               |  |                      |                           |

| Single pane<br>wood/vinyl | Double pane<br>metal | Double pane<br>wood/vinyl |
|---------------------------|----------------------|---------------------------|
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.2                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.3                       | 1.2                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.4                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| 1.3                       | 1.3                  |                           |
| E-                        |                      |                           |

| Average SIR | 1.4 | 1.4 |  |
|-------------|-----|-----|--|
| Max SIR     | 1.6 | 1.6 |  |
| Min SIR     | 1.1 | 1.0 |  |

| 1.3          | 1.3         | -                                       |
|--------------|-------------|---|
| 1.4          | 1.3         |   |
| 1.3          | 1.2         |   |
| JID 1 1 1 CI | TED C 1 1 1 | 100000000000000000000000000000000000000 |

Slightly lower SIR because higher SEER for whole home AC (8 vs 6) yet still not much cooling

| Other metrics:<br>Wood Frame Vented Crawl Space home<br>Single pane wood windows |         |
|--|---------|
| Annual cost savings  | \$120   |
| Measure Cost   | \$1,386 |
| Simple Payback   | 11.6    |
| Energy Savings (Mbtu/yr)   |         |
| Initial home heat+cool   | 70.6    |
| Storm savings  | 14.2    |
| % reduction  | 20%     |

| Other metrics:<br>Wood Frame Vented Crawl Space I<br>Single pane wood windows | home    |
|---|---------|
| Annual cost savings   | \$119   |
| Measure Cost  | \$1,386 |
| Simple Payback  | 11.6    |
| Energy Savings (Mbtu/yr)  |         |
| Initial home heat+cool  | 76.4    |
| Storm savings   | 14.1    |
| % reduction   | 18%     |

if include 1/3 of air inf savings \$152 9.1

if include 1/3 of air inf savings

\$155

#### Denver CO Zone 5

 HDD65
 6020

 CDD50
 2732

 Natural Gas (\$/Mcf, 2012 avg)
 \$8.26

 Electricity (\$/kWh, 2012 avg)
 \$0.1139

 Low-e Storms \$7.85/ft2 + \$30/window

SIR with different primary window types:

|    |                               | Single pane | Double pane | Double pane |
|----|-------------------------------|-------------|-------------|-------------|
|    | Home type                     | wood/vinyl  | metal       | wood/vinyl  |
| 1  | Exposed Floor 1               | 1.4         | 1.4         |             |
| 2  | Wood Frame Cape Cod 1 KW 1    | 1.2         | 1.1         |             |
| 3  | Wood Frame Cape Cod 2 KW 2    | 1.3         | 1.5         |             |
| 4  | Wood Frame Cape Cod 3 KW 3    | 1.2         | 1.1         |             |
| 5  | Wood Frame Cape Cod 4 KW 4    | 1.4         | 1.1         |             |
| 6  | Wood Frame Cape Cod 1 KW 5    | 1.2         | 1.1         |             |
| 7  | Masonry 1                     | 1.4         | 1.3         |             |
| 8  | Masonry 2                     | 1.4         | 1.3         |             |
| 9  | Masonry 3                     | 1.4         | 1.3         |             |
| 10 | Masonry 4                     | 1.4         | 1.3         |             |
| 11 | Masonry 5                     | 1.2         | 1.2         |             |
| 12 | Masonry 6                     | 1.3         | 1.3         |             |
| 13 | Row House Masonry 1           | 1.2         | 1.1         |             |
| 14 | Row House Masonry 2           | 1.2         | 1.1         |             |
| 15 | Row House Wood Frame 1        | 1.1         | 1.1         |             |
| 16 | Row House Wood Frame 2        | 1.3         | 1.2         |             |
| 17 | Semi Detached Masonry 1       | 1.4         | 1.4         |             |
| 18 | Semi Detached Masonry 2       | 1.5         | 1.4         |             |
| 19 | Semi Detached Wood Frame 1    | 1.4         | 1.3         |             |
| 20 | Semi Detached Wood Frame 2    | 1.3         | 1.3         |             |
| 21 | Wood Frm Cond Bsmt 1          | 1.2         | 1.1         |             |
| 22 | Wood Frm Cond Bsmt 2          | 1.3         | 1.3         |             |
| 23 | Wood Frm Cond Bsmt 3          | 1.3         | 1.3         |             |
| 24 | Wood Frm Cond Bsmt 4          | 1.3         | 1.3         |             |
| 25 | Wood Frm Slab 1               | 1.4         | 1.3         |             |
| 26 | Wood Frm Slab 2               | 1.4         | 1.3         |             |
| 27 | Wood Frm Slab 3               | 1.4         | 1.3         |             |
| 28 | Wood Frm Slab 4               | 1.4         | 1.3         |             |
| 29 | Wood Frm Uncon Bsmt 1         | 1.2         | 1.1         |             |
| 30 | Wood Frm Uncon Bsmt 2         | 1.3         | 1.5         |             |
| 31 | Wood Frm Uncon Bsmt 3         | 1.3         | 1.5         |             |
| 32 | Wood Frm Uncon Bsmt 4         | 1.3         | 1.2         |             |
| 33 | Wood Frm Uncon Bsmt 5         | 1.3         | 1.3         |             |
| 34 | Wood Frm Vented Crawl Space 1 | 1.1         | 1.2         |             |
| 35 | Wood Frm Vented Crawl Space 2 | 1.3         | 1.5         |             |
| 36 | Wood Frm Vented Crawl Space 3 | 1.3         | 1.5         |             |
| 37 | Wood Frm Vented Crawl Space 4 | 1.3         | 1.2         |             |
| 38 | Wood Frm Vented Crawl Space 5 | 1.3         | 1.3         |             |
| 39 | Wood Frm Vented Crawl Space 6 | 1.2         | 1.1         |             |

Average SIR Max SIR Min SIR

| R | 1.3 | 1.3 |  |
|---|-----|-----|--|
| R | 1.5 | 1.5 |  |
| 2 | 1.1 | 1.1 |  |

| Other metrics: Wood Frame Vented Crawl Space home |       |
|---|-------|
| Single pane wood windows                          |       |
| Annual cost savings                               | \$70  |
| Measure Cost                                      | \$924 |
| Simple Payback                                    | 13.2  |
| Energy Savings (Mbtu/yr)                          |       |
| Initial home heat+cool                            | 60.7  |
| Storm savings                                     | 10.6  |
| % reduction                                       | 18%   |

if include 1/3 of air inf savings \$94

9.8

<-- adjusted for all 4 sides using 75% of savings for south not adjusted, it is 14%

#### Boise ID Zone 5

 HDD65
 5861

 CDD50
 2807

 Natural Gas (\$/Mcf, 2012 avg)
 \$8.37

 Electricity (\$/kWh, 2012 avg)
 \$0.0847

 Low-e Storms \$7.85/ft2 + \$30/window

SIR with different primary window types:

|    |                               | Single pane | Double pane | Double pane |
|----|-------------------------------|-------------|-------------|-------------|
|    | Home type                     | wood/vinyl  | metal       | wood/vinyl  |
| 1  | Exposed Floor 1               | 1.2         | 1.2         |             |
| 2  | Wood Frame Cape Cod 1 KW 1    | 1.3         | 1.3         |             |
| 3  | Wood Frame Cape Cod 2 KW 2    | 1.3         | 1.3         |             |
| 4  | Wood Frame Cape Cod 3 KW 3    | 1.3         | 1.3         |             |
| 5  | Wood Frame Cape Cod 4 KW 4    | 1.3         | 1.3         |             |
| 6  | Wood Frame Cape Cod 1 KW 5    | 1.4         | 1.3         |             |
| 7  | Masonry 1                     | 1.4         | 1.4         |             |
| 8  | Masonry 2                     | 1.5         | 1.2         |             |
| 9  | Masonry 3                     | 1.3         | 1.2         |             |
| 10 | Masonry 4                     | 1.4         | 1.4         |             |
| 11 | Masonry 5                     | 1.4         | 1.4         |             |
| 12 | Masonry 6                     | 1.3         | 1.2         |             |
| 13 | Row House Masonry 1           |             |             |             |
| 14 | Row House Masonry 2           |             |             |             |
| 15 | Row House Wood Frame 1        |             | 1.2         |             |
| 16 | Row House Wood Frame 2        | 1.3         | 1.2         |             |
| 17 | Semi Detached Masonry 1       | 1.5         | 1.4         |             |
| 18 | Semi Detached Masonry 2       | 1.5         | 1.4         |             |
| 19 | Semi Detached Wood Frame 1    | 1.2         | 1.2         |             |
| 20 | Semi Detached Wood Frame 2    | 1.3         | 1.2         |             |
| 21 | Wood Frm Cond Bsmt 1          | 1.3         | 1.2         |             |
| 22 | Wood Frm Cond Bsmt 2          | 1.3         | 1.2         |             |
| 23 | Wood Frm Cond Bsmt 3          | 1.3         | 1.2         |             |
| 24 | Wood Frm Cond Bsmt 4          | 1.3         | 1.2         |             |
| 25 | Wood Frm Slab 1               | 1.3         | 1.2         |             |
| 26 | Wood Frm Slab 2               | 1.3         | 1.2         |             |
| 27 | Wood Frm Slab 3               | 1.3         | 1.2         |             |
| 28 | Wood Frm Slab 4               | 1.2         | 1.2         |             |
| 29 | Wood Frm Uncon Bsmt 1         | 1.3         | 1.2         |             |
| 30 | Wood Frm Uncon Bsmt 2         | 1.2         | 1.3         |             |
| 31 | Wood Frm Uncon Bsmt 3         | 1.2         | 1.2         |             |
| 32 | Wood Frm Uncon Bsmt 4         | 1.2         | 1.2         |             |
| 33 | Wood Frm Uncon Bsmt 5         | 1.2         | 1.2         |             |
| 34 | Wood Frm Vented Crawl Space 1 | 1.2         | 1.2         |             |
| 35 | Wood Frm Vented Crawl Space 2 | 1.2         | 1.3         |             |
| 36 | Wood Frm Vented Crawl Space 3 | 1.2         | 1.2         |             |
| 37 | Wood Frm Vented Crawl Space 4 | 1.2         | 1.3         |             |
| 38 | Wood Frm Vented Crawl Space 5 | 1.2         | 1.2         |             |
| 39 | Wood Frm Vented Crawl Space 6 | 1.3         | 1.1         |             |

| Average SIR | 1.3 |
|-------------|-----|
| Max SIR     | 1.5 |
| Min SIR     | 1.2 |

| Other metrics:               |         |
|------------------------------|---------|
| Wood Frame Vented Crawl Spa- | ce home |
| Single pane wood windows     |         |
|                              |         |
| Annual cost savings          | \$75    |
| Measure Cost                 | \$924   |
| Simple Payback               | 12.3    |
|                              |         |
| Energy Savings (Mbtu/yr)     |         |

1.4 1.1

| Simple Payback           | 12.3 |
|--------------------------|------|
|                          |      |
| Energy Savings (Mbtu/yr) |      |
| Initial home heat+cool   | 60.5 |
|                          |      |
| Storm savings            | 10.8 |
| % reduction              | 18%  |

if include 1/3 of air inf savings \$100

9.2

<-- adjusted for all 4 sides using 75% of savings for south if not adjusted, it is 14%

#### New York NY Zone 4

HDD65 4805

 $\mbox{\bf Note:}$  fuel prices in NYC are actually higher than these state average, so this is conservative CDD50

3634

Natural Gas (\$/Mcf, 2011 avg) Electricity (\$/kWh, 2012 avg) \$13.71 (2012 avg not available) \$0.1769

Low-e Storms \$7.85/ft2 + \$30/window

SIR with different primary window types:

|    | · ·                           | SIR With t  | interent primary w | паон сурсы. |
|----|-------------------------------|-------------|--------------------|-------------|
|    |                               | Single pane | Double pane        | Double pane |
|    | Home type                     | wood/vinyl  | metal              | wood/vinyl  |
| 1  | Exposed Floor 1               | 2.1         | 2.0                | 1.4         |
| 2  | Wood Frame Cape Cod 1 KW 1    | 2.1         | 2.0                | 1.4         |
| 3  | Wood Frame Cape Cod 2 KW 2    | 2.1         | 2.0                | 1.4         |
| 4  | Wood Frame Cape Cod 3 KW 3    | 2.1         | 2.0                | 1.4         |
| 5  | Wood Frame Cape Cod 4 KW 4    | 2.1         | 2.0                | 1.4         |
| 6  | Wood Frame Cape Cod 1 KW 5    | 2.2         | 2.1                | 1.4         |
| 7  | Masonry 1                     | 2.2         | 2.1                | 1.4         |
| 8  | Masonry 2                     | 2.2         | 2.0                | 1.4         |
| 9  | Masonry 3                     | 2.2         | 2.1                | 1.4         |
| 10 | Masonry 4                     | 2.2         | 2.1                | 1.4         |
| 11 | Masonry 5                     | 2.2         | 2.1                | 1.4         |
| 12 | Masonry 6                     | 2.2         | 2.1                | 1.4         |
| 13 | Row House Masonry 1           | 1.7         | 1.6                | 1.2         |
| 14 | Row House Masonry 2           | 1.7         | 1.6                | 1.2         |
| 15 | Row House Wood Frame 1        | 2.0         | 2.0                | 1.3         |
| 16 | Row House Wood Frame 2        | 2.1         | 2.0                | 1.4         |
| 17 | Semi Detached Masonry 1       | 2.2         | 2.1                | 1.4         |
| 18 | Semi Detached Masonry 2       | 2.2         | 2.1                | 1.5         |
| 19 | Semi Detached Wood Frame 1    | 2.1         | 2.0                | 1.4         |
| 20 | Semi Detached Wood Frame 2    | 2.2         | 2.1                | 1.5         |
| 21 | Wood Frm Cond Bsmt 1          | 2.2         | 2.1                | 1.4         |
| 22 | Wood Frm Cond Bsmt 2          | 2.2         | 2.1                | 1.5         |
| 23 | Wood Frm Cond Bsmt 3          | 2.2         | 2.1                | 1.5         |
| 24 | Wood Frm Cond Bsmt 4          | 2.2         | 2.1                | 1.5         |
| 25 | Wood Frm Slab 1               | 2.2         | 2.1                | 1.5         |
| 26 | Wood Frm Slab 2               | 2.2         | 2.1                | 1.5         |
| 27 | Wood Frm Slab 3               | 2.2         | 2.1                | 1.5         |
| 28 | Wood Frm Slab 4               | 2.2         | 2.2                | 1.5         |
| 29 | Wood Frm Uncon Bsmt 1         | 2.1         | 2.0                | 1.4         |
| 30 | Wood Frm Uncon Bsmt 2         | 2.1         | 2.0                | 1.4         |
| 31 | Wood Frm Uncon Bsmt 3         | 2.1         | 2.0                | 1.4         |
| 32 | Wood Frm Uncon Bsmt 4         | 2.1         | 2.0                | 1.4         |
| 33 | Wood Frm Uncon Bsmt 5         | 2.1         | 2.0                | 1.4         |
| 34 | Wood Frm Vented Crawl Space 1 | 2.1         | 2.0                | 1.4         |
| 35 | Wood Frm Vented Crawl Space 2 | 2.1         | 2.0                | 1.4         |
| 36 | Wood Frm Vented Crawl Space 3 | 2.1         | 2.0                | 1.4         |
| 37 | Wood Frm Vented Crawl Space 4 | 2.1         | 2.1                | 1.4         |
| 38 | Wood Frm Vented Crawl Space 5 | 2.1         | 2.0                | 1.4         |
| 39 | Wood Frm Vented Crawl Space 6 | 2.2         | 2.1                | 1.4         |

2.1 2.0 Average SIR 1.4 1.5 1.2 Max SIR 2.2 2.2 Min SIR 1.6

| Other metrics:<br>Wood Frame Vented Crawl Space home<br>Single pane wood windows |         |
|--|---------|
| Annual cost savings  | \$194   |
| Measure Cost   | \$1,386 |
| Simple Payback   | 7.1     |
| Energy Savings (Mbtu/yr)   |         |
| Initial home heat+cool   | 61.6    |
| Storm savings  | 13.8    |
| % reduction  | 22%     |

if include 1/3 of air inf savings \$252

#### Washington DC

Zone 4

HDD65 CDD50 4047 4391 Natural Gas (\$/Mcf, 2011 avg) \$13.06

(2012 avg not available)

Electricity (\$/kWh, 2012 avg) \$0. Low-E Storms \$7.85/ft2 + \$30/window \$0.1227

Regular Low-E

On

| Only 400 ft2 room air conditioned       |
|---|
| CTD with different primary window types |

|                                  | SIR with different primary window types: |       |            |
|----------------------------------|--|-------|------------|
|                                  | Single pane   Double pane   Double pane  |       |            |
| Home type                        | wood/vinyl                               | metal | wood/vinyl |
| 1 Exposed Floor 1                | 1.4                                      | 1.3   |            |
| 2 Wood Frame Cape Cod 1 KW 1     | 1.3                                      | 1.3   |            |
| 3 Wood Frame Cape Cod 2 KW 2     | 1.4                                      | 1.3   |            |
| 4 Wood Frame Cape Cod 3 KW 3     | 1.3                                      | 1.3   |            |
| 5 Wood Frame Cape Cod 4 KW 4     | 1.4                                      | 1.3   |            |
| 6 Wood Frame Cape Cod 1 KW 5     | 1.4                                      | 1.3   |            |
| 7 Masonry 1                      | 1.4                                      | 1.3   |            |
| 8 Masonry 2                      | 1.4                                      | 1.3   |            |
| 9 Masonry 3                      | 1.4                                      | 1.3   |            |
| 10 Masonry 4                     | 1.4                                      | 1.3   |            |
| 11 Masonry 5                     | 1.4                                      | 1.4   |            |
| 12 Masonry 6                     | 1.4                                      | 1.3   |            |
| 13 Row House Masonry 1           | 1.3                                      | 1.3   |            |
| 14 Row House Masonry 2           | 1.3                                      | 1.3   |            |
| 15 Row House Wood Frame 1        | 1.3                                      | 1.2   |            |
| 16 Row House Wood Frame 2        | 1.3                                      | 1.3   |            |
| 17 Semi Detached Masonry 1       | 1.4                                      | 1.3   |            |
| 18 Semi Detached Masonry 2       | 1.4                                      | 1.3   |            |
| 19 Semi Detached Wood Frame 1    | 1.4                                      | 1.3   |            |
| 20 Semi Detached Wood Frame 2    | 1.4                                      | 1.3   |            |
| 21 Wood Frm Cond Bsmt 1          | 1.4                                      | 1.3   |            |
| 22 Wood Frm Cond Bsmt 2          | 1.4                                      | 1.3   |            |
| 23 Wood Frm Cond Bsmt 3          | 1.4                                      | 1.3   |            |
| 24 Wood Frm Cond Bsmt 4          | 1.4                                      | 1.3   |            |
| 25 Wood Frm Slab 1               | 1.4                                      | 1.4   |            |
| 26 Wood Frm Slab 2               | 1.4                                      | 1.4   |            |
| 27 Wood Frm Slab 3               | 1.4                                      | 1.4   |            |
| 28 Wood Frm Slab 4               | 1.5                                      | 1.4   |            |
| 29 Wood Frm Uncon Bsmt 1         | 1.4                                      | 1.3   |            |
| 30 Wood Frm Uncon Bsmt 2         | 1.4                                      | 1.3   |            |
| 31 Wood Frm Uncon Bsmt 3         | 1.4                                      | 1.3   |            |
| 32 Wood Frm Uncon Bsmt 4         | 1.4                                      | 1.3   |            |
| 33 Wood Frm Uncon Bsmt 5         | 1.4                                      | 1.3   |            |
| 34 Wood Frm Vented Crawl Space 1 |  | 1.3   |            |
| 35 Wood Frm Vented Crawl Space 2 |  | 1.3   |            |
| 36 Wood Frm Vented Crawl Space 3 |  | 1.3   |            |
| 37 Wood Frm Vented Crawl Space 4 |  | 1.3   |            |
| 38 Wood Frm Vented Crawl Space 5 |  | 1.3   |            |
| 39 Wood Frm Vented Crawl Space 6 | 1.5                                      | 1.4   |            |
|                                  |  |       |            |

| Average SIR | 1.4 | 1.3 | - |
|-------------|-----|-----|---|
| Max SIR     | 1.5 | 1.4 |   |
| Min SIR     | 1.3 | 1.2 |   |

| Wood Frame Vented Crawl Sp.<br>Single pane wood windows | ace home | if include 1<br>of air inf<br>savings |
|---|----------|---------------------------------------|
| Annual cost savings                                     | \$126    | \$161.67                              |
| Measure Cost  | \$1,386  |                                       |
| Simple Payback  | 11.0     | 8.6                                   |
|   |          |                                       |
| Energy Savings (Mbtu/yr)                                |          |                                       |
| Initial home heat+cool                                  | 47.0     |                                       |
| Storm savings   | 9.3      |                                       |
| % reduction   | 20%      |                                       |
|   |          |                                       |

| f include 1/3<br>of air inf<br>savings | Other metrics:<br>Wood Frame Vented Crawl Space home<br>Single pane wood windows |         |  |
|--|--|---------|--|
| \$161.67                               | Annual cost savings  | \$140   |  |
|  | Measure Cost   | \$1,386 |  |
| 8.6                                    | Simple Payback   | 9.9     |  |
|  |  |         |  |
|  | Energy Savings (Mbtu/yr)   |         |  |
|  | Initial home heat+cool   | 54.7    |  |
|  | Storm savings  | 9.7     |  |
|  | % reduction  | 18%     |  |
|  | Site energy  |         |  |

Regular Low-E

wood/vinyl

1.5

1.5 1.5

1.5 1.6

1.6

1.6

1.6

1.6

1.6 1.5

1.5 1.4

1.5

1.5 1.6 1.4 1.5

1.6

1.6

1.6

1.6

1.6

1.6 1.6

1.6

1.6 1.5 1.5 1.5 1.6 1.5

1.5

1.5

1.5

1.6

1.6

1.5 1.7

1.4

Whole home air conditioned

SIR with different primary window types: Single pane | Double pane | Double pane

metal

1.5

1.4

1.4

1.4 1.6

1.6

1.5

1.5

1.6

1.6

1.6

1.5

1.4

1.4

1.5

1.5 1.6

1.4

1.5

1.6

1.5

1.5

1.5

1.6

1.5

1.5

1.5

1.5

1.5

1.5

1.5

1.5

1.5

1.5

1.5

1.5

1.5

1.5

1.6

1.4

wood/vinyl

1.2

1.1

1.1

1.1 1.1

1.1

1.1

1.1

1.1

1.2

1.1

1.0

1.1

1.1

1.1 1.1

1.1

1.0

1.1

1.1

1.1

1.1

1.1

1.1

1.1

1.1

1.1

1.1

1.1

1.2

1.2

1.1

1.1

1.1

1.1

1.1

1.1

1.2

| -                                       |
|---|
| if include 1/3<br>of air inf<br>savings |
| \$178                                   |
|   |
| 7.8                                     |
|   |
|   |
|   |

#### Solar Control Low-E Whole home air conditioned

| SIR with different primary window type |            |            |  |
|--|------------|------------|--|
| Single pane                            | Double     | pane       |  |
| wood/vinyl                             | pane metal | wood/vinyl |  |
| 1.7                                    | 1.7        | 1.2        |  |
| 1.7                                    | 1.7        | 1.2        |  |
| 1.6                                    | 1.5        | 1.1        |  |
| 1.6                                    | 1.5        | 1.1        |  |
| 1.6                                    | 1.5        | 1.1        |  |
| 1.7                                    | 1.7        | 1.3        |  |
| 1.7                                    | 1.7        | 1.3        |  |
| 1.6                                    | 1.6        | 1.2        |  |
| 1.7                                    | 1.6        | 1.2        |  |
| 1.7                                    | 1.7        | 1.3        |  |
| 1.7                                    | 1.7        | 1.3        |  |
| 1.7                                    | 1.6        | 1.2        |  |
| 1.5                                    | 1.4        | 1.1        |  |
| 1.5                                    | 1.4        | 1.1        |  |
| 1.4                                    | 1.4        | 1.0        |  |
| 1.5                                    | 1.4        | 1.1        |  |
| 1.6                                    | 1.5        | 1.1        |  |
| 1.6                                    | 1.5        | 1.2        |  |
| 1.5                                    | 1.5        | 1.1        |  |
| 1.5                                    | 1.5        | 1.1        |  |
| 1.7                                    | 1.7        | 1.3        |  |
| 1.6                                    | 1.6        | 1.2        |  |
| 1.6                                    | 1.6        | 1.2        |  |
| 1.6                                    | 1.6        | 1.2        |  |
| 1.7                                    | 1.7        | 1.3<br>1.2 |  |
| 1.6                                    | 1.6        |            |  |
| 1.6                                    | 1.6        | 1.2        |  |
| 1.6<br>1.7                             | 1.6<br>1.7 | 1.2<br>1.3 |  |
| 1.6                                    | 1.5        | 1.2        |  |
| 1.6                                    | 1.5        | 1.2        |  |
| 1.7                                    | 1.7        | 1.2        |  |
| 1.7                                    | 1.7        | 1.3        |  |
| 1.7                                    | 1.7        | 1.2        |  |
| 1.6                                    | 1.7        | 1.2        |  |
| 1.6                                    | 1.5        | 1.2        |  |
| 1.6                                    | 1.5        | 1.2        |  |
| 1.7                                    | 1.7        | 1.3        |  |
| 1.6                                    | 1.6        | 1.2        |  |
| 1.0                                    | 1.0        | 1.2        |  |

| 1.6 | 1.6 | 1.2 |
|-----|-----|-----|
| 1.7 | 1.7 | 1.3 |
| 1.4 | 1.4 | 1   |

|   | Other metrics:              |                      |
|---|-----------------------------|----------------------|
| 3 | Wood Frame Vented Crawl Spa | ce home              |
|   | Single pane wood windows    |                      |
|   | 31,11                       |                      |
|   | Annual cost savings         | \$149                |
|   | Measure Cost                | \$1,386              |
|   | Simple Payback              | 9.3                  |
|   |                             |                      |
|   | Energy Savings (Mbtu/yr)    |                      |
|   | Initial home heat+cool      | 54.7                 |
|   | Storm savings               | 9.0                  |
|   | % reduction                 | 16%                  |
|   | 1                           | January and American |

if include 1/3

of air inf

savings

\$187

7.4

Lower site energy % savings, but slightly higher SIR because cost diff

#### Raleigh NC

Home type Exposed Floor 1

Masonry 1 Masonry 2

Masonry 3

Masonry 4

Masonry 5

Masonry 6

Row House Masonry 1

Row House Masonry 2 Row House Wood Frame 1

Row House Wood Frame 2

Semi Detached Masonry 1 Semi Detached Masonry 2

Semi Detached Wood Frame 1

2

8 Q

10

11

12

13

14

15

16 17

19

20

21

22

23

24

25

26

27

28

29

30

Zone 4

HDD65 3457 CDD50 4499

Natural Gas (\$/Mcf, 2011 avg) \$12.55 \$0.1081

Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window

Wood Frame Cape Cod 1 KW 1 Wood Frame Cape Cod 2 KW 2 Wood Frame Cape Cod 3 KW 3 Wood Frame Cape Cod 4 KW 4 Wood Frame Cape Cod 1 KW 5 (2012 avg not available)

\$1.227

per therm

#### NG furnace, central AC with standard Low-e

SIR with different primary window types:

| SIR with different primary window types: |                      |                           |  |
|--|----------------------|---------------------------|--|
| Single pane<br>wood/vinyl                | Double pane<br>metal | Double pane<br>wood/vinyl |  |
| 1.1                                      | 1.2                  |                           |  |
| 1.1                                      | 1.2                  |                           |  |
| 1.1                                      | 1.2                  |                           |  |
| 1.1                                      | 1.2                  |                           |  |
| 1.1                                      | 1.2                  |                           |  |
| 1.2                                      | 1.2                  |                           |  |
| 1.2                                      | 1.1                  |                           |  |
| 1.2                                      | 1.1                  |                           |  |
| 1.2                                      | 1.1                  |                           |  |
| 1.2                                      | 1.2                  |                           |  |
| 1.2                                      | 1.2                  |                           |  |
| 1.2                                      | 1.2                  |                           |  |
| 1.1                                      | 1.1                  |                           |  |
| 1.1                                      | 1.1                  |                           |  |
| 1.0                                      | 1.0                  |                           |  |
| 1.1                                      | 1.1                  |                           |  |
| 1.2                                      | 1.1                  |                           |  |
|  |                      |                           |  |

1.2

1.1

1.2

1.3

1.1

1.1

1.2

12

1.2

1.1

1.1

1.1

1.2

----

Semi Detached Wood Frame 2 1.1 1.1 Wood Frm Cond Bsmt 1 1.2 1.2 Wood Frm Cond Bsmt 2 1.2 1.1 Wood Frm Cond Bsmt 3 1.2 1.1 Wood Frm Cond Bsmt 4 1.2 1.1 Wood Frm Slab 1 1.2 1.2 Wood Frm Slab 2 12 12 Wood Frm Slab 3 1.2 1.2

1.2

1.1

1.2

1.2

1.1

1.1

1.2

12

1.1

1.1

1.1

1.1

1.2

Othe

31 Wood Frm Uncon Bsmt 3 Wood Frm Uncon Bsmt 4 Wood Frm Uncon Bsmt 5 33 34 Wood Frm Vented Crawl Space 1 35 Wood Frm Vented Crawl Space 2 36 Wood Frm Vented Crawl Space 3

Wood Frm Slab 4

Wood Frm Uncon Bsmt 1

Wood Frm Uncon Bsmt 2

37 Wood Frm Vented Crawl Space 4 38 Wood Frm Vented Crawl Space 5 39 Wood Frm Vented Crawl Space 6

> Average SIR Max SIR Min SIR

| 1.2 | 1.2 |  |
|-----|-----|--|
| 1.2 | 1.3 |  |
| 1.0 | 1.0 |  |

Woo Singl Annı Meas Simp Energ

Initia Storn % re NG furnace, central AC with Solar Control Low-e

SIR with different primary window types:

|             | fferent primary wi |             |
|-------------|--------------------|-------------|
| Single pane | Double pane        | Double pane |
| wood/vinyl  | metal              | wood/vinyl  |
| 1.3         | 1.3                | 1.0         |
| 1.3         | 1.3                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.3                | 1.0         |
| 1.3         | 1.2                | 1.0         |
| 1.3         | 1.2                | 1.0         |
| 1.3         | 1.2                | 1.0         |
| 1.3         | 1.2                | 1.0         |
| 1.3         | 1.4                | 1.0         |
| 1.3         | 1.4                | 1.0         |
| 1.2         | 1.1                |             |
| 1.2         | 1.2                |             |
| 1.1         | 1.1                |             |
| 1.2         | 1.2                |             |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.4                |             |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.2                |             |
| 1.3         | 1.3                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.5         | 1.5                |             |
| 1.4         | 1.4                | 1.0         |
| 1.4         | 1.4                |             |
| 1.4         | 1.4                |             |
| 1.3         | 1.3                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.3         | 1.3                | 1.0         |
| 1.3         | 1.3                | 1.0         |
| 1.3         | 1.3                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.2         | 1.2                | 1.0         |
| 1.3         | 1.3                | 1.0         |
| 1.3         | 1.2                | 1.0         |
| 1.3         | 1,2                | 1.0         |

| 1.3 | 1.3 | 1.0 |
|-----|-----|-----|
| 1.5 | 1.5 | 1.0 |
| 1.1 | 1.1 | 1.0 |

Often only specify east / west

| r metrics:<br>d Frame Vented Crawl Space home<br>le pane wood windows |         | i |
|---|---------|---|
| ual cost savings  | \$103   |   |
| sure Cost   | \$1,386 |   |
| ole Payback   | 13.5    |   |
| Carrier of Office (con)   |         |   |
| gy Savings (Mbtu/yr)  |         |   |
| al home heat+cool   | 45.3    |   |
| n savings   | 7.4     |   |
| eduction  | 16%     | 1 |

if include 1/3 savings \$130 10.6

| Other metrics:<br>Wood Frame Vented Crawl Space | home    |
|---|---------|
| Single pane wood windows                        |         |
| Annual cost savings                             | \$113   |
| Measure Cost                                    | \$1,386 |
| Simple Payback                                  | 12.3    |
|   |         |
| Energy Savings (Mbtu/yr)                        |         |
| Initial home heat+cool                          | 45.3    |
| Storm savings                                   | 7.1     |
| % reduction                                     | 16%     |

if include 1/3 of air inf savings \$140 9.9

#### Kansas City MO

Zone 4

HDD65 5393 CDD50 3852 Natural Gas (\$/Mcf, 2012 avg) \$12.31 \$0.1007

Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window per therm

\$1.203

#### Only 400 ft2 room air conditioned

SIR with different primary window types:

| Home type  |    |                               | SIK WITH UI | nerent primary wi | nuon types. |
|--|----|-------------------------------|-------------|-------------------|-------------|
| 2 Wood Frame Cape Cod 1 KW 1 3 Wood Frame Cape Cod 2 KW 2 4 Wood Frame Cape Cod 3 KW 3 5 Wood Frame Cape Cod 4 KW 4 1.5 1.4 6 Wood Frame Cape Cod 4 KW 5 1.5 1.4 7 Masonry 1 1.5 1.4 8 Masonry 2 1.5 1.4 1.1 8 Masonry 2 1.5 1.4 1.0 9 Masonry 3 1.4 1.4 1.0 10 Masonry 4 1.5 1.4 1.1 11 Masonry 5 1.5 1.4 1.1 11 Masonry 6 1.4 1.4 1.0 13 Row House Masonry 1 14 Row House Masonry 1 15 Row House Masonry 2 15 Row House Masonry 1 16 Row House Wood Frame 1 17 Semi Detached Masonry 1 18 Semi Detached Masonry 1 19 Semi Detached Masonry 1 10 Semi Detached Wood Frame 2 11.5 1.4 1.1 12 Wood Fram Cape Cod 1 KW 5 1.5 1.4 1.1 13 1.0 15 Row House Wood Frame 1 1.5 1.4 1.3 1.0 16 Row House Wood Frame 2 1.5 1.4 1.1 17 Semi Detached Wood Frame 1 1.5 1.4 1.1 18 Semi Detached Wood Frame 1 1.5 1.4 1.1 20 Semi Detached Wood Frame 2 21 1.5 1.4 1.1 21 Wood Fram Cond Bsmt 1 22 Wood Fram Cond Bsmt 1 23 Wood Fram Cond Bsmt 1 24 Wood Fram Cond Bsmt 4 25 Wood Fram Slab 1 26 Wood Fram Slab 1 27 Wood Fram Slab 1 28 Wood Fram Slab 4 29 Wood Fram Slab 4 29 Wood Fram Slab 4 20 Wood Fram Slab 4 21.5 1.5 1.1 21.0 1.1 22 Wood Fram Slab 3 23 1.5 1.5 1.1 24 Wood Fram Cond Bsmt 1 25 Wood Fram Slab 4 26 Wood Fram Slab 3 27 Wood Fram Slab 4 28 Wood Fram Slab 4 29 Wood Fram Slab 4 20 Wood Fram Slab 4 21 1.5 1.5 1.1 21 1.0 22 Wood Fram Slab 3 23 1.5 1.5 1.1 24 Wood Fram Slab 4 25 1.5 1.5 1.1 26 Wood Fram Slab 4 27 Wood Fram Slab 4 28 Wood Fram Slab 4 29 Wood Fram Slab 4 30 Wood Fram Uncon Bsmt 1 31 1.5 1.4 1.0 31 Wood Fram Uncon Bsmt 5 32 Wood Fram Uncon Bsmt 5 33 1.5 1.4 1.0 34 Wood Fram Vented Crawl Space 3 35 1.5 1.4 1.0 36 Wood Fram Vented Crawl Space 3 37 1.5 1.4 1.0 38 Wood Fram Vented Crawl Space 3 31 1.5 1.4 1.0  |    | Home type                     |             |                   |             |
| 3 Wood Frame Cape Cod 2 KW 2 4 Wood Frame Cape Cod 3 KW 3 5 Wood Frame Cape Cod 4 KW 4 1.5 1.4 6 Wood Frame Cape Cod 4 KW 5 1.5 1.4 7 Masonry 1 1.5 1.4 1.1 8 Masonry 2 1.5 1.4 1.0 9 Masonry 3 1.4 1.4 1.0 10 Masonry 4 1.5 1.4 1.1 11 Masonry 5 1.5 1.4 1.1 11 Masonry 6 1.4 1.4 1.1 12 Masonry 1 1.5 1.4 1.1 13 1.0 14 Row House Masonry 1 1.5 1.4 1.3 1.0 15 Row House Masonry 2 1.4 1.3 1.0 16 Row House Wood Frame 1 17 Semi Detached Masonry 1 18 Semi Detached Masonry 1 19 Semi Detached Moof Frame 1 10 Semi Detached Wood Frame 1 11 Semi Detached Wood Frame 2 11 Semi Detached Wood Frame 2 11 Semi Detached Wood Frame 2 11 Semi Detached Moof Frame 2 11 Semi Detached Wood Frame 2 12 Wood Frm Cond Bsmt 1 13 Semi Detached Wood Frame 2 14 Semi Detached Wood Frame 2 15 Semi Detached Wood Frame 2 16 Semi Detached Wood Frame 2 17 Semi Detached Wood Frame 2 18 Semi Detached Wood Frame 2 19 Semi Detached Wood Frame 2 10 Semi Detached Wood Frame 2 11 Semi Detached Wood Frame 2 12 Semi Detached Wood Frame 2 13 Semi Detached Wood Frame 2 14 Semi Detached Wood Frame 2 15 Semi Detached Wood Frame 2 16 Semi Detached Wood Frame 2 17 Semi Detached Wood Frame 2 18 Semi Detached Wood Frame 2 19 Semi Detached Wood Frame 2 10 Semi Detached Wo | 1  | Exposed Floor 1               | 1.5         | 1.4               | 1.0         |
| 4 Wood Frame Cape Cod 3 KW 3 5 Wood Frame Cape Cod 4 KW 4 6 Wood Frame Cape Cod 1 KW 5 7 Masonry 1 1.5 1.5 1.4 1.7 7 Masonry 1 1.5 1.5 1.4 1.1 1.0 9 Masonry 3 1.4 1.5 1.4 1.1 1.0 10 Masonry 4 1.5 1.5 1.4 1.1 11 Masonry 5 1.5 1.4 1.1 11 Masonry 5 1.5 1.4 1.1 11 Masonry 6 1.4 1.4 1.0 13 Row House Masonry 1 14 14 1.3 1.0 15 16 Row House Mood Frame 1 17 17 Semi Detached Masonry 2 18 Semi Detached Masonry 2 19 Semi Detached Wood Frame 2 19 Semi Detached Wood Frame 1 10 Semi Detached Wood Frame 1 11.5 11.4 11.1 12 Wood Fram Cond Bsmt 1 11.5 11.4 11.1 12 Wood Fram Cond Bsmt 2 11.5 11.4 11.1 11.6 11.6 11.6 11.6 11.6 11.6  | 2  | Wood Frame Cape Cod 1 KW 1    | 1.5         | 1.4               |             |
| 5         Wood Frame Cape Cod 4 KW 4         1.5         1.4            6         Wood Frame Cape Cod 1 KW 5         1.5         1.4            7         Masonry 1         1.5         1.4         1.1           8         Masonry 2         1.5         1.4         1.0           9         Masonry 3         1.4         1.4         1.0           10         Masonry 4         1.5         1.4         1.1           11         Masonry 5         1.5         1.4         1.1           12         Masonry 6         1.4         1.4         1.0           13         Row House Masonry 1         1.4         1.3         1.0           14         Row House Wood Frame 1         1.4         1.3         1.0           15         Row House Wood Frame 2         1.4         1.3         1.0           15         Row House Wood Frame 1         1.4         1.3         1.0           15         Row House Wood Frame 2         1.4         1.3         1.0           15         Row House Wood Frame 1         1.5         1.4         1.1           18         Semi Detached Masonry 2         1.5         1.4         1.1   | 3  | Wood Frame Cape Cod 2 KW 2    | 1.5         | 1.4               |             |
| 6         Wood Frame Cape Cod 1 KW 5         1.5         1.4            7         Masonry 1         1.5         1.4         1.1           8         Masonry 2         1.5         1.4         1.0           9         Masonry 3         1.4         1.4         1.0           10         Masonry 4         1.5         1.4         1.1           11         Masonry 5         1.5         1.4         1.1           12         Masonry 6         1.4         1.4         1.0           13         Row House Masonry 1         1.4         1.3         1.0           14         Row House Masonry 2         1.4         1.3         1.0           15         Row House Wood Frame 1         1.4         1.3         1.0           16         Row House Wood Frame 2         1.4         1.3         1.0           17         Semi Detached Masonry 1         1.5         1.4         1.1           18         Semi Detached Masonry 2         1.5         1.4         1.1           19         Semi Detached Wood Frame 1         1.5         1.4         1.1           20         Semi Detached Wood Frame 1         1.5         1.4         1.1   | 4  | Wood Frame Cape Cod 3 KW 3    | 1.5         | 1.4               |             |
| 7         Masonry 1         1.5         1.4         1.1           8         Masonry 2         1.5         1.4         1.0           9         Masonry 3         1.4         1.4         1.0           10         Masonry 4         1.5         1.4         1.1           11         Masonry 5         1.5         1.4         1.1           12         Masonry 6         1.4         1.4         1.0           13         Row House Masonry 1         1.4         1.3         1.0           14         Row House Masonry 2         1.4         1.3         1.0           15         Row House Wood Frame 1         1.4         1.3         1.0           15         Row House Wood Frame 2         1.4         1.3         1.0           15         Row House Wood Frame 2         1.4         1.3         1.0           15         Row House Wood Frame 2         1.4         1.3         1.0           15         Row House Wood Frame 2         1.4         1.3         1.0           15         Row House Wood Frame 2         1.5         1.4         1.1           16         Row House Wood Frame 2         1.5         1.4         1.1   | 5  | Wood Frame Cape Cod 4 KW 4    | 1.5         | 1.4               |             |
| 8         Masonry 2         1.5         1.4         1.0           9         Masonry 3         1.4         1.4         1.0           10         Masonry 4         1.5         1.4         1.1           11         Masonry 5         1.5         1.4         1.1           12         Masonry 6         1.4         1.4         1.0           13         Row House Masonry 1         1.4         1.3         1.0           14         Row House Masonry 2         1.4         1.3         1.0           15         Row House Wood Frame 1         1.4         1.3         1.0           15         Row House Wood Frame 1         1.4         1.3         1.0           15         Row House Wood Frame 1         1.4         1.3         1.0           15         Row House Wood Frame 2         1.4         1.3         1.0           16         Row House Wood Frame 1         1.5         1.4         1.1           18         Semi Detached Masonry 2         1.5         1.4         1.1           19         Semi Detached Masonry 2         1.5         1.4         1.1           20         Semi Detached Wood Frame 1         1.5         1.4   | 6  | Wood Frame Cape Cod 1 KW 5    | 1.5         | 1.4               |             |
| 9 Masonry 3 1.4 1.0 10 Masonry 4 1.5 1.5 1.4 1.1 11 Masonry 5 1.5 1.4 1.1 12 Masonry 6 1.4 1.4 1.4 1.0 13 10 14 Row House Masonry 1 14 1.3 1.0 15 Row House Masonry 2 1.4 1.5 16 Row House Wood Frame 1 17 16 Row House Wood Frame 2 18 Semi Detached Masonry 1 19 Semi Detached Masonry 1 10 Semi Detached Masonry 2 11.5 11.5 11.4 11.1 11.1 12.5 13.6 14.7 15.7 16.7 16.7 16.7 17 18 Semi Detached Masonry 1 19 Semi Detached Masonry 1 10 Semi Detached Masonry 2 11.5 11.5 11.4 11.1 11.1 12.5 12.6 13.6 14.7 15.7 15.7 14.7 15.7 15.7 16.7 16.7 17 18 Semi Detached Wood Frame 1 19 Semi Detached Wood Frame 1 19 Semi Detached Wood Frame 1 19 Semi Detached Wood Frame 2 19 Semi Detached Wood Frame 2 19 Semi Detached Wood Frame 2 10 Semi Detached Wood Frame 2 11.5 11.5 11.6 11.7 11.7 11.7 11.7 11.7 11.7 11.7   | 7  | Masonry 1                     | 1.5         | 1.4               | 1.1         |
| 10       Masonry 4       1.5       1.4       1.1         11       Masonry 5       1.5       1.4       1.1         12       Masonry 6       1.4       1.4       1.0         13       Row House Masonry 1       1.4       1.3       1.0         14       Row House Wood Frame 1       1.4       1.3       1.0         15       Row House Wood Frame 1       1.4       1.3       1.0         16       Row House Wood Frame 2       1.4       1.3       1.0         17       Semi Detached Masonry 1       1.5       1.4       1.1         18       Semi Detached Masonry 2       1.5       1.4       1.1         19       Semi Detached Wood Frame 1       1.5       1.4       1.1         19       Semi Detached Wood Frame 2       1.5       1.4       1.1         20       Semi Detached Wood Frame 2       1.5       1.4       1.1         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Slab 1       1.5       1   | 8  | Masonry 2                     | 1.5         | 1.4               | 1.0         |
| 11       Masonry 5       1.5       1.4       1.1         12       Masonry 6       1.4       1.4       1.0         13       Row House Masonry 1       1.4       1.3       1.0         14       Row House Wood Frame 1       1.4       1.3       1.0         15       Row House Wood Frame 1       1.4       1.3       1.0         16       Row House Wood Frame 2       1.4       1.3       1.0         17       Semi Detached Masonry 1       1.5       1.4       1.1         18       Semi Detached Masonry 2       1.5       1.4       1.1         19       Semi Detached Wood Frame 1       1.5       1.4       1.1         19       Semi Detached Wood Frame 2       1.5       1.4       1.1         20       Semi Detached Wood Frame 2       1.5       1.4       1.1         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Slab 1       1.5  | 9  | Masonry 3                     | 1.4         | 1.4               | 1.0         |
| 12     Masonry 6     1.4     1.4     1.0       13     Row House Masonry 1     1.4     1.3     1.0       14     Row House Wood Frame 1     1.4     1.3     1.0       15     Row House Wood Frame 1     1.4     1.3     1.0       16     Row House Wood Frame 2     1.4     1.3     1.0       17     Semi Detached Masonry 1     1.5     1.4     1.1       18     Semi Detached Masonry 2     1.5     1.4     1.1       19     Semi Detached Wood Frame 1     1.5     1.4     1.1       20     Semi Detached Wood Frame 2     1.5     1.4     1.1       21     Wood Frm Cond Bsmt 1     1.5     1.4     1.1       22     Wood Frm Cond Bsmt 2     1.5     1.4     1.1       21     Wood Frm Cond Bsmt 3     1.5     1.5     1.1       24     Wood Frm Cond Bsmt 4     1.5     1.5     1.1       25     Wood Frm Slab 1     1.5     1.5     1.1       26     Wood Frm Slab 2     1.5     1.5     1.1       27     Wood Frm Slab 3     1.5     1.5     1.1       28     Wood Frm Slab 4     1.5     1.5     1.1       29     Wood Frm Uncon Bsmt 1     1.5     <   | 10 | Masonry 4                     | 1.5         | 1.4               | 1.1         |
| 13       Row House Masonry 1       1.4       1.3       1.0         14       Row House Masonry 2       1.4       1.3       1.0         15       Row House Wood Frame 1       1.4       1.3       1.0         16       Row House Wood Frame 2       1.4       1.3       1.0         17       Semi Detached Masonry 1       1.5       1.4       1.1         18       Semi Detached Masonry 2       1.5       1.4       1.1         19       Semi Detached Wood Frame 1       1.5       1.4       1.1         20       Semi Detached Wood Frame 2       1.5       1.4       1.1         20       Semi Detached Wood Frame 2       1.5       1.4       1.1         20       Semi Detached Wood Frame 2       1.5       1.4       1.1         20       Semi Detached Wood Frame 2       1.5       1.4       1.1         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Slab 1       1.5       1.5       1.1         25  | 11 | Masonry 5                     | 1.5         | 1.4               | 1.1         |
| 14     Row House Masonry 2     1.4     1.3     1.0       15     Row House Wood Frame 1     1.4     1.3        16     Row House Wood Frame 2     1.4     1.3     1.0       17     Semi Detached Masonry 1     1.5     1.4     1.1       18     Semi Detached Masonry 2     1.5     1.4     1.1       19     Semi Detached Wood Frame 1     1.5     1.4        20     Semi Detached Wood Frame 2     1.5     1.4     1.2       21     Wood Frm Cond Bsmt 1     1.5     1.4     1.1       22     Wood Frm Cond Bsmt 2     1.5     1.4     1.1       23     Wood Frm Cond Bsmt 3     1.5     1.5     1.4     1.1       24     Wood Frm Cond Bsmt 4     1.5     1.5     1.1       25     Wood Frm Cond Bsmt 4     1.5     1.5     1.1       26     Wood Frm Slab 1     1.5     1.5     1.1       26     Wood Frm Slab 2     1.5     1.5     1.1       27     Wood Frm Slab 3     1.5     1.5     1.1       28     Wood Frm Slab 4     1.5     1.5     1.1       29     Wood Frm Uncon Bsmt 2     1.5     1.5     1.1       30     Wood Frm Uncon Bsmt 3 <td>12</td> <td>Masonry 6</td> <td>1.4</td> <td>1.4</td> <td>1.0</td>   | 12 | Masonry 6                     | 1.4         | 1.4               | 1.0         |
| 15       Row House Wood Frame 1       1.4       1.3          16       Row House Wood Frame 2       1.4       1.3       1.0         17       Semi Detached Masonry 1       1.5       1.4       1.1         18       Semi Detached Masonry 2       1.5       1.4       1.1         19       Semi Detached Wood Frame 1       1.5       1.4       1.1         20       Semi Detached Wood Frame 2       1.5       1.4       1.2         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Slab 1       1.5       1.4       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.5       1.1         30       Wood Frm Uncon Bsmt 2       1.5   | 13 | Row House Masonry 1           | 1.4         | 1.3               | 1.0         |
| 16       Row House Wood Frame 2       1.4       1.3       1.0         17       Semi Detached Masonry 1       1.5       1.4       1.1         18       Semi Detached Masonry 2       1.5       1.4       1.1         19       Semi Detached Wood Frame 1       1.5       1.4       1.2         20       Semi Detached Wood Frame 2       1.5       1.4       1.2         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         26       Wood Frm Slab 1       1.5       1.5       1.1         26       Wood Frm Slab 3       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.5       1.1         30       Wood Frm Uncon Bsmt 2       1.5  | 14 | Row House Masonry 2           | 1.4         | 1.3               | 1.0         |
| 17       Semi Detached Masonry 1       1.5       1.4       1.1         18       Semi Detached Masonry 2       1.5       1.4       1.1         19       Semi Detached Wood Frame 1       1.5       1.4          20       Semi Detached Wood Frame 2       1.5       1.4       1.2         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         26       Wood Frm Slab 1       1.5       1.5       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5   | 15 | Row House Wood Frame 1        | 1.4         | 1.3               |             |
| 18       Semi Detached Masonry 2       1.5       1.4       1.1         19       Semi Detached Wood Frame 1       1.5       1.4          20       Semi Detached Wood Frame 2       1.5       1.4       1.2         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         26       Wood Frm Slab 1       1.5       1.4       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5   | 16 | Row House Wood Frame 2        | 1.4         | 1.3               | 1.0         |
| 19       Semi Detached Wood Frame 1       1.5       1.4          20       Semi Detached Wood Frame 2       1.5       1.4       1.2         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         26       Wood Frm Slab 1       1.5       1.4       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5       1.4       1.0         34       Wood Frm Uncon Bsmt 5       1.5       <   | 17 | Semi Detached Masonry 1       | 1.5         | 1.4               | 1.1         |
| 20       Semi Detached Wood Frame 2       1.5       1.4       1.2         21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Slab 1       1.5       1.4       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.5       1.1         30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5       1.4       1.0         33       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         35       Wood Frm Vented Crawl Space 1       1.5   | 18 | Semi Detached Masonry 2       | 1.5         | 1.4               | 1.1         |
| 21       Wood Frm Cond Bsmt 1       1.5       1.4       1.1         22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Slab 1       1.5       1.4       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5       1.4       1.0         33       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Vented Crawl Space 1       1.5       1.4       1.0         36       Wood Frm Vented Crawl Space 2       1.5   | 19 | Semi Detached Wood Frame 1    | 1.5         | 1.4               |             |
| 22       Wood Frm Cond Bsmt 2       1.5       1.4       1.1         23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Slab 1       1.5       1.4       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5       1.4       1.0         33       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Vented Crawl Space 1       1.5       1.4       1.0         35       Wood Frm Vented Crawl Space 2       1.5       1.4       1.0         36       Wood Frm Vented Crawl Space 3 <td< td=""><td>20</td><td>Semi Detached Wood Frame 2</td><td>1.5</td><td>1.4</td><td>1.2</td></td<>  | 20 | Semi Detached Wood Frame 2    | 1.5         | 1.4               | 1.2         |
| 23       Wood Frm Cond Bsmt 3       1.5       1.5       1.1         24       Wood Frm Cond Bsmt 4       1.5       1.5       1.1         25       Wood Frm Slab 1       1.5       1.4       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5       1.4       1.0         33       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Vented Crawl Space 1       1.5       1.4       1.0         35       Wood Frm Vented Crawl Space 2       1.5       1.4       1.0         36       Wood Frm Vented Crawl Space 3       1.5       1.4       1.0         37       Wood Frm Vented Crawl Space 4       1.5       1.4       1.0         38       Wood Frm Vented Crawl Space   | 21 | Wood Frm Cond Bsmt 1          | 1.5         | 1.4               | 1.1         |
| 24     Wood Frm Cond Bsmt 4     1.5     1.5     1.1       25     Wood Frm Slab 1     1.5     1.4     1.1       26     Wood Frm Slab 2     1.5     1.5     1.1       27     Wood Frm Slab 3     1.5     1.5     1.1       28     Wood Frm Slab 4     1.5     1.5     1.1       29     Wood Frm Uncon Bsmt 1     1.5     1.4        30     Wood Frm Uncon Bsmt 2     1.5     1.4     1.0       31     Wood Frm Uncon Bsmt 3     1.5     1.4     1.0       32     Wood Frm Uncon Bsmt 4     1.5     1.4     1.0       33     Wood Frm Uncon Bsmt 5     1.5     1.4     1.0       34     Wood Frm Vented Crawl Space 1     1.5     1.4     1.0       35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0   | 22 | Wood Frm Cond Bsmt 2          | 1.5         | 1.4               | 1.1         |
| 25       Wood Frm Slab 1       1.5       1.4       1.1         26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5       1.4       1.0         33       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Vented Crawl Space 1       1.5       1.4       1.0         35       Wood Frm Vented Crawl Space 2       1.5       1.4       1.0         36       Wood Frm Vented Crawl Space 3       1.5       1.4       1.0         37       Wood Frm Vented Crawl Space 4       1.5       1.4       1.0         38       Wood Frm Vented Crawl Space 5       1.5       1.4       1.0   | 23 | Wood Frm Cond Bsmt 3          | 1.5         | 1.5               | 1.1         |
| 26       Wood Frm Slab 2       1.5       1.5       1.1         27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5       1.4       1.0         33       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Vented Crawl Space 1       1.5       1.4       1.0         35       Wood Frm Vented Crawl Space 2       1.5       1.4       1.0         36       Wood Frm Vented Crawl Space 3       1.5       1.4       1.0         37       Wood Frm Vented Crawl Space 4       1.5       1.4       1.0         38       Wood Frm Vented Crawl Space 5       1.5       1.4       1.0  | 24 | Wood Frm Cond Bsmt 4          | 1.5         | 1.5               | 1.1         |
| 27       Wood Frm Slab 3       1.5       1.5       1.1         28       Wood Frm Slab 4       1.5       1.5       1.1         29       Wood Frm Uncon Bsmt 1       1.5       1.4          30       Wood Frm Uncon Bsmt 2       1.5       1.4       1.0         31       Wood Frm Uncon Bsmt 3       1.5       1.4       1.0         32       Wood Frm Uncon Bsmt 4       1.5       1.4       1.0         33       Wood Frm Uncon Bsmt 5       1.5       1.4       1.0         34       Wood Frm Vented Crawl Space 1       1.5       1.4       1.0         35       Wood Frm Vented Crawl Space 2       1.5       1.4       1.0         36       Wood Frm Vented Crawl Space 3       1.5       1.4       1.0         37       Wood Frm Vented Crawl Space 4       1.5       1.4       1.0         38       Wood Frm Vented Crawl Space 5       1.5       1.4       1.0   | 25 | Wood Frm Slab 1               | 1.5         | 1.4               | 1.1         |
| 28     Wood Frm Slab 4     1.5     1.5     1.1       29     Wood Frm Uncon Bsmt 1     1.5     1.4        30     Wood Frm Uncon Bsmt 2     1.5     1.4     1.0       31     Wood Frm Uncon Bsmt 3     1.5     1.4     1.0       32     Wood Frm Uncon Bsmt 4     1.5     1.4     1.0       33     Wood Frm Uncon Bsmt 5     1.5     1.4     1.0       34     Wood Frm Vented Crawl Space 1     1.5     1.4     1.0       35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0  | 26 | Wood Frm Slab 2               | 1.5         | 1.5               | 1.1         |
| 29     Wood Frm Uncon Bsmt 1     1.5     1.4        30     Wood Frm Uncon Bsmt 2     1.5     1.4     1.0       31     Wood Frm Uncon Bsmt 3     1.5     1.4     1.0       32     Wood Frm Uncon Bsmt 4     1.5     1.4     1.0       33     Wood Frm Uncon Bsmt 5     1.5     1.4     1.0       34     Wood Frm Vented Crawl Space 1     1.5     1.4     1.0       35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0   | 27 | Wood Frm Slab 3               | 1.5         | 1.5               | 1.1         |
| 30     Wood Frm Uncon Bsmt 2     1.5     1.4     1.0       31     Wood Frm Uncon Bsmt 3     1.5     1.4     1.0       32     Wood Frm Uncon Bsmt 4     1.5     1.4     1.0       33     Wood Frm Uncon Bsmt 5     1.5     1.4     1.0       34     Wood Frm Vented Crawl Space 1     1.5     1.4     1.0       35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0   | 28 | Wood Frm Slab 4               | 1.5         | 1.5               | 1.1         |
| 31     Wood Frm Uncon Bsmt 3     1.5     1.4     1.0       32     Wood Frm Uncon Bsmt 4     1.5     1.4     1.0       33     Wood Frm Uncon Bsmt 5     1.5     1.4     1.0       34     Wood Frm Vented Crawl Space 1     1.5     1.4     1.0       35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0  | 29 | Wood Frm Uncon Bsmt 1         | 1.5         | 1.4               |             |
| 32     Wood Frm Uncon Bsmt 4     1.5     1.4     1.0       33     Wood Frm Uncon Bsmt 5     1.5     1.4     1.0       34     Wood Frm Vented Crawl Space 1     1.5     1.4     1.0       35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0   | 30 | Wood Frm Uncon Bsmt 2         | 1.5         | 1.4               | 1.0         |
| 33     Wood Frm Uncon Bsmt 5     1.5     1.4     1.0       34     Wood Frm Vented Crawl Space 1     1.5     1.4     1.0       35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0  | 31 | Wood Frm Uncon Bsmt 3         | 1.5         | 1.4               | 1.0         |
| 34     Wood Frm Vented Crawl Space 1     1.5     1.4     1.0       35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0   | 32 | Wood Frm Uncon Bsmt 4         | 1.5         | 1.4               | 1.0         |
| 35     Wood Frm Vented Crawl Space 2     1.5     1.4     1.0       36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0  | 33 | Wood Frm Uncon Bsmt 5         | 1.5         | 1.4               | 1.0         |
| 36     Wood Frm Vented Crawl Space 3     1.5     1.4     1.0       37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0   | 34 | Wood Frm Vented Crawl Space 1 | 1.5         | 1.4               | 1.0         |
| 37     Wood Frm Vented Crawl Space 4     1.5     1.4     1.0       38     Wood Frm Vented Crawl Space 5     1.5     1.4     1.0  | 35 | Wood Frm Vented Crawl Space 2 | 1.5         | 1.4               | 1.0         |
| 38 Wood Frm Vented Crawl Space 5 1.5 1.4 1.0   | 36 | Wood Frm Vented Crawl Space 3 | 1.5         | 1.4               | 1.0         |
| *  | 37 | Wood Frm Vented Crawl Space 4 | 1.5         | 1.4               | 1.0         |
| 39 Wood Frm Vented Crawl Space 6 1.5 1.4 1.0   | 38 | Wood Frm Vented Crawl Space 5 |             |                   |             |
|  | 39 | Wood Frm Vented Crawl Space 6 | 1.5         | 1.4               | 1.0         |

| Average SIR |
|-------------|
| Max SIR     |
| Min CID     |

1.5

| Other metrics:                     |         |  |
|------------------------------------|---------|--|
| Wood Frame Vented Crawl Space home |         |  |
| Single pane wood windows           |         |  |
|                                    |         |  |
| Annual cost savings                | \$136   |  |
| Measure Cost                       | \$1,386 |  |
| Simple Payback 10.2                |         |  |
|                                    |         |  |
| Energy Savings (Mbtu/yr)           |         |  |
| Initial home heat+cool             | 55.5    |  |
| Storm savings                      | 10.7    |  |
| % reduction                        | 19%     |  |

1.4

1.5

Whole home air conditioned

SIR with different primary window types:

| Single pane | Double pane | Double pane |
|-------------|-------------|-------------|
| wood/vinyl  | metal       | wood/vinyl  |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.6         | 1.2         |
| 1.6         | 1.6         | 1.1         |
| 1.7         | 1.6         | 1.2         |
| 1.6         | 1.7         | 1.1         |
| 1.8         | 1.7         | 1.2         |
| 1.8         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.8         | 1.7         | 1.2         |
| 1.8         | 1.8         | 1.2         |
| 1.8         | 1.7         | 1.2         |
| 1.7         | 1.6         | 1.1         |
| 1.7         | 1.6         | 1.1         |
| 1.6         | 1.5         | 1.1         |
| 1.7         | 1.6         | 1.2         |
| 1.8         | 1.7         | 1.2         |
| 1.8         | 1.7         | 1.2         |
| 1.7         | 1.6         | 1.1         |
| 1.7         | 1.7         | 1.2         |
| 1.8         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.8         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.6         | 1.1         |
| 1.7         | 1.6         | 1.1         |
| 1.7         | 1.6         | 1.1         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.6         | 1.1         |
| 1.7         | 1.6         | 1.1         |
| 1.7         | 1.6         | 1.1         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |
| 1.7         | 1.7         | 1.2         |

| 1.7 | 1.7 | 1.2 |
|-----|-----|-----|
| 1.8 | 1.8 | 1.2 |
| 1.6 | 1.5 | 1.1 |

if include 1/3 of air inf savings \$174 8.0

| Other metrics: Wood Frame Vented Crawl Space home |         |
|---|---------|
| Single pane wood windows                          |         |
| Annual cost savings                               | \$155   |
| Measure Cost                                      | \$1,386 |
| Simple Payback                                    | 8.9     |
| Energy Savings (Mbtu/yr)                          |         |
| Initial home heat+cool                            | 65.1    |
| Storm savings                                     | 11.4    |
| % reduction                                       | 18%     |

if include 1/3 of air inf savings \$196

7.1

1.0

## Seattle WA Zone 4 HDD65

4908 2021 \$11.89 \$0.0853 CDD50 Natural Gas (\$/Mcf, 2012 avg) Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window

SIR with different primary window types:

|    |                               | Single pane | Double pane | Double pane |
|----|-------------------------------|-------------|-------------|-------------|
|    | Home type                     | wood/vinyl  | metal       | wood/vinyl  |
| 1  | Exposed Floor 1               | 1.4         | 1.3         |             |
| 2  | Wood Frame Cape Cod 1 KW 1    | 1.4         | 1.3         |             |
| 3  | Wood Frame Cape Cod 2 KW 2    | 1.4         | 1.3         |             |
| 4  | Wood Frame Cape Cod 3 KW 3    | 1.4         | 1.3         |             |
| 5  | Wood Frame Cape Cod 4 KW 4    | 1.4         | 1.3         |             |
| 6  | Wood Frame Cape Cod 1 KW 5    | 1.4         | 1.4         |             |
| 7  | Masonry 1                     | 1.5         | 1.4         | 1.0         |
| 8  | Masonry 2                     | 1.5         | 1.4         |             |
| 9  | Masonry 3                     | 1.5         | 1.4         |             |
| 10 | Masonry 4                     | 1.5         | 1.4         |             |
| 11 | Masonry 5                     | 1.5         | 1.4         | 1.0         |
| 12 | Masonry 6                     | 1.5         | 1.4         | 1.0         |
| 13 | Row House Masonry 1           | 1.5         | 1.4         | 1.0         |
| 14 | Row House Masonry 2           | 1.5         | 1.4         | 1.0         |
| 15 | Row House Wood Frame 1        | 1.3         | 1.3         |             |
| 16 | Row House Wood Frame 2        | 1.5         | 1.4         | 1.0         |
| 17 | Semi Detached Masonry 1       | 1.5         | 1.4         | 1.0         |
| 18 | Semi Detached Masonry 2       | 1.5         | 1.4         | 1.0         |
| 19 | Semi Detached Wood Frame 1    | 1.4         | 1.3         |             |
| 20 | Semi Detached Wood Frame 2    | 1.4         | 1.4         |             |
| 21 | Wood Frm Cond Bsmt 1          | 1.5         | 1.4         | 1.0         |
| 22 | Wood Frm Cond Bsmt 2          | 1.5         | 1.4         | 1.0         |
| 23 | Wood Frm Cond Bsmt 3          | 1.5         | 1.4         | 1.0         |
| 24 | Wood Frm Cond Bsmt 4          | 1.5         | 1.4         | 1.0         |
| 25 | Wood Frm Slab 1               | 1.5         | 1.4         | 1.0         |
| 26 | Wood Frm Slab 2               | 1.5         | 1.4         | 1.0         |
| 27 | Wood Frm Slab 3               | 1.5         | 1.4         |             |
| 28 | Wood Frm Slab 4               | 1.5         | 1.4         |             |
| 29 | Wood Frm Uncon Bsmt 1         | 1.4         | 1.3         |             |
| 30 | Wood Frm Uncon Bsmt 2         | 1.4         | 1.3         |             |
| 31 | Wood Frm Uncon Bsmt 3         | 1.4         | 1.3         |             |
| 32 | Wood Frm Uncon Bsmt 4         | 1.4         | 1.3         |             |
| 33 | Wood Frm Uncon Bsmt 5         | 1.4         | 1.4         |             |
| 34 | Wood Frm Vented Crawl Space 1 | 1.4         | 1.3         |             |
| 35 | Wood Frm Vented Crawl Space 2 | 1.4         | 1.3         |             |
| 36 | Wood Frm Vented Crawl Space 3 | 1.4         | 1.3         |             |
| 37 | Wood Frm Vented Crawl Space 4 | 1.4         | 1.4         |             |
| 38 | Wood Frm Vented Crawl Space 5 | 1.4         | 1.4         |             |
| 39 | Wood Frm Vented Crawl Space 6 | 1.5         | 1.4         |             |

Avera N N

| age SIR | 1.4 | 1.4 |  |
|---------|-----|-----|--|
| Max SIR | 1.5 | 1.4 |  |
| Min SIR | 1.3 | 1.3 |  |

if include 1/3 of air inf savings \$166

#### Atlanta GA

#### Zone 3

HDD65 2991 CDD50 5038

Natural Gas (\$/Mcf, 2011 avg) \$15.72 \$0.1100

Electricity (\$/kWh, 2012 avg) Low-e Storms \$7.85/ft2 + \$30/window (2012 avg not available)

\$1.537

per therm

#### NG furnace, central AC with standard Low-e

|                               | SIR with different primary window types: |             |             |
|-------------------------------|--|-------------|-------------|
|                               | Single pane                              | Double pane | Double pane |
| Home type                     | wood/vinyl                               | metal       | wood/vinyl  |
| Exposed Floor 1               | 1.2                                      | 1.2         |             |
| Wood Frame Cape Cod 1 KW 1    | 1.2                                      | 1.2         |             |
| Wood Frame Cape Cod 2 KW 2    | 1.2                                      | 1.2         |             |
| Wood Frame Cape Cod 3 KW 3    | 1.2                                      | 1.2         |             |
| Wood Frame Cape Cod 4 KW 4    | 1.2                                      | 1.2         |             |
| Wood Frame Cape Cod 1 KW 5    | 1.3                                      | 1.3         |             |
| Masonry 1                     | 1.3                                      | 1.3         |             |
| Masonry 2                     | 1.3                                      | 1.2         |             |
| Masonry 3                     | 1.3                                      | 1.2         |             |
| Masonry 4                     | 1.3                                      | 1.3         |             |
| Masonry 5                     | 1.4                                      | 1.4         | 1.1         |
| Masonry 6                     | 1.3                                      | 1.3         |             |
| Row House Masonry 1           | 1.2                                      | 1.2         |             |
| Row House Masonry 2           | 1.2                                      | 1.1         |             |
| Row House Wood Frame 1        | 1.1                                      | 1.1         |             |
| Row House Wood Frame 2        | 1.2                                      | 1.2         |             |
| Semi Detached Masonry 1       | 1.2                                      | 1.3         |             |
| Semi Detached Masonry 2       | 1.3                                      | 1.3         |             |
| Semi Detached Wood Frame 1    | 1.1                                      | 1.1         |             |
| Semi Detached Wood Frame 2    | 1.2                                      | 1.2         |             |
| Wood Frm Cond Bsmt 1          | 1.3                                      | 1.3         |             |
| Wood Frm Cond Bsmt 2          | 1.3                                      | 1.2         |             |
| Wood Frm Cond Bsmt 3          | 1.3                                      | 1.2         |             |
| Wood Frm Cond Bsmt 4          | 1.3                                      | 1.2         |             |
| Wood Frm Slab 1               | 1.3                                      | 1.3         |             |
| Wood Frm Slab 2               | 1.3                                      | 1.3         |             |
| Wood Frm Slab 3               | 1.3                                      | 1.2         |             |
| Wood Frm Slab 4               | 1.3                                      | 1.3         |             |
| Wood Frm Uncon Bsmt 1         | 1.2                                      | 1.2         |             |
| Wood Frm Uncon Bsmt 2         | 1.2                                      | 1.2         |             |
| Wood Frm Uncon Bsmt 3         | 1.2                                      | 1.2         |             |
| Wood Frm Uncon Bsmt 4         | 1.2                                      | 1.2         |             |
| Wood Frm Uncon Bsmt 5         | 1.3                                      | 1.2         |             |
| Wood Frm Vented Crawl Space 1 | 1.2                                      | 1.2         |             |
| Wood Frm Vented Crawl Space 2 | 1.2                                      | 1.2         |             |
| Wood Frm Vented Crawl Space 3 | 1.2                                      | 1.2         |             |
| Wood Frm Vented Crawl Space 4 | 1.2                                      | 1.2         |             |
| Wood Frm Vented Crawl Space 5 | 1.3                                      | 1.2         |             |
| Wood Frm Vented Crawl Space 6 | 1.2                                      | 1.2         |             |

| Average SIR |
|-------------|
| Max SIR     |
| Min SIR     |

| 1.2 | 1.2 |   |
|-----|-----|---|
| 1.4 | 1.4 |   |
| 1.1 | 1.1 | - |
|     |     |   |

| NG furnace, central AC  |    |
|-------------------------|----|
| with Solar Control Low- | ·e |

SIR with different primary window types:

| SIR with different primary window types: |             |             |  |  |
|--|-------------|-------------|--|--|
| Single pane                              | Double pane | Double pane |  |  |
| wood/vinyl                               | metal       | wood/vinyl  |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.3                                      | 1.4         | 1.1         |  |  |
| 1.3                                      | 1.4         | 1.1         |  |  |
| 1.3                                      | 1.4         | 1.1         |  |  |
| 1.5                                      | 1.4         | 1.3         |  |  |
| 1.5                                      | 1.5         | 1.3         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| 1.5                                      | 1.5         | 1.3         |  |  |
| 1.5                                      | 1.4         | 1.2         |  |  |
| 1.4                                      | 1.4         | 1.1         |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.3                                      | 1.4         | 1.1         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| 1.3                                      | 1.2         | 1.1         |  |  |
| 1.3                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| 1.3                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.3                                      | 1.3         | 1.1         |  |  |
| 1.3                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.3                                      | 1.3         | 1.1         |  |  |
| 1.3                                      | 1.3         | 1.1         |  |  |
| 1.3                                      | 1.3         | 1.1         |  |  |
| 1.4                                      | 1.4         | 1.3         |  |  |
| 1.4                                      | 1.3         | 1.1         |  |  |
| <u> </u>                                 |             |             |  |  |

| 1.4 | 1.3 | 1.2 |
|-----|-----|-----|
| 1.5 | 1.5 | 1.3 |
| 1.2 | 1.2 | 1.1 |

But only if solar screens unselected (SIR  $\sim 2.3)$ Often only specify east / west

| Other metrics:                     |         |  |
|------------------------------------|---------|--|
| Wood Frame Vented Crawl Space home |         |  |
| Single pane wood windows           |         |  |
| <b>.</b>                           | 6112    |  |
| Annual cost savings                | \$112   |  |
| Measure Cost                       | \$1,386 |  |
| Simple Payback                     | 12.4    |  |
| Energy Savings (Mbtu/yr)           |         |  |
| Initial home heat+cool             | 41.0    |  |
| Storm savings                      | 6.6     |  |
| % reduction                        | 16%     |  |

if include 1/3 of air inf savings \$143 9.7

| Other metrics:<br>Wood Frame Vented Crawl Space hor<br>Single pane wood windows | ne      |
|---|---------|
| Annual cost savings   | \$124   |
| Measure Cost  | \$1,386 |
| Simple Payback  | 11.2    |
|   |         |
| Energy Savings (Mbtu/yr)  |         |
| Initial home heat+cool  | 41.0    |
| Storm savings   | 6.4     |
| % reduction   | 16%     |

if include 1/3 of air inf savings \$155 9.0

Dallas TX Zone 3 HDD65 CDD50

Natural Gas (\$/Mcf, 2012 avg) \$1 Electricity (\$/kWh, 2012 avg) \$0. Low-E Storms \$7.85/ft2 + \$30/window \$10.90 \$0.1104 2259 6587

NG furnace, central AC with Solar Control Low-E

### NG furnace, central AC with standard Low-E

SIR with different primary window types:

|    |                               | SIR WITH DITT | erent primary | window types |
|----|-------------------------------|---------------|---------------|--------------|
|    |                               | Single pane   | Double pane   | Double pane  |
|    | Home type                     | wood/vinyl    | metal         | wood/vinyl   |
| 1  | Exposed Floor 1               | 1.1           | 1.1           |              |
| 2  | Wood Frame Cape Cod 1 KW 1    | 1.1           | 1.3           |              |
| 3  | Wood Frame Cape Cod 2 KW 2    | 1.1           | 1.3           |              |
| 4  | Wood Frame Cape Cod 3 KW 3    | 1.1           | 1.3           |              |
| 5  | Wood Frame Cape Cod 4 KW 4    | 1.1           | 1.3           |              |
| 6  | Wood Frame Cape Cod 1 KW 5    | 1.2           | 1.2           |              |
| 7  | Masonry 1                     | 1.1           | 1.2           |              |
| 8  | Masonry 2                     | 1.2           | 1.3           |              |
| 9  | Masonry 3                     | 1.3           | 1.3           |              |
| 10 | Masonry 4                     | 1.1           | 1.1           |              |
| 11 | Masonry 5                     | 1.2           | 1.2           |              |
| 12 | Masonry 6                     | 1.5           | 1.5           |              |
| 13 | Row House Masonry 1           | 1.1           | 1.0           |              |
| 14 | Row House Masonry 2           | 1.1           | 1.1           |              |
| 15 | Row House Wood Frame 1        | 1.1           | 1.2           |              |
| 16 | Row House Wood Frame 2        | 1.3           | 1.2           |              |
| 17 | Semi Detached Masonry 1       | 1.1           | 1.1           |              |
| 18 | Semi Detached Masonry 2       | 1.2           | 1.2           |              |
|    | Semi Detached Wood Frame 1    | 1.1           | 1.1           |              |
| 20 | Semi Detached Wood Frame 2    | 1.2           | 1.1           |              |
| 21 | Wood Frm Cond Bsmt 1          | 1.2           | 1.2           |              |
|    | Wood Frm Cond Bsmt 2          | 1.2           | 1.2           |              |
|    | Wood Frm Cond Bsmt 3          | 1.2           | 1.2           |              |
|    | Wood Frm Cond Bsmt 4          | 1.2           | 1.2           |              |
|    | Wood Frm Slab 1               | 1.1           | 1.1           |              |
|    | Wood Frm Slab 2               | 1.1           | 1.1           |              |
|    | Wood Frm Slab 3               | 1.1           | 1.1           |              |
|    | Wood Frm Slab 4               | 1.2           | 1.1           |              |
|    | Wood Frm Uncon Bsmt 1         | 1.2           | 1.2           |              |
|    | Wood Frm Uncon Bsmt 2         | 1.2           | 1.2           |              |
|    | Wood Frm Uncon Bsmt 3         | 1.2           | 1.1           |              |
|    | Wood Frm Uncon Bsmt 4         | 1.2           | 1.1           |              |
|    | Wood Frm Uncon Bsmt 5         | 1.1           | 1.1           |              |
|    | Wood Frm Vented Crawl Space 1 | 1.1           | 1.1           |              |
|    | Wood Frm Vented Crawl Space 2 | 1.1           | 1.1           |              |
|    | Wood Frm Vented Crawl Space 3 | 1.1           | 1.1           |              |
|    | Wood Frm Vented Crawl Space 4 | 1.2           | 1.1           |              |
|    | Wood Frm Vented Crawl Space 5 | 1.1           | 1.1           |              |
| 39 | Wood Frm Vented Crawl Space 6 | 1.4           | 1.4           |              |

| _          |     |     |  |
|------------|-----|-----|--|
| verage SIR | 1.2 | 1.2 |  |
| Max SIR    | 1.5 | 1.5 |  |
| Min SIR    | 1.1 | 1.0 |  |

But only if solar screens unselected Several S/E/W or E/W only

| Wood Frame Vented Crawl Spa<br>Single pane wood windows | ce home |
|---|---------|
| Annual cost savings                                     | \$86    |
| Measure Cost  | \$924   |
| Simple Payback  | 10.7    |
| Energy Savings (Mbtu/yr)                                |         |
| Initial home heat+cool                                  | 45.7    |
| Storm savings   | 4.9     |
| % reduction   | 11%     |

| SIR with different primary window types: |             |             |  |
|--|-------------|-------------|--|
|  | Double pane | Double pane |  |
| wood/vinyl                               | metal       | wood/vinyl  |  |
| 1.3                                      | 1.3         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.5                                      | 1.5         | 1.1         |  |
| 1.5                                      | 1.5         | 1.1         |  |
| 1.5                                      | 1.7         | 1.6         |  |
| 1.7                                      | 1.7         | 1.6         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.5                                      | 1.5         | 1.1         |  |
| 1.7                                      | 1.7         | 1.6         |  |
| 1.2                                      | 1.2         |             |  |
| 1.2                                      | 1.2         |             |  |
| 1.3                                      | 1.3         | 1.1         |  |
| 1.4                                      | 1.3         | 1.0         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.3         | 1.1         |  |
| 1.5                                      | 1.3         | 1.1         |  |
| 1.3                                      | 1.3         | 1.1         |  |
| 1.5                                      | 1.5         | 1.1         |  |
| 1.5                                      | 1.5         | 1.1         |  |
| 1.5                                      | 1.5         | 1.1         |  |
| 1.3                                      | 1.3         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.3                                      | 1.3         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.3                                      | 1.3         | 1.1         |  |
| 1.3                                      | 1.3         | 1.1         |  |
| 1.3                                      | 1.3         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.4                                      | 1.4         | 1.1         |  |
| 1.2                                      | 1.3         | 1.1         |  |
| 1.6                                      | 1.7         | 1.4         |  |
|  |             |             |  |

| 1.4                                  | 1.4 | 1.1 |  |
|--------------------------------------|-----|-----|--|
| 1.7                                  | 1.7 | 1.6 |  |
| 1.2                                  | 1.2 | 1.0 |  |
| But only if solar screens unselected |     |     |  |

Over double pane wood, just E/W

| if include 1/3<br>of air inf<br>savings | Other metrics:<br>Wood Frame Vented Crawl Space home<br>Single pane wood windows |         |
|---|--|---------|
| \$121                                   | Annual cost savings  | \$152   |
|   | Measure Cost   | \$1,386 |
| 7.6                                     | Simple Payback   | 9.1     |
|   |  |         |
|   | Energy Savings (Mbtu/yr)   |         |
|   | Initial home heat+cool   | 45.7    |
|   | Storm savings  | 7.6     |
|   | % reduction  | 17%     |
|   | ,  | /0      |

Heat pump, central AC with standard Low-E

SIR with different primary window types:

| Six with different primary window types: |                   |                           |  |
|--|-------------------|---------------------------|--|
| Single pane<br>wood/vinyl                | Double pane metal | Double pane<br>wood/vinyl |  |
|  | netai<br>1.1      | wood/villyl               |  |
| 1.2<br>1.2                               | 1.1<br>1.2        |                           |  |
|  |                   |                           |  |
| 1.2<br>1.2                               | 1.1<br>1.2        |                           |  |
|  |                   |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.5                                      | 1.3               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.6                                      | 1.6               | 1.3                       |  |
| 1.2                                      | 1.1               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.4                                      | 1.3               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.1                                      | 1.1               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.4                                      | 1.3               |                           |  |
| 1.4                                      | 1.4               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.3                                      | 1.2               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.3                                      | 1.2               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.3                                      | 1.2               |                           |  |
| 1.3                                      | 1.3               |                           |  |
| 1.2                                      | 1.2               |                           |  |
| 1.4                                      | 1.4               | 1.2                       |  |
| ***                                      | 4.7               | 1.2                       |  |
| - 1 2                                    | 1.3               |                           |  |

| 1.3 | 1.2 |  |
|-----|-----|--|
| 1.6 | 1.6 |  |
| 1.1 | 1.1 |  |

But only if solar screens unselected

| if include 1/3<br>of air inf<br>savings | Wood Frame Vented Crawl Space home<br>Single pane wood windows |         | if include 1/3<br>of air inf<br>savings |
|---|--|---------|---|
| \$187                                   | Annual cost savings  | \$134   | \$172                                   |
|   | Measure Cost   | \$1,386 |   |
| 7.4                                     | Simple Payback   | 10.3    | 8.1                                     |
|   |  |         |   |
|   | Energy Savings (Mbtu/yr)                                       |         |   |
|   | Initial home heat+cool   | 31.9    |   |
|   | Storm savings  | 4.1     |   |
|   | % reduction  | 13%     |   |

| Heat | pump, central AC    |  |
|------|---------------------|--|
| with | Solar Control Low-E |  |

SIR with different primary window types:

| Single pane | Double pane | Double pane |
|-------------|-------------|-------------|
| wood/vinyl  | metal       | wood/vinyl  |
| 1.4         | 1.4         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.6         | 1.5         | 1.2         |
| 1.6         | 1.6         | 1.2         |
| 1.6         | 1.8         | 1.6         |
| 1.8         | 1.8         | 1.6         |
| 1.5         | 1.5         | 1.2         |
| 1.6         | 1.6         | 1.2         |
| 1.8         | 1.8         | 1.6         |
| 1.7         | 1.4         |             |
| 1.7         | 1.3         |             |
| 1.6         | 1.7         | 1.1         |
| 1.5         | 1.5         | 1.0         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.4         | 1.2         |
| 1.6         | 1.4         | 1.2         |
| 1.6         | 1.4         | 1.2         |
| 1.4         | 1.4         | 1.2         |
| 1.6         | 1.6         | 1.2         |
| 1.6         | 1.6         | 1.2         |
| 1.6         | 1.6         | 1.2         |
| 1.4         | 1.4         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.5         | 1.6         |
| 1.4         | 1.4         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.4         | 1.4         | 1.2         |
| 1.3         | 1.3         | 1.2         |
| 1.4         | 1.4         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.5         | 1.2         |
| 1.5         | 1.5         | 1.6         |
| 1.3         | 1.3         | 1.2         |
| 1.7         | 1.8         | 1.5         |
|             | 1.5         | - 12        |

| 1.6              | 1.0          | 1         | ٠, |
|------------------|--------------|-----------|----|
| 1.3              | 1.3          | 1         | .( |
| But only if sola | ar screens u | nselected |    |
|                  |              |           |    |

Over double pane wood, just E/W

| Other metrics:<br>3 Wood Frame Vented Crawl Space home<br>Single pane wood windows |                  |  |
|--|------------------|--|
| Annual cost savings<br>Measure Cost  | \$164<br>\$1,386 |  |
| Simple Payback   | 8.5              |  |
| Energy Savings (Mbtu/yr)   |                  |  |
| Initial home heat+cool   | 31.9             |  |
| Storm savings  | 5.1              |  |
| % reduction  | 16%              |  |

if include 1/3 of air inf savings \$202 6.9

**Houston TX** Zone 2 HDD65 CDD50

30 Wood Frm Uncon Bsmt 2 31 Wood Frm Uncon Bsmt 3 32 Wood Frm Uncon Bsmt 4 33 Wood Frm Uncon Bsmt 5 34 Wood Frm Vented Crawl Space 1 35 Wood Frm Vented Crawl Space 2 36 Wood Frm Vented Crawl Space 3 37 Wood Frm Vented Crawl Space 4 38 Wood Frm Vented Crawl Space 5 39 Wood Frm Vented Crawl Space 6

Natural Gas (\$/Mcf, 2012 avg) \$10.90 Electricity (\$/kWh, 2012 avg) \$0. Low-E Storms \$7.85/ft2 + \$30/window \$0.1104

#### NG furnace, central AC with standard Low-E

|   |                            | THE STANDARD CON E                       |             |             |  |
|---|----------------------------|--|-------------|-------------|--|
|   |                            | SIR with different primary window types: |             |             |  |
|   |                            | Single pane                              | Double pane | Double pane |  |
|   | Home type                  | wood/vinyl                               | metal       | wood/vinyl  |  |
| 1 | Exposed Floor 1            |  |             |             |  |
| 2 | Wood Frame Cape Cod 1 KW 1 |  |             |             |  |
| 3 | Wood Frame Cape Cod 2 KW 2 |  |             |             |  |
| 4 | Wood Frame Cape Cod 3 KW 3 |  |             |             |  |
| 5 | Wood Frame Cape Cod 4 KW 4 |  |             |             |  |
| 6 | Wood Frame Cape Cod 1 KW 5 |  |             |             |  |
| 7 | Masonry 1                  |  |             |             |  |
| 8 | Masonry 2                  |  |             |             |  |
|   | Masonry 3                  |  |             |             |  |
|   | Masonry 4                  |  |             |             |  |
|   | Masonry 5                  |  |             |             |  |
|   | Masonry 6                  |  |             |             |  |
|   | Row House Masonry 1        |  |             |             |  |
|   | Row House Masonry 2        |  |             |             |  |
|   | Row House Wood Frame 1     |  |             |             |  |
|   | Row House Wood Frame 2     |  |             |             |  |
|   | Semi Detached Masonry 1    |  |             |             |  |
|   | Semi Detached Masonry 2    |  |             |             |  |
|   | Semi Detached Wood Frame 1 |  |             |             |  |
|   | Semi Detached Wood Frame 2 |  |             |             |  |
|   | Wood Frm Cond Bsmt 1       |  |             |             |  |
|   | Wood Frm Cond Bsmt 2       |  |             |             |  |
|   | Wood Frm Cond Bsmt 3       |  |             |             |  |
|   | Wood Frm Cond Bsmt 4       |  |             |             |  |
|   | Wood Frm Slab 1            |  |             |             |  |
|   | Wood Frm Slab 2            |  |             |             |  |
|   | Wood Frm Slab 3            |  |             |             |  |
|   | Wood Frm Slab 4            |  |             |             |  |
|   | Wood Frm Uncon Bsmt 1      |  |             |             |  |
|   |                            |  |             |             |  |

| _           |   |   |   |
|-------------|---|---|---|
| Average SIR | - | - | - |
| Max SIR     |   |   |   |
|             |   |   |   |

---

NG furnace, central AC

1371 7357

| SIR with different primary window types: |             |            |  |
|--|-------------|------------|--|
|  | Double pane |            |  |
| wood/vinyl                               | metal       | wood/vinyl |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.7         |            |  |
| 1.7                                      | 1.7         |            |  |
| 1.1                                      | 1.1         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
|  | 1.0         |            |  |
|  | 1.1         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.1                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.7                                      | 1.7         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.6                                      | 1.7         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.1         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.1                                      | 1.1         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.2                                      | 1.1         |            |  |
| 1.2                                      | 1.2         |            |  |
| 1.6                                      | 1.7         |            |  |
| 1.1<br>1.5                               | 1.1         | 1.4        |  |
| 1.5                                      | 1.6         | 1.4        |  |
| 1.2                                      | 1.3         |            |  |
|  |             |            |  |

| 1.1   | 1.0              |                  |    |  |
|---|------------------|------------------|----|--|
| But only if sola  | er screens unsel | ected (SIR ~ 2.2 | 2) |  |
| All only specify east / west, except WFVC5 and 6 have S/E/W |                  |                  |    |  |
| Not sure why  | jumps from 1.2   | to 1.7           |    |  |
|   |                  |                  |    |  |

| Other metrics:<br>Wood Frame Vented Crawl Sp<br>Single pane wood windows | pace home | if include 1/3<br>of air inf<br>savings |
|--|-----------|---|
| Annual cost savings  | \$96      | \$126                                   |
| Measure Cost   | \$924     |   |
| Simple Payback   | 9.6       | 7.3                                     |
|  |           |   |
| Energy Savings (Mbtu/yr)   |           |   |
| Initial home heat+cool   | 35.5      |   |
| Storm savings  | 4.5       | < adjusted f                            |
| % reduction  | 13%       | if don't adjust,                        |

<-- adjusted for all 4 sides using only 40% of savings on north if don't adjust, it is 11%

Heat pump, central AC with standard Low-E

| with standar                             |             |             |  |
|--|-------------|-------------|--|
| SIR with different primary window types: |             |             |  |
| Single pane                              | Double pane | Double pane |  |
| wood/vinyl                               | metal       | wood/vinyl  |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
|  |             |             |  |
| -  | -           |             |  |
|  |             |             |  |
|  |             |             |  |

Heat pump, central AC with Solar Control Low-E SIR with different primary window types:

| Single pane | Double pane | Double pane |
|-------------|-------------|-------------|
| wood/vinyl  | metal       | wood/vinyl  |
| 1.1         | 1.1         |             |
| 1.2         | 1.1         |             |
| 1.2         | 1.1         |             |
| 1.2         | 1.1         |             |
| 1.2         | 1.1         |             |
| 1.2         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.2         | 1.4         |             |
| 1.7         | 1.4         |             |
| 1.1         | 1.1         |             |
| 1.2         | 1.2         |             |
| 1.6         | 1.6         | 1.4         |
| 1.0         | 1.0         |             |
| 1.0         | 1.1         |             |
| 1.2         | 1.2         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.2         | 1.2         |             |
| 1.2         | 1.1         |             |
| 1.2         | 1.2         |             |
| 1.2         | 1.1         |             |
| 1.2         | 1.1         |             |
| 1.2         | 1.1         |             |
| 1.7         | 1.4         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.3         | 1.4         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |
| 1.1         | 1.1         |             |

| - |     |     |  |
|---|-----|-----|--|
| Γ | 1.2 | 1.2 |  |
| Г | 1.7 | 1.6 |  |
|   | 1.0 | 1.0 |  |

But only if solar screens unselected (SIR ~ 2.3)
All only specify south / east / west, and occasionally just e/w (not north)

| Other metrics:                     |       |  |
|------------------------------------|-------|--|
| Wood Frame Vented Crawl Space home |       |  |
| Single pane wood windows           |       |  |
|                                    |       |  |
| Annual cost savings                | \$97  |  |
| Measure Cost                       | \$924 |  |
| Simple Payback                     | 9.5   |  |
|                                    |       |  |
| Energy Savings (Mbtu/yr)           |       |  |
| Initial home heat+cool             | 27.9  |  |
| Storm savings                      | 3.4   |  |
| % reduction                        | 12%   |  |

if include 1/3 of air inf savings \$127 7.3

<-- adjusted for all 4 sides using only 40% of savings for north since mainly solar if don't adjust, it is 11%

#### Jacksonville FL

Zone 2

HDD65 1434 CDD50 6847 Natural Gas (\$/Mcf, 2012 avg) --Electricity (\$/kWh, 2012 avg) \$0.1152 Low-e Storms \$7.85/ft2 + \$30/window

Heat pump, central AC with standard Low-e

SIR with different primary window types:

| Heat pump, central AC    |
|--------------------------|
| with Solar Control Low-e |
| CTT 1.1 1100             |

| 1 Exposed Floor 1 2 Wood Frame Cape Cod 1 KW 1 3 Wood Frame Cape Cod 2 KW 2 4 Wood Frame Cape Cod 3 KW 3 5 Wood Frame Cape Cod 4 KW 4 6 Wood Frame Cape Cod 1 KW 5 7 Masonry 1 8 Masonry 2 9 Masonry 3 |    | Home type                     | Single pane<br>wood/vinyl | Double pane<br>metal | Double pane<br>wood/vinyl |
|--|----|-------------------------------|---------------------------|----------------------|---------------------------|
| 3 Wood Frame Cape Cod 2 KW 2 4 Wood Frame Cape Cod 3 KW 3 5 Wood Frame Cape Cod 4 KW 4 6 Wood Frame Cape Cod 1 KW 5 7 Masonry 1 8 Masonry 2 9 Masonry 3  | 1  | Exposed Floor 1               |                           |                      |                           |
| 4 Wood Frame Cape Cod 3 KW 3 5 Wood Frame Cape Cod 4 KW 4 6 Wood Frame Cape Cod 1 KW 5 7 Masonry 1 8 Masonry 2 9 Masonry 3   | 2  | Wood Frame Cape Cod 1 KW 1    |                           |                      |                           |
| 5 Wood Frame Cape Cod 4 KW 4   | 3  | Wood Frame Cape Cod 2 KW 2    |                           |                      |                           |
| 6 Wood Frame Cape Cod 1 KW 5   | 4  | Wood Frame Cape Cod 3 KW 3    |                           |                      |                           |
| 7 Masonry 1  | 5  | Wood Frame Cape Cod 4 KW 4    |                           |                      |                           |
| 8 Masonry 2  | 6  | Wood Frame Cape Cod 1 KW 5    |                           |                      |                           |
| 9 Masonry 3  | 7  | Masonry 1                     |                           |                      |                           |
| 10     Masonry 4          11     Masonry 5          12     Masonry 6          13     Row House Masonry 1          14     Row House Masonry 2   | 8  | Masonry 2                     |                           |                      |                           |
| 11     Masonry 5          12     Masonry 6          13     Row House Masonry 1          14     Row House Masonry 2   | 9  | Masonry 3                     |                           |                      |                           |
| 12 Masonry 6 13 Row House Masonry 1 14 Row House Masonry 2   | 10 | Masonry 4                     |                           |                      |                           |
| 13 Row House Masonry 1   | 11 | Masonry 5                     |                           |                      |                           |
| 14 Row House Masonry 2   | 12 | Masonry 6                     |                           |                      |                           |
|  | 13 | Row House Masonry 1           |                           |                      |                           |
|  | 14 | Row House Masonry 2           |                           |                      |                           |
| 15 Row House Wood Frame 1  | 15 | Row House Wood Frame 1        |                           |                      |                           |
| 16 Row House Wood Frame 2  | 16 | Row House Wood Frame 2        |                           |                      |                           |
| 17 Semi Detached Masonry 1   | 17 | Semi Detached Masonry 1       |                           |                      |                           |
| 18 Semi Detached Masonry 2   | 18 | Semi Detached Masonry 2       |                           |                      |                           |
| 19 Semi Detached Wood Frame 1  | 19 | Semi Detached Wood Frame 1    |                           |                      |                           |
| 20 Semi Detached Wood Frame 2  | 20 | Semi Detached Wood Frame 2    |                           |                      |                           |
| 21 Wood Frm Cond Bsmt 1  | 21 | Wood Frm Cond Bsmt 1          |                           |                      |                           |
| 22 Wood Frm Cond Bsmt 2  | 22 | Wood Frm Cond Bsmt 2          |                           |                      |                           |
| 23 Wood Frm Cond Bsmt 3  | 23 | Wood Frm Cond Bsmt 3          |                           |                      |                           |
| 24 Wood Frm Cond Bsmt 4  | 24 | Wood Frm Cond Bsmt 4          |                           |                      |                           |
| 25 Wood Frm Slab 1   | 25 | Wood Frm Slab 1               |                           |                      |                           |
| 26 Wood Frm Slab 2   | 26 | Wood Frm Slab 2               |                           |                      |                           |
| 27 Wood Frm Slab 3   | 27 | Wood Frm Slab 3               |                           |                      |                           |
| 28 Wood Frm Slab 4   | 28 | Wood Frm Slab 4               |                           |                      |                           |
| 29 Wood Frm Uncon Bsmt 1   | 29 | Wood Frm Uncon Bsmt 1         |                           |                      |                           |
| 30 Wood Frm Uncon Bsmt 2   | 30 | Wood Frm Uncon Bsmt 2         |                           |                      |                           |
| 31 Wood Frm Uncon Bsmt 3   | 31 | Wood Frm Uncon Bsmt 3         |                           |                      |                           |
| 32 Wood Frm Uncon Bsmt 4   | 32 | Wood Frm Uncon Bsmt 4         |                           |                      |                           |
| 33 Wood Frm Uncon Bsmt 5   | 33 | Wood Frm Uncon Bsmt 5         |                           |                      |                           |
| 34 Wood Frm Vented Crawl Space 1   | 34 | Wood Frm Vented Crawl Space 1 |                           |                      |                           |
| 35 Wood Frm Vented Crawl Space 2   | 35 | Wood Frm Vented Crawl Space 2 |                           |                      |                           |
| 36 Wood Frm Vented Crawl Space 3   | 36 | Wood Frm Vented Crawl Space 3 |                           |                      |                           |
| 37 Wood Frm Vented Crawl Space 4   | 37 | Wood Frm Vented Crawl Space 4 |                           |                      |                           |
| 38 Wood Frm Vented Crawl Space 5   | 38 | Wood Frm Vented Crawl Space 5 |                           |                      |                           |
| 39 Wood Frm Vented Crawl Space 6   | 39 | Wood Frm Vented Crawl Space 6 |                           |                      |                           |

| Average SIR |   | - |  |
|-------------|---|---|--|
| Max SIR     |   |   |  |
| Min SIR     | - |   |  |

| SIR with different primary window types: |             |             |  |  |
|--|-------------|-------------|--|--|
| Single pane                              | Double pane | Double pane |  |  |
| wood/vinyl                               | metal       | wood/vinyl  |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.7         |             |  |  |
| 1.6                                      | 1.7         |             |  |  |
| 1.1                                      | 1.1         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.5                                      | 1.5         | 1.4         |  |  |
|  |             |             |  |  |
|  | 1.1         |             |  |  |
| 1.1                                      | 1.1         |             |  |  |
| 1.1                                      | 1.1         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.1                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.6                                      | 1.7         |             |  |  |
| 1.2                                      | 1.1         |             |  |  |
| 1.2                                      | 1.1         |             |  |  |
| 1.2                                      | 1.1         |             |  |  |
| 1.6                                      | 1.7         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.1                                      | 1.1         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.2                                      | 1.2         |             |  |  |
| 1.6                                      | 1.2         |             |  |  |
| 1.1                                      | 1.1         |             |  |  |
| 1.5                                      | 1.6         | 1.3         |  |  |

| 1.2 | 1.2 |  |
|-----|-----|--|
| 1.6 | 1.7 |  |
| 1.1 | 1.1 |  |

But only if solar screens unselected (SIR  $\sim 2.3)$  Often only specify  $\mbox{east}\,/\mbox{ west}$ 

| Other metrics:<br>Wood Frame Vented Crawl Space home |       |  |
|--|-------|--|
|  |       |  |
|  | 00.5  |  |
| Annual cost savings                                  | \$96  |  |
| Measure Cost   | \$924 |  |
| Simple Payback                                       | 9.6   |  |
| Energy Savings (Mbtu/yr)                             |       |  |
| Initial home heat+cool                               | 25.8  |  |
| Storm savings  | 3.2   |  |
| % reduction  | 12%   |  |

if include 1/3 of air inf savings \$120

#### Phoenix AZ

Zone 2

 HDD65
 1350

 CDD50
 8425

 Natural Gas (\$/Mcf, 2012 avg)
 - 

 Electricity (\$/kWh, 2012 avg)
 \$0.1127

Low-e Storms \$7.85/ft2 + \$30/window

Heat pump, central AC with standard Low-e

SIR with different primary window types:

### Heat pump, central AC with Solar Control Low-e

SIR with different primary window types:

|    |                               | Single pane | Double pane | Double pane |
|----|-------------------------------|-------------|-------------|-------------|
|    | Home type                     | wood/vinyl  | metal       | wood/vinyl  |
| 1  | Exposed Floor 1               |             |             |             |
| 2  | Wood Frame Cape Cod 1 KW 1    |             |             |             |
| 3  | Wood Frame Cape Cod 2 KW 2    |             |             |             |
| 4  | Wood Frame Cape Cod 3 KW 3    |             |             |             |
| 5  | Wood Frame Cape Cod 4 KW 4    |             |             |             |
| 6  | Wood Frame Cape Cod 1 KW 5    |             |             |             |
| 7  | Masonry 1                     |             |             |             |
| 8  | Masonry 2                     |             |             |             |
| 9  | Masonry 3                     |             |             |             |
| 10 | Masonry 4                     |             |             |             |
| 11 | Masonry 5                     |             |             |             |
| 12 | Masonry 6                     |             |             |             |
| 13 | Row House Masonry 1           |             |             |             |
| 14 | Row House Masonry 2           |             |             |             |
| 15 | Row House Wood Frame 1        |             |             |             |
| 16 | Row House Wood Frame 2        |             |             |             |
| 17 | Semi Detached Masonry 1       |             |             |             |
| 18 | Semi Detached Masonry 2       |             |             |             |
| 19 | Semi Detached Wood Frame 1    |             |             |             |
| 20 | Semi Detached Wood Frame 2    |             |             |             |
| 21 | Wood Frm Cond Bsmt 1          |             |             |             |
| 22 | Wood Frm Cond Bsmt 2          |             |             |             |
| 23 | Wood Frm Cond Bsmt 3          |             |             |             |
| 24 | Wood Frm Cond Bsmt 4          |             |             |             |
| 25 | Wood Frm Slab 1               |             |             |             |
| 26 | Wood Frm Slab 2               |             |             |             |
| 27 | Wood Frm Slab 3               |             |             |             |
| 28 | Wood Frm Slab 4               |             |             |             |
| 29 | Wood Frm Uncon Bsmt 1         |             |             |             |
| 30 | Wood Frm Uncon Bsmt 2         |             |             |             |
| 31 | Wood Frm Uncon Bsmt 3         |             |             |             |
| 32 | Wood Frm Uncon Bsmt 4         |             |             |             |
| 33 | Wood Frm Uncon Bsmt 5         |             |             |             |
| 34 | Wood Frm Vented Crawl Space 1 |             |             |             |
| 35 | Wood Frm Vented Crawl Space 2 |             |             |             |
| 36 | Wood Frm Vented Crawl Space 3 |             |             |             |
| 37 | Wood Frm Vented Crawl Space 4 |             |             |             |
| 38 | Wood Frm Vented Crawl Space 5 |             |             |             |
| 39 | Wood Frm Vented Crawl Space 6 |             |             |             |

| Single pane<br>wood/vinyl | Double pane<br>metal | Double pane<br>wood/vinyl |
|---------------------------|----------------------|---------------------------|
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
| -                         |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |
|                           |                      |                           |

| Average SIR | <br> |  |
|-------------|------|--|
| Max SIR     | <br> |  |
| Min SIR     | <br> |  |

None had SIR > 1

None had SIR > 1

#### Miami FL

Zone 1

HDD65 200 CDD50 9474 Natural Gas (\$/Mcf, 2012 avg) Electricity (\$/kWh, 2012 avg) \$0.1152

Low-e Storms \$7.85/ft2 + \$30/window

#### Heat pump, central AC with standard Low-e

SIR with different primary window types:

|    |                               | SIR with different primary window types: |                      |                           |  |
|----|-------------------------------|--|----------------------|---------------------------|--|
|    | Home type                     | Single pane<br>wood/vinyl                | Double pane<br>metal | Double pane<br>wood/vinyl |  |
| 1  | Exposed Floor 1               |  |                      |                           |  |
| 2  | Wood Frame Cape Cod 1 KW 1    |  |                      |                           |  |
| 3  | Wood Frame Cape Cod 2 KW 2    |  |                      |                           |  |
| 4  | Wood Frame Cape Cod 3 KW 3    |  |                      |                           |  |
| 5  | Wood Frame Cape Cod 4 KW 4    |  |                      |                           |  |
| 6  | Wood Frame Cape Cod 1 KW 5    |  |                      |                           |  |
| 7  | Masonry 1                     |  |                      |                           |  |
| 8  | Masonry 2                     |  |                      |                           |  |
| 9  | Masonry 3                     |  |                      |                           |  |
| 10 | Masonry 4                     |  |                      |                           |  |
| 11 | Masonry 5                     |  |                      |                           |  |
| 12 | Masonry 6                     |  |                      |                           |  |
| 13 | Row House Masonry 1           |  |                      |                           |  |
| 14 | Row House Masonry 2           |  |                      |                           |  |
| 15 | Row House Wood Frame 1        |  |                      |                           |  |
| 16 | Row House Wood Frame 2        |  |                      |                           |  |
| 17 | Semi Detached Masonry 1       |  |                      |                           |  |
| 18 | Semi Detached Masonry 2       |  |                      |                           |  |
| 19 | Semi Detached Wood Frame 1    |  |                      |                           |  |
| 20 | Semi Detached Wood Frame 2    |  |                      |                           |  |
| 21 | Wood Frm Cond Bsmt 1          |  |                      |                           |  |
| 22 | Wood Frm Cond Bsmt 2          |  |                      |                           |  |
| 23 | Wood Frm Cond Bsmt 3          |  |                      |                           |  |
| 24 | Wood Frm Cond Bsmt 4          |  |                      |                           |  |
| 25 | Wood Frm Slab 1               |  |                      |                           |  |
| 26 | Wood Frm Slab 2               |  |                      |                           |  |
| 27 | Wood Frm Slab 3               |  |                      |                           |  |
| 28 | Wood Frm Slab 4               |  |                      |                           |  |
| 29 | Wood Frm Uncon Bsmt 1         |  |                      |                           |  |
| 30 | Wood Frm Uncon Bsmt 2         |  |                      |                           |  |
| 31 | Wood Frm Uncon Bsmt 3         |  |                      |                           |  |
| 32 | Wood Frm Uncon Bsmt 4         |  |                      |                           |  |
| 33 | Wood Frm Uncon Bsmt 5         |  |                      |                           |  |
| 34 | Wood Frm Vented Crawl Space 1 |  |                      |                           |  |
| 35 | Wood Frm Vented Crawl Space 2 |  |                      |                           |  |
| 36 | Wood Frm Vented Crawl Space 3 |  |                      |                           |  |
| 37 | Wood Frm Vented Crawl Space 4 |  |                      |                           |  |
| 38 | Wood Frm Vented Crawl Space 5 |  |                      |                           |  |
| 39 | Wood Frm Vented Crawl Space 6 |  |                      |                           |  |

Average SIR Max SIR Min SIR

| <br> |  |
|------|--|
| <br> |  |
| <br> |  |

Heat pump, central AC

with Solar Control Low-e
SIR with different primary window types:

| wood/vinyl 1.2 | ible pane<br>metal<br>1.2<br>1.2 | Double pane<br>wood/vinyl |
|----------------|----------------------------------|---------------------------|
| 1.2            | 1.2                              |                           |
|                |                                  | 1.1                       |
|                | 1.2                              |                           |
| 1.2            |                                  | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.3                              | 1.1                       |
| 1.2            | 1.3                              | 1.1                       |
| 1.2            | 1.3                              | 1.1                       |
| 1.2            | 1.3                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.3                              | 1.1                       |
| 1.2            | 1.4                              | 1.1                       |
| 1.2            | 1.3                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.3                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.2            | 1.2                              | 1.1                       |
| 1.5            | 1.9                              | 1.1                       |

| 1.2 | 1.2 | 1.1 |
|-----|-----|-----|
| 1.5 | 1.9 | 1.1 |
| 1.2 | 1.2 | 1.1 |

But only if solar screens and film unselected All specify south / east / west

| Other metrics:<br>Wood Frame Vented Crawl Space home<br>Single pane wood windows |       |  |
|--|-------|--|
| Annual cost savings  | \$95  |  |
| Measure Cost   | \$924 |  |
| Simple Payback 9.7   |       |  |
|  |       |  |
| Energy Savings (Mbtu/yr)   |       |  |
| Initial home heat+cool   | 33.0  |  |
| Storm savings  | 3.2   |  |
| % reduction  | 10%   |  |

if include 1/3 of air inf savings \$132 7.0

# Appendix B RESFEN 6 Modeling Assumptions

The following table captures the differences in modeling assumptions for the Energy Star analysis reference house between RESFEN 5 and RESFEN 6 (in development).

Table 0-1. RESFEN 6 Assumptions – Reference House for Energy Star Analysis

| PARAMETER                                 | RESFEN 5   | RESFEN 6 - DRAFT   | Notes on changes   |
|---|--|--|--|
| Floor Area (ft <sup>2</sup> & dimensions) | Reference House: 2000 sf Specific House: Variable, from 1,000 to 4,000 square feet, input by user. | Reference House: New – 1 Story: 1700sf New – 2 Story: 2800sf Existing 1 Story: 1700sf Existing 2 Story: 2600sf | NFRC noted the following: New Construction: 2005 U.S. Census Bureau Characteristics Median New house size is 2200sf; Average is 2400. Existing Construction: Keep same default as RESFEN 5 unless new data to the contrary is presented.  LBNL decided to keep with these basic numbers, but differentiate between smaller single story homes and larger two story homes.  [For the Energy Star analysis, results for both 1 and 2 story homes will be generated. End results will be based on appropriate regional weightings of 1 and 2 story homes.]  Using RECS 2001, an analysis of public use microdata, we came up with the following, at a national level: - For existing homes (defined as pre-1990), RECS supports an average house size of 2000 sf, as NFRC had agreed upon. Single story homes (65% of existing homes nationally) are 1700sf and Two+ story homes (35%) are 2600sf. When weighted by fractions of the population, the average comes out to 2000 For New (after 1990) homes, NFRC had chosen to go with the census data Median of 2200, not the average of 2400. We agree that it makes sense to use a Median so that the size is not skewed by the small number of very large houses. RECS comes up with a slightly different average of 2600 (2000sf for single and 3400 Sf for 2+ story). We decided we should keep the NFRC value of 2200 as the normalized area but use RECS data on 1 and 2 story to modify this average number. This leads to using 1700 sf for New - 1 story (58%) and 2800 sf for New 2-story (42%). |

| House Type | New Construction Existing Construction  | Reference House: New Construction is frame. Existing Construction is frame. Both 1 and 2 story houses are modeled in all climates. National or regional energy impact studies will be based on the fractions of 1 and 2 story homes in each climate, for New and Existing. | For reference, see census map: http://www.eia.doe.gov/emeu/recs/census_map.htm 1  IECC Climate map at: www.energycodes.gov/implement/pdfs/color_map climate_zones_Mar03.pdf  Data on New Construction; From http://www.census.gov/const/www/charindex.html #singlecomplete Look at Number of Stories  Data on Existing Construction Source: RECS 2001 Microdata, http://www.eia.doe.gov/emeu/recs/recs2001/publicu se2001.html  |
|------------|---|--|---|
| Foundation | Foundation is based on location based on NAHB data. There are a maximum of three options per climate zone, chosen from: Basement Slab-on-Grade Crawlspace | Default foundation based on location as with RESFEN 5.   | What is in RESFEN is very similar to NFRC.  NFRC proposed: New and Existing Construction: Basement in climate zone 5-8; Crawlspace in climate zone 4; Slab-on-grade in climate zones 1-3.  What is in RESFEN is essentially this, except that some southern Zone 4 cities have slabs and some northern Zone 4 cities have basements to better represent current practice.  Foundation modeling process updated based on 1998 research: Winkelmann, FC. 1998. "Underground Surfaces: How to Get a Better Underground Surface Heat Transfer Calculation in DOE-2.1E", Building Energy Simulation Users' News, Vol. 19, No. 1 (Spring 1998), pp. 6-12, Lawrence Berkeley National Laboratory, Berkeley CA, Electronic versions of the Users' News are available at <a href="http://gundog.lbl.gov">http://gundog.lbl.gov</a> . |

| Insulation (a) | Envelope insulation levels are based on location. See RESFEN 5 documentation, Table 6-1 for a list of Packages that correspond to each location. See Tables 6-3 and 6-4 for a list of R-values for each building component for each location. See Table 6 for a list of U-factors that correspond to the R-value constructions.  New construction: See Table 6-4. (Council of American Building Officials, 1993)  Existing construction: See Table 6-5. (Ritschard, et al. 1992) | New Construction: Envelope insulation levels based on location using 2006 IECC requirements in Table 402.1.1 (except for fenestration).  Existing: Same as RESFEN 5.0. |   |
|----------------|--|--|---|
| Infiltration   | New Construction: ELA=0.77 ft <sup>2</sup> (0.58 ACH) Existing Construction: ELA=1.00 ft <sup>2</sup> (0.70 ACH)   | New Construction:<br>SLA = 0.00036<br>Existing Construction:<br>SLA = 0.00054  | As proposed by NFRC. Consistent with 2006 IECC reference home Table 404.5.2(1). SLA is EA/total sf.  [Note: inconsistency between RESFEN 3.1/5.0 documentation and code; infiltration in code was set to SLA=.00057.] |

| Structural Mass (lb/ft²)                             | This is a parameter used in programs that don't explicitly model internal walls. In RESFEN, we use a simple equation to estimate the amount of internal walls per floor area: interior wall area = 0.527 * floor area RESFEN then models the amount of internal walls. Since interior walls are typically 2x4 16" oc with 0.5" of gypboard on each side, the amount of material per square foot of wall is  1" x 12" x 12" or 0.08333 ft3 of gypboard  3.5" x 1.625" x 12"/16 or 0.002469 ft3 of wood  The total weight per floor area of floor adds up to 2.24 lbs/ft2, which is somewhat lower than the the 3.5 lb/ft2 cited. But in a 2- story, there's also the floor that would add another 2.20 lbs/ft2, for a total of 4.44 lbs/ft2. This is consistent with the average value of 3.5 lb/ft2 in the IECC. | Internal walls are modeled explicitly as with RESFEN 5.  Where masonry floors are used: 80% of floor area covered by R-2 carpet and pad, and 20% of floor directly exposed to room air. This is in addition to the 3.5 lb/ft2/  Basement walls: masonry, and include insulation located on the exterior of the walls (new construction) and the interior side of the walls (existing construction). This is in addition to above. | Consistent with 2006 IECC reference home Table 404.5.2(1) average value. |
|--|--|---|--|
|  | Basement walls and slabs are modeled separately.   |   |  |
| <b>Internal Mass</b> Furniture (lb/ft <sup>2</sup> ) | 8.0 lb/ft <sup>2</sup> of floor area, in accordance with the Model Energy Code and NFRC Annual Energy Performance Subcommittee recommendation (September 1998).  | 8.0 lb/ft <sup>2</sup> of floor area  | Consistent with 2006 IECC reference home Table 404.5.2(1).               |

| Window Area (% Floor Area)  Variable Specific House: Variable Reference House: 15%  Reference House: 15%  Specific House: Variable Reference House: 15%  Item 18% is too high. A recent DOE/PNNL study from a few years ago found 13.5% to be average.  IECC implies that below 12% is low and above 18% is highwhich implies 15% (as used in RESFEN) is appropriate. | Obstruction: Exterior Obstructions, a completely opaque (t=0.0), same-height obstruction 20 feet away, intended to represent adjacent buildings.  Interior: Interior shades with a Seasonal SHGC multiplier, summer value = 0.80, winter value = 0.90.  Int+Ovh: Interior shades & 2' overhangs  Ovh+Obs: 2' overhangs & obstructions  All: Interior shades, 2' overhangs, & obstructions Typical(b): to represent a statistically average solar gain reduction for a generic house, this option includes:  Interior shades (Seasonal SHGC multiplier, summer value = 0.80, winter value = 0.90);  1' overhang; a 67% transmitting same- height obstruction 20' away intended to represent adjacent buildings.  To account for other sources of solar heat gain reduction (insect screens, trees, dirt, building & window self- shading), the SHGC multiplier was further reduced by 0.1. This results in a final winter SHGC multiplier of 0.8 and a final summer SHGC multiplier of 0.7. (Note these factors are multipliers; i.e. a window with a SHGC of 0.5 is reduced to 0.4 in the winter and 0.35 in the summer.) | Reference House uses Typical. |   |
|---|---|-------------------------------|---|
|   | Variable  |                               | ago found 13.5% to be average.  IECC implies that below 12% is low and above 18% is |

|    |                           |  |                                      | There is also Oil Heating in the NorthEast (49% in New England and 24% in Mid-Atlantic) in Existing Homes. Rather than model Oil homes in the NE region in Existing houses; or we can account for this later in the speadsheet part of this project. (Not much in New Construction.) |
|----|---------------------------|--|--------------------------------------|--|
| В  | <b>HVAC System Sizing</b> | For each climate, system sizes are fixed for all window options.           | Same as RESFEN 5 for Existing homes. | Consistent with 2006 IECC reference home Table 404.5.2(1).   |
| .6 |                           | Fixed sizes are based on the use of DOE-                                   |                                      | Section M1401.3 of the International Residential Code says "   |
|    |                           | 2 auto-sizing for the same house as defined in the analysis, with the most |                                      | Heating and cooling equipment shall be sized based on building loads calculated in accordance with ACCA  |

Specific House: Variable

Reference House: Evenly Distributed on All four

Gas furnace & A/C. Heat

Pump with A/C in South and

Autosizing is used for New

homes - they are sized

with the specific windows

chosen.

There are a significant number of Heat Pumps in the South

(half of new construction in the south) and some in the West

From http://www.census.gov/const/www/charindex.html

Manual J or other approved heating and cooling calculation

Look at Type of Heating Fuel; Data on

(presumably the SW).

Existing Construction

#singlecomplete

methodologies."

orientations.

SW

**Window Distribution** 

**HVAC System** 

Variable

Pump

(e)

Furnace & A/C, Heat

representative window for that specific

climate. An auto-sizing multiplier of 1.3

used to account for a typical safety factor.

| HVAC Efficiency          | New Construction:  AFUE = 0.78, A/C SEER=10.0  Existing Construction:  AFUE = 0.70, A/C SEER= 8.0 | New: Gas furnace: AFUE = 0.80 in climate zones 1-3, 0.90 in climate zones 4-8. A/C SEER = 13. Heat pump HSPF = 7.7; Oil furnace AFUE = 0.80  Existing: Gas furnace AFUE = 0.78; A/C (& Heat Pump) SEER = 10; Heat pump HSPF = 6.8 | For New, as per NFRC: Gas furnace: 2005 Gas Appliance Manufacturers Association data showed 34% of all U.S. furnaces sold are condensing (AFUE 90+%). We assume most of these are used in the north, so use new federal minimum (0.80) in zones 1-3, and condensing furnace (0.90) in zones 4-8. A/C: New federal minimum. Heat pump: New federal minimum.  Conversion from SEER or HPSF to COP (1/CEIR) for use in DOE2 using updated research: <a href="http://www.fsec.ucf.edu/en/publications/html/FSEC-PF-413-04/">http://www.fsec.ucf.edu/en/publications/html/FSEC-PF-413-04/</a> |
|--------------------------|---|---|--|
| <b>Duct Losses</b>       | Heating: 10% (fixed) Cooling: 10% (fixed)   | 12% for basement foundation  20% for crawlspace and slabon-grade foundations  | Consistent with 2006 IECC proposed design default distribution efficiencies (Table 404.5.2(2). As proposed by NFRC.  Duct losses entered into DOE2 by modifying efficiencies.  |
| Part-Load Performance    | New part-load curves for DOE2 (Henderson 1998) for both new and existing house types              | Same as RESFEN 5.   |  |
| Thermostat Settings      | Heating: 70°F, Cooling: 78°F Basement (partially conditioned): Heating 62°F, Cooling 85°F         | Heating: 70°F, Cooling: 78°F<br>Basement (partially<br>conditioned): Heating 62°F,<br>Cooling 85°F  |  |
| Night Heating<br>Setback | 65°F (11 PM – 6 AM <sup>(d)</sup> )   | 65°F (11 PM – 6 AM )  |  |
| Cooling Setup            | N/A   | N/A   |  |

| Internal Loads      | Sensible: 43,033 Btu/day + (floor area * 8.42 Btu/ft <sup>2</sup> -day for lighting) Latent: 12.2 kBtu/day  | Use IECC [Table 404.5.2(1)] proposal of: Internal gain (Btu/day) = 17,900 + 23.8×floor area + 4104×number of bedrooms. 3 bedrooms shall be used. | This includes latent as well as sensible, as well as lighting loads (per conversation with Phil Fairey, 1/11/08). The way FSEC uses the equation is for the total internal loads of the house. They then subtract out the people heat gain, which they model as per standard DOE-2/ASHRAE assumption (255 sensible/200 latent per person per hour, etc.). The remainder is then assumed to be 0.80 sensible and 0.20 latent.  The hourly profile is based on modeling assumptions developed by the California Energy Commission in 1980 (Mickey Horn and Cynthia Helmich 1980. "Assumptions Used with Energy Performance Computer Programs", Project Report No. 7 for "1980 Residential Building Standard Development Project", June 1980, P400-80-026, pp. 33-48). |
|---------------------|---|--|---|
| Natural Ventilation | Enthalpic – Sherman-Grimsrud (78°F / 72°F based on 4 days' history <sup>(e)</sup> ) Windows closed from 11pm to 6am. Only 25% of window area can be open for ventilation. Windows will only open if outdoor temperature has been below the setpoint for prior 4 days. | Maximum operable window area reduced from 25% to 12.5%. Max ACH capped at 10. Based on California research on use of windows for ventilation.    | RESFEN 6 algorithm updated based on the reported operation of windows in the recent Sherman and Price report, "Study of Ventilation Practices and Household Characteristics in New California Homes:" http://www.arb.ca.gov/research/apr/past/03-326.pdf  |
| Weather Data        | All TMY2 <sup>(f)</sup>   |  |   |
| Number of Locations | 239 US cities <sup>(f)</sup> 4 Canadian cities  | For E* analysis: 97 EWC climates plus Charlotte NC, Amarillo TX, and Prescott AZ   |   |
| Calculation Tool    | DOE-2.1E  | DOE 2.1E version 1.14  |   |

#### **Footnotes**

- (a) Insulation values do not include exterior siding, structural sheathing, and interior drywall. For examples, an R-19 requirement could be met EITHER by R-19 cavity insulation OR R-13 cavity insulation plus R-6 insulating sheathing. Wall requirements apply to wood-frame or mass (concrete, masonry, log) wall constructions, but do not apply to metal-frame construction."
- (b) These assumptions are intended to represent the average solar heat gain reduction for a large sample of houses. A one-foot overhang is assumed on all four orientations in order to represent the average of a two-foot overhang and no overhang. A 67% transmitting obstruction 20 feet away on all four orientations represents the average of obstructions (such as neighboring buildings and trees) 20 feet away on one-third of the total windows and no obstructions in front of the remaining two-thirds of windows. An interior shade is assumed to have a Solar Heat Gain Coefficient multiplier of 0.9 during the winter and 0.8 during the summer. To account for solar heat gain reducing effects from other sources such as screens, trees, dirt, and self-shading of the building, the SHGC multiplier was further reduced by 0.1 throughout the year. This amounts to a 12.5% decrease in the summer and an 11.1% decrease in the winter. The final SHGC multipliers (0.8 in the winter and 0.7 in the summer) thus reflect the combined effects of shading devices and other sources.

- RESFEN 5: For each climate, DOE-2's auto-sizing feature was used with the window most likely to be installed in new construction (assumed to be the MEC default). Tables 6.4 and 6.5 show the required prescriptive U-factors for windows for the 52 climates. For climates where the U-factor requirement is greater than or equal to 1.0, an aluminum frame window with single glazing (U-factor = 1.30; SHGC = 0.74) is used. For climates where the U-factor requirement is between 0.65 and 1.0, an aluminum frame window with double glazing (U-factor = 0.87; SHGC = 0.66) is used. For climates where the U-factor requirements are below 0.65, as well as in the four Canadian climates, a vinyl frame window with double glazing (U-factor = 0.49; SHGC = 0.57) is used for the sizing calculation.
- (d) RESFEN models a moderate setback of 65° F in recognition that some but not all houses may use night setbacks. Recent studies of residential indoor conditions have shown that, during the heating season, nighttime temperatures are significantly lower than daytime temperatures (Ref: "Occupancy Patterns and Energy Consumption in New California Houses," Berkeley Solar Group for the California Energy Commission, 1990).
- (e) RESFEN uses a feature in DOE-2 that allows the ventilation temperature to switch between a higher heating (or winter) and a lower cooling (or summer) temperature based on the cooling load over the previous four days.
- (f) RESFEN uses Typical Meteorological Year (TMY2) weather tapes from the National Renewable Energy Laboratory. There are 239 TMY2 locations with average weather data compiled from 30+ years of historical weather data. (National Renewable Energy Laboratory, 1995).

This work was supported by the Assistant Secretary for Energy Efficiency and Renewable Energy, Office of Building Technology, State and Community Programs, Office of Building Systems of the U.S. Department of Energy under Contract No. DE-AC03-76SF00098.

# Appendix C RESFEN Calculation Results

Smaller, Older Home (1-story, 1700 ft<sup>2</sup>)

| Climate Zone | Location     | Window   | HVAC         | Whole | House Cooling | Whole Ho | use Heating | Source | Energy | % source energy saving |
|--------------|--------------|--|--------------|-------|---------------|----------|-------------|--------|--------|------------------------|
| 8            | AK Fairbanks | Wood frame, single pane                        | Furnace / AC | 72    | kWh           | 354.1    | MBtu        | 387.5  | MBtu   |                        |
| 8            | AK Fairbanks | with exterior clear panel                      | Furnace / AC | 59    | kWh           | 301      | MBtu        | 329.4  | MBtu   | 15.0%                  |
| 8            | AK Fairbanks | with interior clear panel                      | Furnace / AC | 59    | kWh           | 297.8    | MBtu        | 325.9  | MBtu   | 15.9%                  |
| 8            | AK Fairbanks | with exterior low-e panel                      | Furnace / AC | 45    | kWh           | 289.7    | MBtu        | 316.9  | MBtu   | 18.2%                  |
| 8            | AK Fairbanks | with interior low-e panel                      | Furnace / AC | 56    | kWh           | 283.5    | MBtu        | 310.2  | MBtu   | 19.9%                  |
| 8            | AK Fairbanks | Wood frame, double pane                        | Furnace / AC | 66    | kWh           | 313.5    | MBtu        | 343.1  | MBtu   |                        |
| 8            | AK Fairbanks | with exterior clear panel                      | Furnace / AC | 53    | kWh           | 297.6    | MBtu        | 325.6  | MBtu   | 5.1%                   |
| 8            | AK Fairbanks | with interior clear panel                      | Furnace / AC | 58    | kWh           | 294.2    | MBtu        | 321.9  | MBtu   | 6.2%                   |
| 8            | AK Fairbanks | with exterior low-e panel                      | Furnace / AC | 40    | kWh           | 288.6    | MBtu        | 315.6  | MBtu   | 8.0%                   |
| 8            | AK Fairbanks | with interior low-e panel                      | Furnace / AC | 52    | kWh           | 283.8    | MBtu        | 310.5  | MBtu   | 9.5%                   |
| 8            | AK Fairbanks | Metal frame, double pane                       | Furnace / AC | 58    | kWh           | 332.3    | MBtu        | 363.5  | MBtu   |                        |
| 8            | AK Fairbanks | with exterior clear panel                      | Furnace / AC | 57    | kWh           | 305.5    | MBtu        | 334.3  | MBtu   | 8.1%                   |
| 8            | AK Fairbanks | with interior clear panel                      | Furnace / AC | 55    | kWh           | 301.9    | MBtu        | 330.3  | MBtu   | 9.1%                   |
| 8            | AK Fairbanks | with exterior low-e panel                      | Furnace / AC | 44    | kWh           | 293.3    | MBtu        | 320.8  | MBtu   | 11.8%                  |
| 8            | AK Fairbanks | with interior low-e panel                      | Furnace / AC | 49    | kWh           | 289.4    | MBtu        | 316.6  | MBtu   | 12.9%                  |
| 8            | AK Fairbanks | with exterior clear panel, worst case mounting | Furnace / AC | 52    | kWh           | 314.8    | MBtu        | 344.4  | MBtu   | 5.3%                   |
| 8            | AK Fairbanks | with exterior low-e panel, worst case mounting | Furnace / AC | 39    | kWh           | 307.5    | MBtu        | 336.2  | MBtu   | 7.5%                   |
| 7            | AK Anchorage | Wood frame, single pane                        | Furnace / AC | 12    | kWh           | 213.8    | MBtu        | 233.6  | MBtu   |                        |
| 7            | AK Anchorage | with exterior clear panel                      | Furnace / AC | 10    | kWh           | 173.9    | MBtu        | 190.0  | MBtu   | 18.7%                  |
| 7            | AK Anchorage | with interior clear panel                      | Furnace / AC | 10    | kWh           | 171.6    | MBtu        | 187.5  | MBtu   | 19.7%                  |
| 7            | AK Anchorage | with exterior low-e panel                      | Furnace / AC | 7     | kWh           | 165      | MBtu        | 180.3  | MBtu   | 22.8%                  |
| 7            | AK Anchorage | with interior low-e panel                      | Furnace / AC | 9     | kWh           | 160.2    | MBtu        | 175.0  | MBtu   | 25.1%                  |
| 7            | AK Anchorage | Wood frame, double pane                        | Furnace / AC | 11    | kWh           | 183.1    | MBtu        | 200.1  | MBtu   |                        |
| 7            | AK Anchorage | with exterior clear panel                      | Furnace / AC | 9     | kWh           | 171.6    | MBtu        | 187.5  | MBtu   | 6.3%                   |
| 7            | AK Anchorage | with interior clear panel                      | Furnace / AC | 9     | kWh           | 169.1    | MBtu        | 184.8  | MBtu   | 7.7%                   |
| 7            | AK Anchorage | with exterior low-e panel                      | Furnace / AC | 7     | kWh           | 164.3    | MBtu        | 179.5  | MBtu   | 10.3%                  |
| 7            | AK Anchorage | with interior low-e panel                      | Furnace / AC | 9     | kWh           | 160.6    | MBtu        | 175.5  | MBtu   | 12.3%                  |
| 7            | AK Anchorage | Metal frame, double pane                       | Furnace / AC | 9     | kWh           | 198.2    | MBtu        | 216.5  | MBtu   |                        |
| 7            | AK Anchorage | with exterior clear panel                      | Furnace / AC | 9     | kWh           | 177.8    | MBtu        | 194.3  | MBtu   | 10.3%                  |
| 7            | AK Anchorage | with interior clear panel                      | Furnace / AC | 9     | kWh           | 175.1    | MBtu        | 191.3  | MBtu   | 11.6%                  |
| 7            | AK Anchorage | with exterior low-e panel                      | Furnace / AC | 7     | kWh           | 167.9    | MBtu        | 183.4  | MBtu   | 15.3%                  |
| 7            | AK Anchorage | with interior low-e panel                      | Furnace / AC | 8     | kWh           | 164.9    | MBtu        | 180.2  | MBtu   | 16.8%                  |
| 7            | AK Anchorage | with exterior clear panel, worst case mounting | Furnace / AC | 9     | kWh           | 185.2    | MBtu        | 202.3  | MBtu   | 6.6%                   |
| 7            | AK Anchorage | with exterior low-e panel, worst case mounting | Furnace / AC | 6     | kWh           | 179.1    | MBtu        | 195.6  | MBtu   | 9.6%                   |

| Climate<br>Zone | Location     | Window   | Cooling<br>Cost (\$) | Heating Cost (\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|--------------|--|----------------------|-------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 8               | AK Fairbanks | Wood frame, single pane                        | 12.82                | 2931.54           | 2944.36         |                     |                       |                   |                      |
| 8               | AK Fairbanks | with exterior clear panel                      | 10.5                 | 2492.42           | 2502.92         | \$441.44            | 15.0%                 | 5.1               |                      |
| 8               | AK Fairbanks | with interior clear panel                      | 10.5                 | 2466.05           | 2476.55         | \$467.81            | 15.9%                 | 4.8               |                      |
| 8               | AK Fairbanks | with exterior low-e panel                      | 8.01                 | 2398.98           | 2406.99         | \$537.37            | 18.3%                 | 4.7               | 2.7                  |
| 8               | AK Fairbanks | with interior low-e panel                      | 9.97                 | 2347.55           | 2357.52         | \$586.84            | 19.9%                 | 4.3               | 2.1                  |
| 8               | AK Fairbanks | Wood frame, double pane                        | 11.75                | 2595.71           | 2607.46         |                     |                       |                   |                      |
| 8               | AK Fairbanks | with exterior clear panel                      | 9.43                 | 2463.88           | 2473.31         | \$134.15            | 5.1%                  | 16.8              |                      |
| 8               | AK Fairbanks | with interior clear panel                      | 10.32                | 2435.63           | 2445.95         | \$161.51            | 6.2%                  | 14.0              |                      |
| 8               | AK Fairbanks | with exterior low-e panel                      | 7.12                 | 2389.53           | 2396.65         | \$210.81            | 8.1%                  | 11.9              | 3.3                  |
| 8               | AK Fairbanks | with interior low-e panel                      | 9.26                 | 2350.01           | 2359.27         | \$248.19            | 9.5%                  | 10.1              | 2.9                  |
| 8               | AK Fairbanks | Metal frame, double pane                       | 10.32                | 2751.44           | 2761.76         |                     |                       |                   |                      |
| 8               | AK Fairbanks | with exterior clear panel                      | 10.15                | 2529.77           | 2539.92         | \$221.84            | 8.0%                  | 10.2              |                      |
| 8               | AK Fairbanks | with interior clear panel                      | 9.79                 | 2499.72           | 2509.51         | \$252.25            | 9.1%                  | 8.9               |                      |
| 8               | AK Fairbanks | with exterior low-e panel                      | 7.83                 | 2428.57           | 2436.4          | \$325.36            | 11.8%                 | 7.7               | 2.5                  |
| 8               | AK Fairbanks | with interior low-e panel                      | 8.72                 | 2396.13           | 2404.85         | \$356.91            | 12.9%                 | 7.0               | 2.4                  |
| 8               | AK Fairbanks | with exterior clear panel, worst case mounting | 9.26                 | 2606.39           | 2615.65         | \$146.11            | 5.3%                  | 15.4              |                      |
| 8               | AK Fairbanks | with exterior low-e panel, worst case mounting | 6.94                 | 2546.04           | 2552.98         | \$208.78            | 7.6%                  | 12.0              |                      |
| 7               | AK Anchorage | Wood frame, single pane                        | 2.14                 | 1770.6            | 1772.74         |                     |                       |                   |                      |
| 7               | AK Anchorage | with exterior clear panel                      | 1.78                 | 1439.88           | 1441.66         | \$331.08            | 18.7%                 | 6.8               |                      |
| 7               | AK Anchorage | with interior clear panel                      | 1.78                 | 1420.92           | 1422.7          | \$350.04            | 19.7%                 | 6.4               |                      |
| 7               | AK Anchorage | with exterior low-e panel                      | 1.25                 | 1365.89           | 1367.14         | \$405.60            | 22.9%                 | 6.2               | 3.4                  |
| 7               | AK Anchorage | with interior low-e panel                      | 1.6                  | 1326.62           | 1328.22         | \$444.52            | 25.1%                 | 5.7               | 2.7                  |
| 7               | AK Anchorage | Wood frame, double pane                        | 1.96                 | 1516.05           | 1518.01         |                     |                       |                   |                      |
| 7               | AK Anchorage | with exterior clear panel                      | 1.6                  | 1421.05           | 1422.65         | \$95.36             | 6.3%                  | 23.7              |                      |
| 7               | AK Anchorage | with interior clear panel                      | 1.6                  | 1400.41           | 1402.01         | \$116.00            | 7.6%                  | 19.5              |                      |
| 7               | AK Anchorage | with exterior low-e panel                      | 1.25                 | 1360.11           | 1361.36         | \$156.65            | 10.3%                 | 16.0              | 4.2                  |
| 7               | AK Anchorage | with interior low-e panel                      | 1.6                  | 1329.73           | 1331.33         | \$186.68            | 12.3%                 | 13.5              | 3.6                  |
| 7               | AK Anchorage | Metal frame, double pane                       | 1.6                  | 1640.8            | 1642.4          |                     |                       |                   |                      |
| 7               | AK Anchorage | with exterior clear panel                      | 1.6                  | 1472.51           | 1474.11         | \$168.29            | 10.2%                 | 13.4              | 1                    |
| 7               | AK Anchorage | with interior clear panel                      | 1.6                  | 1449.75           | 1451.35         | \$191.05            | 11.6%                 | 11.8              | 1                    |
| 7               | AK Anchorage | with exterior low-e panel                      | 1.25                 | 1390.32           | 1391.57         | \$250.83            | 15.3%                 | 10.0              | 3.1                  |
| 7               | AK Anchorage | with interior low-e panel                      | 1.42                 | 1365.31           | 1366.73         | \$275.67            | 16.8%                 | 9.1               | 3.0                  |
| 7               | AK Anchorage | with exterior clear panel, worst case mounting | 1.6                  | 1533.12           | 1534.72         | \$107.68            | 6.6%                  | 21.0              | 1                    |
| 7               | AK Anchorage | with exterior low-e panel, worst case mounting | 1.07                 | 1482.79           | 1483.86         | \$158.54            | 9.7%                  | 15.8              | 1                    |

| Climate Zone | e Location     | Window   | HVAC         | Whole I | House Cooling | Whole Ho | use Heating | Source | Energy | % source energy savings |
|--------------|----------------|--|--------------|---------|---------------|----------|-------------|--------|--------|-------------------------|
| 7            | MN Duluth      | Wood frame, single pane                        | Furnace / AC | 194     | kWh           | 220.6    | MBtu        | 243.1  | MBtu   |                         |
| 7            | MN Duluth      | with exterior clear panel                      | Furnace / AC | 161     | kWh           | 176      | MBtu        | 194.0  | MBtu   | 20.2%                   |
| 7            | MN Duluth      | with interior clear panel                      | Furnace / AC | 167     | kWh           | 173.5    | MBtu        | 191.4  | MBtu   | 21.3%                   |
| 7            | MN Duluth      | with exterior low-e panel                      | Furnace / AC | 137     | kWh           | 167.3    | MBtu        | 184.3  | MBtu   | 24.2%                   |
| 7            | MN Duluth      | with interior low-e panel                      | Furnace / AC | 159     | kWh           | 162      | MBtu        | 178.7  | MBtu   | 26.5%                   |
| 7            | MN Duluth      | Wood frame, double pane                        | Furnace / AC | 181     | kWh           | 185.9    | MBtu        | 205.1  | MBtu   |                         |
| 7            | MN Duluth      | with exterior clear panel                      | Furnace / AC | 147     | kWh           | 173.7    | MBtu        | 191.4  | MBtu   | 6.7%                    |
| 7            | MN Duluth      | with interior clear panel                      | Furnace / AC | 157     | kWh           | 170.9    | MBtu        | 188.4  | MBtu   | 8.1%                    |
| 7            | MN Duluth      | with exterior low-e panel                      | Furnace / AC | 128     | kWh           | 166.8    | MBtu        | 183.6  | MBtu   | 10.5%                   |
| 7            | MN Duluth      | with interior low-e panel                      | Furnace / AC | 147     | kWh           | 162.5    | MBtu        | 179.1  | MBtu   | 12.7%                   |
| 7            | MN Duluth      | Metal frame, double pane                       | Furnace / AC | 159     | kWh           | 202.1    | MBtu        | 222.5  | MBtu   |                         |
| 7            | MN Duluth      | with exterior clear panel                      | Furnace / AC | 154     | kWh           | 180.1    | MBtu        | 198.4  | MBtu   | 10.8%                   |
| 7            | MN Duluth      | with interior clear panel                      | Furnace / AC | 150     | kWh           | 177.1    | MBtu        | 195.1  | MBtu   | 12.3%                   |
| 7            | MN Duluth      | with exterior low-e panel                      | Furnace / AC | 138     | kWh           | 170.5    | MBtu        | 187.8  | MBtu   | 15.6%                   |
| 7            | MN Duluth      | with interior low-e panel                      | Furnace / AC | 143     | kWh           | 167      | MBtu        | 184.0  | MBtu   | 17.3%                   |
| 7            | MN Duluth      | with exterior clear panel, worst case mounting | Furnace / AC | 147     | kWh           | 188      | MBtu        | 207.0  | MBtu   | 7.0%                    |
| 7            | MN Duluth      | with exterior low-e panel, worst case mounting | Furnace / AC | 124     | kWh           | 182.3    | MBtu        | 200.5  | MBtu   | 9.9%                    |
| 6            | MN Minneapolis | Wood frame, single pane                        | Furnace / AC | 800     | kWh           | 163.3    | MBtu        | 187.5  | MBtu   |                         |
| 6            | MN Minneapolis | with exterior clear panel                      | Furnace / AC | 691     | kWh           | 128.3    | MBtu        | 148.0  | MBtu   | 21.1%                   |
| 6            | MN Minneapolis | with interior clear panel                      | Furnace / AC | 690     | kWh           | 126.4    | MBtu        | 146.0  | MBtu   | 22.2%                   |
| 6            | MN Minneapolis | with exterior low-e panel                      | Furnace / AC | 619     | kWh           | 121.5    | MBtu        | 139.8  | MBtu   | 25.5%                   |
| 6            | MN Minneapolis | with interior low-e panel                      | Furnace / AC | 671     | kWh           | 117.4    | MBtu        | 135.9  | MBtu   | 27.5%                   |
| 6            | MN Minneapolis | Wood frame, double pane                        | Furnace / AC | 739     | kWh           | 136.1    | MBtu        | 157.1  | MBtu   |                         |
| 6            | MN Minneapolis | with exterior clear panel                      | Furnace / AC | 658     | kWh           | 126.5    | MBtu        | 145.7  | MBtu   | 7.3%                    |
| 6            | MN Minneapolis | with interior clear panel                      | Furnace / AC | 679     | kWh           | 124.3    | MBtu        | 143.5  | MBtu   | 8.6%                    |
| 6            | MN Minneapolis | with exterior low-e panel                      | Furnace / AC | 590     | kWh           | 121.1    | MBtu        | 139.0  | MBtu   | 11.5%                   |
| 6            | MN Minneapolis | with interior low-e panel                      | Furnace / AC | 648     | kWh           | 117.7    | MBtu        | 136.0  | MBtu   | 13.5%                   |
| 6            | MN Minneapolis | Metal frame, double pane                       | Furnace / AC | 700     | kWh           | 148.7    | MBtu        | 170.4  | MBtu   |                         |
| 6            | MN Minneapolis | with exterior clear panel                      | Furnace / AC | 682     | kWh           | 131.5    | MBtu        | 151.4  | MBtu   | 11.1%                   |
| 6            | MN Minneapolis | with interior clear panel                      | Furnace / AC | 669     | kWh           | 129.2    | MBtu        | 148.8  | MBtu   | 12.7%                   |
| 6            | MN Minneapolis | with exterior low-e panel                      | Furnace / AC | 610     | kWh           | 124      | MBtu        | 142.4  | MBtu   | 16.4%                   |
| 6            | MN Minneapolis | with interior low-e panel                      | Furnace / AC | 635     | kWh           | 121.2    | MBtu        | 139.6  | MBtu   | 18.1%                   |
| 6            | MN Minneapolis | with exterior clear panel, worst case mounting | Furnace / AC | 656     | kWh           | 137.6    | MBtu        | 157.8  | MBtu   | 7.4%                    |
| 6            | MN Minneapolis | with exterior low-e panel, worst case mounting | Furnace / AC | 583     | kWh           | 133.2    | MBtu        | 152.1  | MBtu   | 10.7%                   |

| Climate<br>Zone | Location                | Window   | Cooling<br>Cost (\$) | Heating Cost (\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|-------------------------|--|----------------------|-------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 7               | MN Duluth               | Wood frame, single pane                        | 22.06                | 1718.71           | 1740.77         |                     |                       |                   |                      |
| 7               | MN Duluth               | with exterior clear panel                      | 18.31                | 1370.78           | 1389.09         | \$351.68            | 20.2%                 | 6.4               |                      |
| 7               | MN Duluth               | with interior clear panel                      | 19.04                | 1351.27           | 1370.31         | \$370.46            | 21.3%                 | 6.1               |                      |
| 7               | MN Duluth               | with exterior low-e panel                      | 15.62                | 1303.44           | 1319.06         | \$421.71            | 24.2%                 | 6.0               | 3.6                  |
| 7               | MN Duluth               | with interior low-e panel                      | 18.13                | 1261.89           | 1280.02         | \$460.75            | 26.5%                 | 5.5               | 2.8                  |
| 7               | MN Duluth               | Wood frame, double pane                        | 20.63                | 1448.21           | 1468.84         |                     |                       |                   |                      |
| 7               | MN Duluth               | with exterior clear panel                      | 16.76                | 1353.33           | 1370.09         | \$98.75             | 6.7%                  | 22.9              |                      |
| 7               | MN Duluth               | with interior clear panel                      | 17.9                 | 1331.16           | 1349.06         | \$119.78            | 8.2%                  | 18.8              |                      |
| 7               | MN Duluth               | with exterior low-e panel                      | 14.59                | 1299.38           | 1313.97         | \$154.87            | 10.5%                 | 16.2              | 4.5                  |
| 7               | MN Duluth               | with interior low-e panel                      | 16.76                | 1265.96           | 1282.72         | \$186.12            | 12.7%                 | 13.5              | 3.8                  |
| 7               | MN Duluth               | Metal frame, double pane                       | 18.13                | 1574.57           | 1592.7          |                     |                       |                   |                      |
| 7               | MN Duluth               | with exterior clear panel                      | 17.56                | 1402.77           | 1420.33         | \$172.37            | 10.8%                 | 13.1              |                      |
| 7               | MN Duluth               | with interior clear panel                      | 17.1                 | 1379.85           | 1396.95         | \$195.75            | 12.3%                 | 11.5              |                      |
| 7               | MN Duluth               | with exterior low-e panel                      | 15.73                | 1327.95           | 1343.68         | \$249.02            | 15.6%                 | 10.1              | 3.3                  |
| 7               | MN Duluth               | with interior low-e panel                      | 16.3                 | 1300.94           | 1317.24         | \$275.46            | 17.3%                 | 9.1               | 3.2                  |
| 7               | MN Duluth               | with exterior clear panel, worst case mounting | 16.76                | 1464.14           | 1480.9          | \$111.80            | 7.0%                  | 20.2              |                      |
| 7               | MN Duluth               | with exterior low-e panel, worst case mounting | 14.14                | 1419.75           | 1433.89         | \$158.81            | 10.0%                 | 15.8              |                      |
| 6               | MN<br>Minneapolis<br>MN | Wood frame, single pane                        | 90.96                | 1272.24           | 1363.2          |                     |                       |                   |                      |
| 6               | Minneapolis<br>MN       | with exterior clear panel                      | 78.57                | 999.59            | 1078.16         | \$285.04            | 20.9%                 | 7.9               |                      |
| 6               | Minneapolis<br>MN       | with interior clear panel                      | 78.66                | 984.34            | 1063            | \$300.20            | 22.0%                 | 7.5               |                      |
| 6               | Minneapolis<br>MN       | with exterior low-e panel                      | 70.57                | 946.85            | 1017.42         | \$345.78            | 25.4%                 | 7.3               | 4.2                  |
| 6               | Minneapolis             | with interior low-e panel                      | 76.49                | 914.31            | 990.8           | \$372.40            | 27.3%                 | 6.7               | 3.5                  |
| 6               | MN<br>Minneapolis       | Wood frame, double pane                        | 84.25                | 1060.08           | 1144.33         |                     |                       |                   |                      |
| 6               | MN<br>Minneapolis<br>MN | with exterior clear panel                      | 75.01                | 985.7             | 1060.71         | \$83.62             | 7.3%                  | 27.0              |                      |
| 6               | Minneapolis<br>MN       | with interior clear panel                      | 77.41                | 968.35            | 1045.76         | \$98.57             | 8.6%                  | 22.9              |                      |
| 6               | Minneapolis<br>MN       | with exterior low-e panel                      | 67.26                | 943.56            | 1010.82         | \$133.51            | 11.7%                 | 18.8              | 5.1                  |
| 6               | Minneapolis             | with interior low-e panel                      | 73.87                | 917.15            | 991.02          | \$153.31            | 13.4%                 | 16.4              | 4.7                  |
| 6               | MN<br>Minneapolis<br>MN | Metal frame, double pane                       | 79.8                 | 1158.66           | 1238.46         |                     |                       |                   |                      |
| 6               | Minneapolis<br>MN       | with exterior clear panel                      | 77.75                | 1024.24           | 1101.99         | \$136.47            | 11.0%                 | 16.5              |                      |
| 6               | Minneapolis<br>MN       | with interior clear panel                      | 76.27                | 1006.27           | 1082.54         | \$155.92            | 12.6%                 | 14.5              |                      |
| 6               | Minneapolis             | with exterior low-e panel                      | 69.54                | 965.69            | 1035.23         | \$203.23            | 16.4%                 | 12.4              | 3.8                  |

| 6 | MN<br>Minneapolis<br>MN<br>Minneapolis | with interior low-e panel with exterior clear panel, worst case mounting | 72.39<br>74.78 | 944.49<br>1072.19 | 1016.88<br>1146.97 | \$221.58<br>\$91.49 | <b>17.9%</b> 7.4% | <b>11.3</b> 24.7 | 3.9 |
|---|--|--|----------------|-------------------|--------------------|---------------------|-------------------|------------------|-----|
| 6 | MN<br>Minneapolis                      | with exterior low-e panel, worst case mounting                           | 66.46          | 1037.5            | 1103.96            | \$134.50            | 10.9%             | 18.7             |     |

| Climate Zone | Location      | Window   | HVAC         | Whole H | louse Cooling | Whole Ho | use Heating | Source     | Energy | % source energy savings |
|--------------|---------------|--|--------------|---------|---------------|----------|-------------|------------|--------|-------------------------|
| 6            | VT Burlington | Wood frame, single pane                        | Furnace / AC | 454     | kWh           | 155      | MBtu        | 174.5      | MBtu   |                         |
| 6            | VT Burlington | with exterior clear panel                      | Furnace / AC | 388     | kWh           | 122.2    | MBtu        | 137.9      | MBtu   | 21.0%                   |
| 6            | VT Burlington | with interior clear panel                      | Furnace / AC | 389     | kWh           | 120.3    | MBtu        | 135.8      | MBtu   | 22.1%                   |
| 6            | VT Burlington | with exterior low-e panel                      | Furnace / AC | 340     | kWh           | 115.6    | MBtu        | 130.1      | MBtu   | 25.4%                   |
| 6            | VT Burlington | with interior low-e panel                      | Furnace / AC | 377     | kWh           | 111.6    | MBtu        | 126.2      | MBtu   | 27.7%                   |
| 6            | VT Burlington | Wood frame, double pane                        | Furnace / AC | 418     | kWh           | 129.5    | MBtu        | 146.2      | MBtu   |                         |
| 6            | VT Burlington | with exterior clear panel                      | Furnace / AC | 367     | kWh           | 120.6    | MBtu        | 135.9      | MBtu   | 7.0%                    |
| 6            | VT Burlington | with interior clear panel                      | Furnace / AC | 380     | kWh           | 118.4    | MBtu        | 133.7      | MBtu   | 8.6%                    |
| 6            | VT Burlington | with exterior low-e panel                      | Furnace / AC | 320     | kWh           | 115.2    | MBtu        | 129.5      | MBtu   | 11.4%                   |
| 6            | VT Burlington | with interior low-e panel                      | Furnace / AC | 362     | kWh           | 112      | MBtu        | 126.5      | MBtu   | 13.5%                   |
| 6            | VT Burlington | Metal frame, double pane                       | Furnace / AC | 391     | kWh           | 141.7    | MBtu        | 159.2      | MBtu   |                         |
| 6            | VT Burlington | with exterior clear panel                      | Furnace / AC | 381     | kWh           | 125.3    | MBtu        | 141.2      | MBtu   | 11.3%                   |
| 6            | VT Burlington | with interior clear panel                      | Furnace / AC | 372     | kWh           | 123.2    | MBtu        | 138.8      | MBtu   | 12.8%                   |
| 6            | VT Burlington | with exterior low-e panel                      | Furnace / AC | 334     | kWh           | 118      | MBtu        | 132.7      | MBtu   | 16.7%                   |
| 6            | VT Burlington | with interior low-e panel                      | Furnace / AC | 352     | kWh           | 115.4    | MBtu        | 130.1      | MBtu   | 18.3%                   |
| 6            | VT Burlington | with exterior clear panel, worst case mounting | Furnace / AC | 363     | kWh           | 131.3    | MBtu        | 147.5      | MBtu   | 7.3%                    |
| 6            | VT Burlington | with exterior low-e panel, worst case mounting | Furnace / AC | 317     | kWh           | 126.9    | MBtu        | 142.2      | MBtu   | 10.7%                   |
| 5            | CO Denver     | Wood frame, single pane                        | Furnace / AC | 973     | kWh           | 109.3    | MBtu        | 130.5      | MBtu   |                         |
| 5            | CO Denver     | with exterior clear panel                      | Furnace / AC | 865     | kWh           | 87       | MBtu        | 104.9      | MBtu   | 19.6%                   |
| 5            | CO Denver     | with interior clear panel                      | Furnace / AC | 867     | kWh           | 85.8     | MBtu        | 103.6      | MBtu   | 20.6%                   |
| 5            | CO Denver     | with exterior low-e panel                      | Furnace / AC | 779     | kWh           | 82.3     | MBtu        | 98.8       | MBtu   | 24.3%                   |
| 5            | CO Denver     | with interior low-e panel                      | Furnace / AC | 842     | kWh           | 79       | MBtu        | 95.9       | MBtu   | 26.5%                   |
| 5            | CO Denver     | Wood frame, double pane                        | Furnace / AC | 917     | kWh           | 91.8     | MBtu        | 110.8      | MBtu   |                         |
| 5            | CO Denver     | with exterior clear panel                      | Furnace / AC | 827     | kWh           | 86.1     | MBtu        | 103.5      | MBtu   | 6.6%                    |
| 5            | CO Denver     | with interior clear panel                      | Furnace / AC | 853     | kWh           | 84.5     | MBtu        | 102.1      | MBtu   | 7.9%                    |
| 5            | CO Denver     | with exterior low-e panel                      | Furnace / AC | 745     | kWh           | 82.3     | MBtu        | 98.4       | MBtu   | 11.1%                   |
| 5            | CO Denver     | with interior low-e panel                      | Furnace / AC | 813     | kWh           | 79.5     | MBtu        | 96.1       | MBtu   | 13.2%                   |
| 5            | CO Denver     | Metal frame, double pane                       | Furnace / AC | 879     | kWh           | 101.7    | MBtu        | 121.1      | MBtu   |                         |
| 5            | CO Denver     | with exterior clear panel                      | Furnace / AC | 856     | kWh           | 89.7     | MBtu        | 107.8 MBtu |        | 11.0%                   |
| 5            | CO Denver     | with interior clear panel                      | Furnace / AC | 841     | kWh           | 88.3     | MBtu        | 106.1 MBtu |        | 12.4%                   |
| 5            | CO Denver     | with exterior low-e panel                      | Furnace / AC | 771     | kWh           | 84.3     | MBtu        | 100.9      | MBtu   | 16.7%                   |
| 5            | CO Denver     | with interior low-e panel                      | Furnace / AC | 800     | kWh           | 82.2     | MBtu        |            |        | 18.3%                   |
| 5            | CO Denver     | with exterior clear panel, worst case mounting | Furnace / AC | 830     | kWh           | 94.6     | MBtu        | 112.8      | MBtu   | 6.9%                    |
| 5            | CO Denver     | with exterior low-e panel, worst case mounting | Furnace / AC | 746     | kWh           | 91.6     | MBtu        | 108.6      | MBtu   | 10.4%                   |

| Climate<br>Zone | Location      | Window   | Cooling Cost (\$) | Heating Cost<br>(\$) | Total Cost<br>(\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e                  |
|-----------------|---------------|--|-------------------|----------------------|--------------------|---------------------|-----------------------|-------------------|---------------------------------------|
| 6               | VT Burlington | Wood frame, single pane                        | 78.59             | 2534.43              | 2613.02            |                     |                       |                   |                                       |
| 6               | VT Burlington | with exterior clear panel                      | 67.12             | 1997.89              | 2065.01            | \$548.01            | 21.0%                 | 4.1               |                                       |
| 6               | VT Burlington | with interior clear panel                      | 67.3              | 1967.56              | 2034.86            | \$578.16            | 22.1%                 | 3.9               |                                       |
| 6               | VT Burlington | with exterior low-e panel                      | 58.82             | 1890.27              | 1949.09            | \$663.93            | 25.4%                 | 3.8               | 2.2                                   |
| 6               | VT Burlington | with interior low-e panel                      | 65.22             | 1824.17              | 1889.39            | \$723.63            | 27.7%                 | 3.5               | 1.8                                   |
| 6               | VT Burlington | Wood frame, double pane                        | 72.31             | 2117.37              | 2189.68            |                     |                       |                   |                                       |
| 6               | VT Burlington | with exterior clear panel                      | 63.49             | 1971.09              | 2034.58            | \$155.10            | 7.1%                  | 14.6              |                                       |
| 6               | VT Burlington | with interior clear panel                      | 65.74             | 1936.35              | 2002.09            | \$187.59            | 8.6%                  | 12.0              |                                       |
| 6               | VT Burlington | with exterior low-e panel                      | 55.36             | 1884.26              | 1939.62            | \$250.06            | 11.4%                 | 10.0              | 2.7                                   |
| 6               | VT Burlington | with interior low-e panel                      | 62.63             | 1830.73              | 1893.36            | \$296.32            | 13.5%                 | 8.5               | 2.3                                   |
| 6               | VT Burlington | Metal frame, double pane                       | 67.64             | 2316.88              | 2384.52            |                     |                       |                   |                                       |
| 6               | VT Burlington | with exterior clear panel                      | 65.91             | 2049.24              | 2115.15            | \$269.37            | 11.3%                 | 8.4               |                                       |
| 6               | VT Burlington | with interior clear panel                      | 64.36             | 2013.5               | 2077.86            | \$306.66            | 12.9%                 | 7.4               |                                       |
| 6               | VT Burlington | with exterior low-e panel                      | 57.78             | 1928.89              | 1986.67            | \$397.85            | 16.7%                 | 6.3               | 2.0                                   |
| 6               | VT Burlington | with interior low-e panel                      | 60.9              | 1886.27              | 1947.17            | \$437.35            | 18.3%                 | 5.7               | 2.0                                   |
| 6               | VT Burlington | with exterior clear panel, worst case mounting | 62.8              | 2146.15              | 2208.95            | \$175.57            | 7.4%                  | 12.9              |                                       |
| 6               | VT Burlington | with exterior low-e panel, worst case mounting | 54.84             | 2075.44              | 2130.28            | \$254.24            | 10.7%                 | 9.9               |                                       |
| 5               | CO Denver     | Wood frame, single pane                        | 110.63            | 881.79               | 992.42             |                     |                       |                   |                                       |
| 5               | CO Denver     | with exterior clear panel                      | 98.61             | 702.45               | 801.06             | \$191.36            | 19.3%                 | 11.8              |                                       |
| 5               | CO Denver     | with interior clear panel                      | 98.84             | 692.17               | 791.01             | \$201.41            | 20.3%                 | 11.2              |                                       |
| 5               | CO Denver     | with exterior low-e panel                      | 88.81             | 664.54               | 753.35             | \$239.07            | 24.1%                 | 10.5              | 5.3                                   |
| 5               | CO Denver     | with interior low-e panel                      | 95.99             | 637.13               | 733.12             | \$259.30            | 26.1%                 | 9.7               | 4.4                                   |
| 5               | CO Denver     | Wood frame, double pane                        | 104.54            | 741.08               | 845.62             |                     |                       |                   |                                       |
| 5               | CO Denver     | with exterior clear panel                      | 94.28             | 694.91               | 789.19             | \$56.43             | 6.7%                  | 40.0              |                                       |
| 5               | CO Denver     | with interior clear panel                      | 97.24             | 681.71               | 778.95             | \$66.67             | 7.9%                  | 33.8              |                                       |
| 5               | CO Denver     | with exterior low-e panel                      | 84.93             | 664.35               | 749.28             | \$96.34             | 11.4%                 | 26.1              | 6.4                                   |
| 5               | CO Denver     | with interior low-e panel                      | 92.68             | 641.31               | 733.99             | \$111.63            | 13.2%                 | 22.5              | 5.7                                   |
| 5               | CO Denver     | Metal frame, double pane                       | 100.21            | 820.86               | 921.07             |                     |                       |                   | · · · · · · · · · · · · · · · · · · · |
| 5               | CO Denver     | with exterior clear panel                      | 97.58             | 724.26               | 821.84             | \$99.23             | 10.8%                 | 22.7              |                                       |
| 5               | CO Denver     | with interior clear panel                      | 95.87             | 712.48               | 808.35             | \$112.72            | 12.2%                 | 20.0              |                                       |
| 5               | CO Denver     | with exterior low-e panel                      | 87.89             | 680.7                | 768.59             | \$152.48            | 16.6%                 | 16.5              | 4.8                                   |
| 5               | CO Denver     | with interior low-e panel                      | 91.2              | 663.71               | 754.91             | \$166.16            | 18.0%                 | 15.1              | 4.8                                   |
| 5               | CO Denver     | with exterior clear panel, worst case mounting | 94.62             | 763.31               | 857.93             | \$63.14             | 6.9%                  | 35.7              |                                       |
| 5               | CO Denver     | with exterior low-e panel, worst case mounting | 85.04             | 738.95               | 823.99             | \$97.08             | 10.5%                 | 25.9              |                                       |

| Climate Zone | Location   | Window   | HVAC         | Whole H | ouse Cooling | Whole Hou | ise Heating | Source | Energy | % source energy savings |
|--------------|------------|--|--------------|---------|--------------|-----------|-------------|--------|--------|-------------------------|
| 5            | ID Boise   | Wood frame, single pane                        | Furnace / AC | 1184    | kWh          | 110.4     | MBtu        | 134.2  | MBtu   |                         |
| 5            | ID Boise   | with exterior clear panel                      | Furnace / AC | 1041    | kWh          | 87.3      | MBtu        | 107.3  | MBtu   | 20.0%                   |
| 5            | ID Boise   | with interior clear panel                      | Furnace / AC | 1042    | kWh          | 86.1      | MBtu        | 106.0  | MBtu   | 21.0%                   |
| 5            | ID Boise   | with exterior low-e panel                      | Furnace / AC | 945     | kWh          | 82.5      | MBtu        | 100.9  | MBtu   | 24.8%                   |
| 5            | ID Boise   | with interior low-e panel                      | Furnace / AC | 1006    | kWh          | 79.2      | MBtu        | 98.0   | MBtu   | 26.9%                   |
| 5            | ID Boise   | Wood frame, double pane                        | Furnace / AC | 1101    | kWh          | 92.4      | MBtu        | 113.5  | MBtu   |                         |
| 5            | ID Boise   | with exterior clear panel                      | Furnace / AC | 1003    | kWh          | 86.4      | MBtu        | 105.9  | MBtu   | 6.8%                    |
| 5            | ID Boise   | with interior clear panel                      | Furnace / AC | 1026    | kWh          | 84.8      | MBtu        | 104.4  | MBtu   | 8.1%                    |
| 5            | ID Boise   | with exterior low-e panel                      | Furnace / AC | 905     | kWh          | 82.4      | MBtu        | 100.4  | MBtu   | 11.6%                   |
| 5            | ID Boise   | with interior low-e panel                      | Furnace / AC | 977     | kWh          | 79.7      | MBtu        | 98.3   | MBtu   | 13.5%                   |
| 5            | ID Boise   | Metal frame, double pane                       | Furnace / AC | 1075    | kWh          | 102.1     | MBtu        | 123.8  | MBtu   |                         |
| 5            | ID Boise   | with exterior clear panel                      | Furnace / AC | 1039    | kWh          | 90        | MBtu        | 110.2  | MBtu   | 11.0%                   |
| 5            | ID Boise   | with interior clear panel                      | Furnace / AC | 1021    | kWh          | 88.5      | MBtu        | 108.4  | MBtu   | 12.5%                   |
| 5            | ID Boise   | with exterior low-e panel                      | Furnace / AC | 937     | kWh          | 84.4      | MBtu        | 102.9  | MBtu   | 16.9%                   |
| 5            | ID Boise   | with interior low-e panel                      | Furnace / AC | 968     | kWh          | 82.4      | MBtu        | 101.1  | MBtu   | 18.4%                   |
| 5            | ID Boise   | with exterior clear panel, worst case mounting | Furnace / AC | 1017    | kWh          | 94.7      | MBtu        | 115.1  | MBtu   | 7.1%                    |
| 5            | ID Boise   | with exterior low-e panel, worst case mounting | Furnace / AC | 919     | kWh          | 91.5      | MBtu        | 110.5  | MBtu   | 10.8%                   |
| 5            | IL Chicago | Wood frame, single pane                        | Furnace / AC | 979     | kWh          | 134.6     | MBtu        | 158.2  | MBtu   |                         |
| 5            | IL Chicago | with exterior clear panel                      | Furnace / AC | 862     | kWh          | 105.9     | MBtu        | 125.5  | MBtu   | 20.7%                   |
| 5            | IL Chicago | with interior clear panel                      | Furnace / AC | 864     | kWh          | 104.3     | MBtu        | 123.8  | MBtu   | 21.7%                   |
| 5            | IL Chicago | with exterior low-e panel                      | Furnace / AC | 787     | kWh          | 100.2     | MBtu        | 118.5  | MBtu   | 25.1%                   |
| 5            | IL Chicago | with interior low-e panel                      | Furnace / AC | 847     | kWh          | 96.7      | MBtu        | 115.3  | MBtu   | 27.1%                   |
| 5            | IL Chicago | Wood frame, double pane                        | Furnace / AC | 912     | kWh          | 112.3     | MBtu        | 133.1  | MBtu   |                         |
| 5            | IL Chicago | with exterior clear panel                      | Furnace / AC | 831     | kWh          | 104.5     | MBtu        | 123.7  | MBtu   | 7.1%                    |
| 5            | IL Chicago | with interior clear panel                      | Furnace / AC | 851     | kWh          | 102.7     | MBtu        | 121.9  | MBtu   | 8.4%                    |
| 5            | IL Chicago | with exterior low-e panel                      | Furnace / AC | 750     | kWh          | 99.9      | MBtu        | 117.7  | MBtu   | 11.6%                   |
| 5            | IL Chicago | with interior low-e panel                      | Furnace / AC | 820     | kWh          | 97.1      | MBtu        | 115.4  | MBtu   | 13.3%                   |
| 5            | IL Chicago | Metal frame, double pane                       | Furnace / AC | 875     | kWh          | 123       | MBtu        | 144.4  | MBtu   |                         |
| 5            | IL Chicago | with exterior clear panel                      | Furnace / AC | 852     | kWh          | 108.7     | MBtu        | 128.5  | MBtu   | 11.0%                   |
| 5            | IL Chicago | with interior clear panel                      | Furnace / AC | 842     | kWh          | 106.8     | MBtu        | 126.3  | MBtu   | 12.5%                   |
| 5            | IL Chicago | with exterior low-e panel                      | Furnace / AC | 777     | kWh          | 102.2     | MBtu        | 120.5  | MBtu   | 16.5%                   |
| 5            | IL Chicago | with interior low-e panel                      | Furnace / AC | 807     | kWh          | 100       | MBtu        | 118.5  | MBtu   | 17.9%                   |
| 5            | IL Chicago | with exterior clear panel, worst case mounting | Furnace / AC | 827     | kWh          | 113.9     | MBtu        | 133.9  | MBtu   | 7.3%                    |
| 5            | IL Chicago | with exterior low-e panel, worst case mounting | Furnace / AC | 751     | kWh          | 110       | MBtu        | 128.7  | MBtu   | 10.8%                   |

| Climate<br>Zone | Location   | Window   | Cooling Cost (\$) | Heating Cost (\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|------------|--|-------------------|-------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 5               | ID Boise   | Wood frame, single pane                        | 100.28            | 903.18            | 1003.46         |                     |                       |                   |                      |
| 5               | ID Boise   | with exterior clear panel                      | 88.49             | 714.47            | 802.96          | \$200.50            | 20.0%                 | 11.3              |                      |
| 5               | ID Boise   | with interior clear panel                      | 88.57             | 703.91            | 792.48          | \$210.98            | 21.0%                 | 10.7              |                      |
| 5               | ID Boise   | with exterior low-e panel                      | 80.33             | 674.6             | 754.93          | \$248.53            | 24.8%                 | 10.1              | 5.3                  |
| 5               | ID Boise   | with interior low-e panel                      | 85.51             | 648.09            | 733.6           | \$269.86            | 26.9%                 | 9.3               | 4.3                  |
| 5               | ID Boise   | Wood frame, double pane                        | 93.59             | 755.8             | 849.39          |                     |                       |                   |                      |
| 5               | ID Boise   | with exterior clear panel                      | 85.26             | 706.42            | 791.68          | \$57.71             | 6.8%                  | 39.1              |                      |
| 5               | ID Boise   | with interior clear panel                      | 87.21             | 693.32            | 780.53          | \$68.86             | 8.1%                  | 32.8              |                      |
| 5               | ID Boise   | with exterior low-e panel                      | 76.93             | 673.82            | 750.75          | \$98.64             | 11.6%                 | 25.5              | 6.2                  |
| 5               | ID Boise   | with interior low-e panel                      | 83.05             | 651.87            | 734.92          | \$114.47            | 13.5%                 | 21.9              | 5.6                  |
| 5               | ID Boise   | Metal frame, double pane                       | 91.38             | 835.15            | 926.53          |                     |                       |                   |                      |
| 5               | ID Boise   | with exterior clear panel                      | 88.32             | 736.26            | 824.58          | \$101.95            | 11.0%                 | 22.1              |                      |
| 5               | ID Boise   | with interior clear panel                      | 86.79             | 723.68            | 810.47          | \$116.06            | 12.5%                 | 19.4              |                      |
| 5               | ID Boise   | with exterior low-e panel                      | 79.65             | 690.69            | 770.34          | \$156.19            | 16.9%                 | 16.1              | 4.7                  |
| 5               | ID Boise   | with interior low-e panel                      | 82.28             | 673.84            | 756.12          | \$170.41            | 18.4%                 | 14.7              | 4.7                  |
| 5               | ID Boise   | with exterior clear panel, worst case mounting | 86.45             | 774.77            | 861.22          | \$65.31             | 7.0%                  | 34.6              |                      |
| 5               | ID Boise   | with exterior low-e panel, worst case mounting | 78.12             | 748.58            | 826.7           | \$99.83             | 10.8%                 | 25.2              |                      |
| 5               | IL Chicago | Wood frame, single pane                        | 111.31            | 1082.3            | 1193.61         |                     |                       |                   |                      |
| 5               | IL Chicago | with exterior clear panel                      | 98.27             | 851.25            | 949.52          | \$244.09            | 20.4%                 | 9.2               |                      |
| 5               | IL Chicago | with interior clear panel                      | 98.5              | 838.38            | 936.88          | \$256.73            | 21.5%                 | 8.8               |                      |
| 5               | IL Chicago | with exterior low-e panel                      | 89.72             | 805.39            | 895.11          | \$298.50            | 25.0%                 | 8.4               | 4.7                  |
| 5               | IL Chicago | with interior low-e panel                      | 96.56             | 777.57            | 874.13          | \$319.48            | 26.8%                 | 7.9               | 4.1                  |
| 5               | IL Chicago | Wood frame, double pane                        | 103.97            | 902.57            | 1006.54         |                     |                       |                   |                      |
| 5               | IL Chicago | with exterior clear panel                      | 94.73             | 840.44            | 935.17          | \$71.37             | 7.1%                  | 31.6              |                      |
| 5               | IL Chicago | with interior clear panel                      | 97.01             | 825.72            | 922.73          | \$83.81             | 8.3%                  | 26.9              |                      |
| 5               | IL Chicago | with exterior low-e panel                      | 85.5              | 802.91            | 888.41          | \$118.13            | 11.7%                 | 21.3              | 5.5                  |
| 5               | IL Chicago | with interior low-e panel                      | 93.48             | 780.46            | 873.94          | \$132.60            | 13.2%                 | 18.9              | 5.2                  |
| 5               | IL Chicago | Metal frame, double pane                       | 99.75             | 988.59            | 1088.34         |                     |                       |                   |                      |
| 5               | IL Chicago | with exterior clear panel                      | 97.13             | 873.8             | 970.93          | \$117.41            | 10.8%                 | 19.2              |                      |
| 5               | IL Chicago | with interior clear panel                      | 95.99             | 858.36            | 954.35          | \$133.99            | 12.3%                 | 16.8              |                      |
| 5               | IL Chicago | with exterior low-e panel                      | 88.58             | 822.04            | 910.62          | \$177.72            | 16.3%                 | 14.1              | 4.2                  |
| 5               | IL Chicago | with interior low-e panel                      | 92                | 803.88            | 895.88          | \$192.46            | 17.7%                 | 13.1              | 4.4                  |
| 5               | IL Chicago | with exterior clear panel, worst case mounting | 94.28             | 915.47            | 1009.75         | \$78.59             | 7.2%                  | 28.7              |                      |
| 5               | IL Chicago | with exterior low-e panel, worst case mounting | 85.61             | 884.43            | 970.04          | \$118.30            | 10.9%                 | 21.2              |                      |

| Climate Zone | Location     | Window   | HVAC         | Whole H | louse Cooling | Whole Hou | use Heating | Source | Energy | % source energy savings |
|--------------|--------------|--|--------------|---------|---------------|-----------|-------------|--------|--------|-------------------------|
| 5            | MA Boston    | Wood frame, single pane                        | Furnace / AC | 613     | kWh           | 119.5     | MBtu        | 137.5  | MBtu   |                         |
| 5            | MA Boston    | with exterior clear panel                      | Furnace / AC | 546     | kWh           | 91.3      | MBtu        | 106.0  | MBtu   | 23.0%                   |
| 5            | MA Boston    | with interior clear panel                      | Furnace / AC | 547     | kWh           | 89.7      | MBtu        | 104.2  | MBtu   | 24.2%                   |
| 5            | MA Boston    | with exterior low-e panel                      | Furnace / AC | 493     | kWh           | 86.1      | MBtu        | 99.7   | MBtu   | 27.5%                   |
| 5            | MA Boston    | with interior low-e panel                      | Furnace / AC | 539     | kWh           | 82.5      | MBtu        | 96.3   | MBtu   | 30.0%                   |
| 5            | MA Boston    | Wood frame, double pane                        | Furnace / AC | 580     | kWh           | 97.4      | MBtu        | 113.0  | MBtu   |                         |
| 5            | MA Boston    | with exterior clear panel                      | Furnace / AC | 522     | kWh           | 90.1      | MBtu        | 104.4  | MBtu   | 7.6%                    |
| 5            | MA Boston    | with interior clear panel                      | Furnace / AC | 539     | kWh           | 88.2      | MBtu        | 102.5  | MBtu   | 9.3%                    |
| 5            | MA Boston    | with exterior low-e panel                      | Furnace / AC | 467     | kWh           | 85.9      | MBtu        | 99.2   | MBtu   | 12.3%                   |
| 5            | MA Boston    | with interior low-e panel                      | Furnace / AC | 521     | kWh           | 82.9      | MBtu        | 96.5   | MBtu   | 14.6%                   |
| 5            | MA Boston    | Metal frame, double pane                       | Furnace / AC | 550     | kWh           | 107.9     | MBtu        | 124.1  | MBtu   |                         |
| 5            | MA Boston    | with exterior clear panel                      | Furnace / AC | 537     | kWh           | 94        | MBtu        | 108.8  | MBtu   | 12.3%                   |
| 5            | MA Boston    | with interior clear panel                      | Furnace / AC | 527     | kWh           | 92.1      | MBtu        | 106.6  | MBtu   | 14.1%                   |
| 5            | MA Boston    | with exterior low-e panel                      | Furnace / AC | 483     | kWh           | 88.1      | MBtu        | 101.8  | MBtu   | 18.0%                   |
| 5            | MA Boston    | with interior low-e panel                      | Furnace / AC | 506     | kWh           | 85.7      | MBtu        | 99.4   | MBtu   | 19.9%                   |
| 5            | MA Boston    | with exterior clear panel, worst case mounting | Furnace / AC | 520     | kWh           | 99.1      | MBtu        | 114.2  | MBtu   | 8.0%                    |
| 5            | MA Boston    | with exterior low-e panel, worst case mounting | Furnace / AC | 468     | kWh           | 95.6      | MBtu        | 109.8  | MBtu   | 11.6%                   |
| 5            | NY Rochester | Wood frame, single pane                        | Furnace / AC | 852     | kWh           | 147.3     | MBtu        | 170.6  | MBtu   |                         |
| 5            | NY Rochester | with exterior clear panel                      | Furnace / AC | 753     | kWh           | 117.4     | MBtu        | 136.8  | MBtu   | 19.8%                   |
| 5            | NY Rochester | with interior clear panel                      | Furnace / AC | 754     | kWh           | 115.8     | MBtu        | 135.1  | MBtu   | 20.8%                   |
| 5            | NY Rochester | with exterior low-e panel                      | Furnace / AC | 683     | kWh           | 111.4     | MBtu        | 129.5  | MBtu   | 24.1%                   |
| 5            | NY Rochester | with interior low-e panel                      | Furnace / AC | 737     | kWh           | 107.9     | MBtu        | 126.3  | MBtu   | 26.0%                   |
| 5            | NY Rochester | Wood frame, double pane                        | Furnace / AC | 800     | kWh           | 124.1     | MBtu        | 144.7  | MBtu   |                         |
| 5            | NY Rochester | with exterior clear panel                      | Furnace / AC | 721     | kWh           | 116       | MBtu        | 135.0  | MBtu   | 6.7%                    |
| 5            | NY Rochester | with interior clear panel                      | Furnace / AC | 742     | kWh           | 114.2     | MBtu        | 133.2  | MBtu   | 7.9%                    |
| 5            | NY Rochester | with exterior low-e panel                      | Furnace / AC | 655     | kWh           | 111.1     | MBtu        | 128.8  | MBtu   | 11.0%                   |
| 5            | NY Rochester | with interior low-e panel                      | Furnace / AC | 715     | kWh           | 108.3     | MBtu        | 126.5  | MBtu   | 12.6%                   |
| 5            | NY Rochester | Metal frame, double pane                       | Furnace / AC | 762     | kWh           | 135       | MBtu        | 156.2  | MBtu   |                         |
| 5            | NY Rochester | with exterior clear panel                      | Furnace / AC | 744     | kWh           | 120.4     | MBtu        | 140.0  | MBtu   | 10.3%                   |
| 5            | NY Rochester | with interior clear panel                      | Furnace / AC | 731     | kWh           | 118.3     | MBtu        | 137.6  | MBtu   | 11.9%                   |
| 5            | NY Rochester | with exterior low-e panel                      | Furnace / AC | 675     | kWh           | 113.6     | MBtu        | 131.8  | MBtu   | 15.6%                   |
| 5            | NY Rochester | with interior low-e panel                      | Furnace / AC | 701     | kWh           | 111.3     | MBtu        | 129.6  | MBtu   | 17.0%                   |
| 5            | NY Rochester | with exterior clear panel, worst case mounting | Furnace / AC | 720     | kWh           | 125.6     | MBtu        | 145.4  | MBtu   | 6.9%                    |
| 5            | NY Rochester | with exterior low-e panel, worst case mounting | Furnace / AC | 650     | kWh           | 121.4     | MBtu        | 140.0  | MBtu   | 10.3%                   |

| Climate<br>Zone | Location     | Window   | Cooling Cost (\$) | Heating Cost<br>(\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|--------------|--|-------------------|----------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 5               | MA Boston    | Wood frame, single pane                        | 91.34             | 1613.91              | 1705.25         |                     |                       |                   |                      |
| 5               | MA Boston    | with exterior clear panel                      | 81.35             | 1231.92              | 1313.27         | \$391.98            | 23.0%                 | 5.8               |                      |
| 5               | MA Boston    | with interior clear panel                      | 81.5              | 1210.5               | 1292            | \$413.25            | 24.2%                 | 5.5               |                      |
| 5               | MA Boston    | with exterior low-e panel                      | 73.46             | 1161.97              | 1235.43         | \$469.82            | 27.6%                 | 5.3               | 3.3                  |
| 5               | MA Boston    | with interior low-e panel                      | 80.31             | 1114.37              | 1194.68         | \$510.57            | 29.9%                 | 4.9               | 2.6                  |
| 5               | MA Boston    | Wood frame, double pane                        | 86.42             | 1314.81              | 1401.23         |                     |                       |                   |                      |
| 5               | MA Boston    | with exterior clear panel                      | 77.78             | 1216.71              | 1294.49         | \$106.74            | 7.6%                  | 21.1              |                      |
| 5               | MA Boston    | with interior clear panel                      | 80.31             | 1191                 | 1271.31         | \$129.92            | 9.3%                  | 17.4              |                      |
| 5               | MA Boston    | with exterior low-e panel                      | 69.58             | 1159.33              | 1228.91         | \$172.32            | 12.3%                 | 14.6              | 3.9                  |
| 5               | MA Boston    | with interior low-e panel                      | 77.63             | 1119.61              | 1197.24         | \$203.99            | 14.6%                 | 12.3              | 3.4                  |
| 5               | MA Boston    | Metal frame, double pane                       | 81.95             | 1456.47              | 1538.42         |                     |                       |                   |                      |
| 5               | MA Boston    | with exterior clear panel                      | 80.01             | 1269.14              | 1349.15         | \$189.27            | 12.3%                 | 11.9              |                      |
| 5               | MA Boston    | with interior clear panel                      | 78.52             | 1243.8               | 1322.32         | \$216.10            | 14.0%                 | 10.4              |                      |
| 5               | MA Boston    | with exterior low-e panel                      | 71.97             | 1189.17              | 1261.14         | \$277.28            | 18.0%                 | 9.1               | 2.9                  |
| 5               | MA Boston    | with interior low-e panel                      | 75.39             | 1157.56              | 1232.95         | \$305.47            | 19.9%                 | 8.2               | 2.9                  |
| 5               | MA Boston    | with exterior clear panel, worst case mounting | 77.48             | 1337.49              | 1414.97         | \$123.45            | 8.0%                  | 18.3              |                      |
| 5               | MA Boston    | with exterior low-e panel, worst case mounting | 69.73             | 1290.75              | 1360.48         | \$177.94            | 11.6%                 | 14.1              |                      |
| 5               | NY Rochester | Wood frame, single pane                        | 150.8             | 1973.28              | 2124.08         |                     |                       |                   |                      |
| 5               | NY Rochester | with exterior clear panel                      | 133.28            | 1573.54              | 1706.82         | \$417.26            | 19.6%                 | 5.4               |                      |
| 5               | NY Rochester | with interior clear panel                      | 133.46            | 1551.69              | 1685.15         | \$438.93            | 20.7%                 | 5.1               |                      |
| 5               | NY Rochester | with exterior low-e panel                      | 120.89            | 1492.92              | 1613.81         | \$510.27            | 24.0%                 | 4.9               | 2.7                  |
| 5               | NY Rochester | with interior low-e panel                      | 130.45            | 1446.36              | 1576.81         | \$547.27            | 25.8%                 | 4.6               | 2.4                  |
| 5               | NY Rochester | Wood frame, double pane                        | 141.6             | 1663.58              | 1805.18         |                     |                       |                   |                      |
| 5               | NY Rochester | with exterior clear panel                      | 127.62            | 1554.69              | 1682.31         | \$122.87            | 6.8%                  | 18.4              |                      |
| 5               | NY Rochester | with interior clear panel                      | 131.33            | 1530.29              | 1661.62         | \$143.56            | 8.0%                  | 15.7              |                      |
| 5               | NY Rochester | with exterior low-e panel                      | 115.94            | 1488.24              | 1604.18         | \$201.00            | 11.1%                 | 12.5              | 3.3                  |
| 5               | NY Rochester | with interior low-e panel                      | 126.56            | 1451.41              | 1577.97         | \$227.21            | 12.6%                 | 11.1              | 3.0                  |
| 5               | NY Rochester | Metal frame, double pane                       | 134.87            | 1808.84              | 1943.71         |                     |                       |                   |                      |
| 5               | NY Rochester | with exterior clear panel                      | 131.69            | 1612.78              | 1744.47         | \$199.24            | 10.3%                 | 11.3              |                      |
| 5               | NY Rochester | with interior clear panel                      | 129.39            | 1585.84              | 1715.23         | \$228.48            | 11.8%                 | 9.9               |                      |
| 5               | NY Rochester | with exterior low-e panel                      | 119.48            | 1521.97              | 1641.45         | \$302.26            | 15.6%                 | 8.3               | 2.5                  |
| 5               | NY Rochester | with interior low-e panel                      | 124.08            | 1491.27              | 1615.35         | \$328.36            | 16.9%                 | 7.6               | 2.6                  |
| 5               | NY Rochester | with exterior clear panel, worst case mounting | 127.44            | 1682.64              | 1810.08         | \$133.63            | 6.9%                  | 16.9              |                      |
| 5               | NY Rochester | with exterior low-e panel, worst case mounting | 115.05            | 1627.26              | 1742.31         | \$201.40            | 10.4%                 | 12.5              |                      |

| Climate Zone | Location         | Window   | HVAC         | Whole H | ouse Cooling | Whole Hou | ise Heating | Source | Energy | % source energy savings |
|--------------|------------------|--|--------------|---------|--------------|-----------|-------------|--------|--------|-------------------------|
| 5            | PA Pittsburgh    | Wood frame, single pane                        | Furnace / AC | 916     | kWh          | 122.6     | MBtu        | 144.4  | MBtu   |                         |
| 5            | PA Pittsburgh    | with exterior clear panel                      | Furnace / AC | 818     | kWh          | 97.6      | MBtu        | 116.0  | MBtu   | 19.7%                   |
| 5            | PA Pittsburgh    | with interior clear panel                      | Furnace / AC | 818     | kWh          | 96.2      | MBtu        | 114.4  | MBtu   | 20.7%                   |
| 5            | PA Pittsburgh    | with exterior low-e panel                      | Furnace / AC | 745     | kWh          | 92.4      | MBtu        | 109.5  | MBtu   | 24.2%                   |
| 5            | PA Pittsburgh    | with interior low-e panel                      | Furnace / AC | 801     | kWh          | 89.2      | MBtu        | 106.6  | MBtu   | 26.2%                   |
| 5            | PA Pittsburgh    | Wood frame, double pane                        | Furnace / AC | 863     | kWh          | 103.2     | MBtu        | 122.6  | MBtu   |                         |
| 5            | PA Pittsburgh    | with exterior clear panel                      | Furnace / AC | 784     | kWh          | 96.4      | MBtu        | 114.3  | MBtu   | 6.8%                    |
| 5            | PA Pittsburgh    | with interior clear panel                      | Furnace / AC | 806     | kWh          | 94.8      | MBtu        | 112.8  | MBtu   | 8.0%                    |
| 5            | PA Pittsburgh    | with exterior low-e panel                      | Furnace / AC | 715     | kWh          | 92.1      | MBtu        | 108.8  | MBtu   | 11.3%                   |
| 5            | PA Pittsburgh    | with interior low-e panel                      | Furnace / AC | 775     | kWh          | 89.6      | MBtu        | 106.7  | MBtu   | 12.9%                   |
| 5            | PA Pittsburgh    | Metal frame, double pane                       | Furnace / AC | 825     | kWh          | 112.9     | MBtu        | 132.8  | MBtu   |                         |
| 5            | PA Pittsburgh    | with exterior clear panel                      | Furnace / AC | 809     | kWh          | 100.2     | MBtu        | 118.7  | MBtu   | 10.6%                   |
| 5            | PA Pittsburgh    | with interior clear panel                      | Furnace / AC | 794     | kWh          | 98.5      | MBtu        | 116.7  | MBtu   | 12.1%                   |
| 5            | PA Pittsburgh    | with exterior low-e panel                      | Furnace / AC | 736     | kWh          | 94.3      | MBtu        | 111.4  | MBtu   | 16.1%                   |
| 5            | PA Pittsburgh    | with interior low-e panel                      | Furnace / AC | 763     | kWh          | 92.3      | MBtu        | 109.6  | MBtu   | 17.5%                   |
| 5            | PA Pittsburgh    | with exterior clear panel, worst case mounting | Furnace / AC | 779     | kWh          | 104.9     | MBtu        | 123.5  | MBtu   | 7.0%                    |
| 5            | PA Pittsburgh    | with exterior low-e panel, worst case mounting | Furnace / AC | 710     | kWh          | 101.4     | MBtu        | 118.9  | MBtu   | 10.5%                   |
| 4            | NY New York City | Wood frame, single pane                        | Furnace / AC | 1185    | kWh          | 109.7     | MBtu        | 133.4  | MBtu   |                         |
| 4            | NY New York City | with exterior clear panel                      | Furnace / AC | 1073    | kWh          | 85.5      | MBtu        | 105.7  | MBtu   | 20.8%                   |
| 4            | NY New York City | with interior clear panel                      | Furnace / AC | 1073    | kWh          | 84.1      | MBtu        | 104.2  | MBtu   | 21.9%                   |
| 4            | NY New York City | with exterior low-e panel                      | Furnace / AC | 996     | kWh          | 81        | MBtu        | 99.9   | MBtu   | 25.1%                   |
| 4            | NY New York City | with interior low-e panel                      | Furnace / AC | 1052    | kWh          | 77.9      | MBtu        | 97.1   | MBtu   | 27.2%                   |
| 4            | NY New York City | Wood frame, double pane                        | Furnace / AC | 1128    | kWh          | 90.8      | MBtu        | 112.1  | MBtu   |                         |
| 4            | NY New York City | with exterior clear panel                      | Furnace / AC | 1041    | kWh          | 84.6      | MBtu        | 104.3  | MBtu   | 6.9%                    |
| 4            | NY New York City | with interior clear panel                      | Furnace / AC | 1064    | kWh          | 82.9      | MBtu        | 102.7  | MBtu   | 8.4%                    |
| 4            | NY New York City | with exterior low-e panel                      | Furnace / AC | 964     | kWh          | 80.9      | MBtu        | 99.4   | MBtu   | 11.3%                   |
| 4            | NY New York City | with interior low-e panel                      | Furnace / AC | 1028    | kWh          | 78.3      | MBtu        | 97.3   | MBtu   | 13.2%                   |
| 4            | NY New York City | Metal frame, double pane                       | Furnace / AC | 1089    | kWh          | 100       | MBtu        | 121.7  | MBtu   |                         |
| 4            | NY New York City | with exterior clear panel                      | Furnace / AC | 1065    | kWh          | 88        | MBtu        | 108.3  | MBtu   | 11.0%                   |
| 4            | NY New York City | 1  | Furnace / AC | 1050    | kWh          | 86.4      | MBtu        | 106.4  | MBtu   | 12.6%                   |
| 4            | NY New York City | with exterior low-e panel                      | Furnace / AC | 989     | kWh          | 82.8      | MBtu        | 101.8  | MBtu   | 16.4%                   |
| 4            | NY New York City | with interior low-e panel                      | Furnace / AC | 1016    | kWh          | 80.8      | MBtu        | 99.9   | MBtu   | 17.9%                   |
| 4            | NY New York City | with exterior clear panel, worst case mounting | Furnace / AC | 1039    | kWh          | 92.4      | MBtu        | 112.8  | MBtu   | 7.3%                    |
| 4            | NY New York City | with exterior low-e panel, worst case mounting | Furnace / AC | 964     | kWh          | 89.4      | MBtu        | 108.7  | MBtu   | 10.7%                   |

| Climate<br>Zone | Location                           | Window   | Cooling Cost (\$) | Heating Cost<br>(\$) | Total Cost<br>(\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|------------------------------------|--|-------------------|----------------------|--------------------|---------------------|-----------------------|-------------------|----------------------|
| 5               | PA Pittsburgh                      | Wood frame, single pane                        | 117.25            | 1434.05              | 1551.3             |                     |                       |                   |                      |
| 5               | PA Pittsburgh                      | with exterior clear panel                      | 104.7             | 1141.74              | 1246.44            | \$304.86            | 19.7%                 | 7.4               |                      |
| 5               | PA Pittsburgh                      | with interior clear panel                      | 104.7             | 1125.45              | 1230.15            | \$321.15            | 20.7%                 | 7.0               |                      |
| 5               | PA Pittsburgh                      | with exterior low-e panel                      | 95.36             | 1080.64              | 1176               | \$375.30            | 24.2%                 | 6.7               | 3.6                  |
| 5               | PA Pittsburgh                      | with interior low-e panel                      | 102.53            | 1044.13              | 1146.66            | \$404.64            | 26.1%                 | 6.2               | 3.1                  |
| 5               | PA Pittsburgh                      | Wood frame, double pane                        | 110.46            | 1207.22              | 1317.68            |                     |                       |                   |                      |
| 5               | PA Pittsburgh                      | with exterior clear panel                      | 100.35            | 1128.21              | 1228.56            | \$89.12             | 6.8%                  | 25.3              |                      |
| 5               | PA Pittsburgh                      | with interior clear panel                      | 103.17            | 1109.55              | 1212.72            | \$104.96            | 8.0%                  | 21.5              |                      |
| 5               | PA Pittsburgh                      | with exterior low-e panel                      | 91.52             | 1077.82              | 1169.34            | \$148.34            | 11.3%                 | 16.9              | 4.3                  |
| 5               | PA Pittsburgh                      | with interior low-e panel                      | 99.2              | 1048.37              | 1147.57            | \$170.11            | 12.9%                 | 14.8              | 3.9                  |
| 5               | PA Pittsburgh                      | Metal frame, double pane                       | 105.6             | 1320.46              | 1426.06            |                     |                       |                   |                      |
| 5               | PA Pittsburgh                      | with exterior clear panel                      | 103.55            | 1172.48              | 1276.03            | \$150.03            | 10.5%                 | 15.0              |                      |
| 5               | PA Pittsburgh                      | with interior clear panel                      | 101.63            | 1152.8               | 1254.43            | \$171.63            | 12.0%                 | 13.1              |                      |
| 5               | PA Pittsburgh                      | with exterior low-e panel                      | 94.21             | 1103.29              | 1197.5             | \$228.56            | 16.0%                 | 11.0              | 3.2                  |
| 5               | PA Pittsburgh                      | with interior low-e panel                      | 97.66             | 1079.7               | 1177.36            | \$248.70            | 17.4%                 | 10.1              | 3.3                  |
| 5               | PA Pittsburgh                      | with exterior clear panel, worst case mounting | 99.71             | 1227.45              | 1327.16            | \$98.90             | 6.9%                  | 22.8              |                      |
| 5               | PA Pittsburgh                      | with exterior low-e panel, worst case mounting | 90.88             | 1185.82              | 1276.7             | \$149.36            | 10.5%                 | 16.8              |                      |
| 4               | NY New York<br>City                | Wood frame, single pane                        | 209.75            | 1470.07              | 1679.82            |                     |                       |                   |                      |
| 4               | NY New York<br>City<br>NY New York | with exterior clear panel                      | 189.92            | 1145.2               | 1335.12            | \$344.70            | 20.5%                 | 6.5               |                      |
| 4               | City<br>NY New York                | with interior clear panel                      | 189.92            | 1127.07              | 1316.99            | \$362.83            | 21.6%                 | 6.2               |                      |
| 4               | City<br>NY New York                | with exterior low-e panel                      | 176.29            | 1085.32              | 1261.61            | \$418.21            | 24.9%                 | 6.0               | 3.5                  |
| 4               | City                               | with interior low-e panel                      | 186.2             | 1043.48              | 1229.68            | \$450.14            | 26.8%                 | 5.6               | 2.9                  |
| 4               | NY New York<br>City                | Wood frame, double pane                        | 199.66            | 1216.09              | 1415.75            |                     |                       |                   |                      |
| 4               | NY New York<br>City<br>NY New York | with exterior clear panel                      | 184.26            | 1133.37              | 1317.63            | \$98.12             | 6.9%                  | 23.0              |                      |
| 4               | City<br>NY New York                | with interior clear panel                      | 188.33            | 1111.52              | 1299.85            | \$115.90            | 8.2%                  | 19.5              |                      |
| 4               | City<br>NY New York                | with exterior low-e panel                      | 170.63            | 1084.27              | 1254.9             | \$160.85            | 11.4%                 | 15.6              | 4.1                  |
| 4               | City                               | with interior low-e panel                      | 181.96            | 1049.19              | 1231.15            | \$184.60            | 13.0%                 | 13.6              | 3.7                  |
| 4               | NY New York<br>City<br>NY New York | Metal frame, double pane                       | 192.75            | 1339.49              | 1532.24            |                     |                       |                   |                      |
| 4               | City<br>NY New York                | with exterior clear panel                      | 188.51            | 1179.09              | 1367.6             | \$164.64            | 10.7%                 | 13.7              |                      |
| 4               | City<br>NY New York                | with interior clear panel                      | 185.85            | 1157.48              | 1343.33            | \$188.91            | 12.3%                 | 11.9              |                      |
| 4               | City                               | with exterior low-e panel                      | 175.05            | 1110.08              | 1285.13            | \$247.11            | 16.1%                 | 10.2              | 3.1                  |

| 4 | NY New York<br>City<br>NY New York | with interior low-e panel                      | 179.83 | 1082.41 | 1262.24 | \$270.00 | 17.6% | 9.3  | 3.1 |
|---|------------------------------------|--|--------|---------|---------|----------|-------|------|-----|
| 4 | City<br>NY New York                | with exterior clear panel, worst case mounting | 183.9  | 1238.56 | 1422.46 | \$109.78 | 7.2%  | 20.6 |     |
| 4 | City                               | with exterior low-e panel, worst case mounting | 170.63 | 1198.31 | 1368.94 | \$163.30 | 10.7% | 15.4 |     |

| Climate Zone | Location      | Window   | HVAC         | Whole Ho | ouse Cooling | Whole Ho | use Heating | Source | Energy | % source energy savings |
|--------------|---------------|--|--------------|----------|--------------|----------|-------------|--------|--------|-------------------------|
| 4            | WA Seattle    | Wood frame, single pane                        | Furnace / AC | 184      | kWh          | 85.9     | MBtu        | 95.9   | MBtu   |                         |
| 4            | WA Seattle    | with exterior clear panel                      | Furnace / AC | 160      | kWh          | 65.4     | MBtu        | 73.3   | MBtu   | 23.6%                   |
| 4            | WA Seattle    | with interior clear panel                      | Furnace / AC | 162      | kWh          | 64.3     | MBtu        | 72.1   | MBtu   | 24.9%                   |
| 4            | WA Seattle    | with exterior low-e panel                      | Furnace / AC | 141      | kWh          | 60.9     | MBtu        | 68.1   | MBtu   | 29.0%                   |
| 4            | WA Seattle    | with interior low-e panel                      | Furnace / AC | 161      | kWh          | 58.2     | MBtu        | 65.4   | MBtu   | 31.8%                   |
| 4            | WA Seattle    | Wood frame, double pane                        | Furnace / AC | 173      | kWh          | 70       | MBtu        | 78.4   | MBtu   |                         |
| 4            | WA Seattle    | with exterior clear panel                      | Furnace / AC | 150      | kWh          | 64.6     | MBtu        | 72.3   | MBtu   | 7.9%                    |
| 4            | WA Seattle    | with interior clear panel                      | Furnace / AC | 159      | kWh          | 63.3     | MBtu        | 70.9   | MBtu   | 9.5%                    |
| 4            | WA Seattle    | with exterior low-e panel                      | Furnace / AC | 130      | kWh          | 60.7     | MBtu        | 67.8   | MBtu   | 13.6%                   |
| 4            | WA Seattle    | with interior low-e panel                      | Furnace / AC | 152      | kWh          | 58.6     | MBtu        | 65.7   | MBtu   | 16.2%                   |
| 4            | WA Seattle    | Metal frame, double pane                       | Furnace / AC | 158      | kWh          | 78.4     | MBtu        | 87.4   | MBtu   |                         |
| 4            | WA Seattle    | with exterior clear panel                      | Furnace / AC | 158      | kWh          | 67.9     | MBtu        | 76.0   | MBtu   | 13.1%                   |
| 4            | WA Seattle    | with interior clear panel                      | Furnace / AC | 155      | kWh          | 66.5     | MBtu        | 74.4   | MBtu   | 14.9%                   |
| 4            | WA Seattle    | with exterior low-e panel                      | Furnace / AC | 137      | kWh          | 62.6     | MBtu        | 69.9   | MBtu   | 20.0%                   |
| 4            | WA Seattle    | with interior low-e panel                      | Furnace / AC | 147      | kWh          | 60.9     | MBtu        | 68.2   | MBtu   | 22.0%                   |
| 4            | WA Seattle    | with exterior clear panel, worst case mounting | Furnace / AC | 148      | kWh          | 71.9     | MBtu        | 80.2   | MBtu   | 8.3%                    |
| 4            | WA Seattle    | with exterior low-e panel, worst case mounting | Furnace / AC | 124      | kWh          | 68.7     | MBtu        | 76.4   | MBtu   | 12.6%                   |
| 4            | DC Washington | Wood frame, single pane                        | Furnace / AC | 1593     | kWh          | 100.4    | MBtu        | 127.9  | MBtu   |                         |
| 4            | DC Washington | with exterior clear panel                      | Furnace / AC | 1420     | kWh          | 79.6     | MBtu        | 103.2  | MBtu   | 19.3%                   |
| 4            | DC Washington | with interior clear panel                      | Furnace / AC | 1419     | kWh          | 78.4     | MBtu        | 101.9  | MBtu   | 20.3%                   |
| 4            | DC Washington | with exterior low-e panel                      | Furnace / AC | 1316     | kWh          | 75.5     | MBtu        | 97.6   | MBtu   | 23.7%                   |
| 4            | DC Washington | with interior low-e panel                      | Furnace / AC | 1381     | kWh          | 72.5     | MBtu        | 95.0   | MBtu   | 25.7%                   |
| 4            | DC Washington | with exterior solar-E panel                    | Furnace / AC | 1119     | kWh          | 79.1     | MBtu        | 99.2   | MBtu   | 22.4%                   |
| 4            | DC Washington | Wood frame, double pane                        | Furnace / AC | 1494     | kWh          | 84.2     | MBtu        | 109.1  | MBtu   |                         |
| 4            | DC Washington | with exterior clear panel                      | Furnace / AC | 1376     | kWh          | 78.8     | MBtu        | 101.8  | MBtu   | 6.6%                    |
| 4            | DC Washington | with interior clear panel                      | Furnace / AC | 1401     | kWh          | 77.4     | MBtu        | 100.6  | MBtu   | 7.8%                    |
| 4            | DC Washington | with exterior low-e panel                      | Furnace / AC | 1277     | kWh          | 75.4     | MBtu        | 97.0   | MBtu   | 11.1%                   |
| 4            | DC Washington | with interior low-e panel                      | Furnace / AC | 1351     | kWh          | 73       | MBtu        | 95.2   | MBtu   | 12.7%                   |
| 4            | DC Washington | with exterior solar-E panel                    | Furnace / AC | 1091     | kWh          | 78.9     | MBtu        | 98.7   | MBtu   | 9.5%                    |
| 4            |               | Metal frame, double pane                       | Furnace / AC | 1452     | kWh          | 92.7     | MBtu        | 117.9  | MBtu   |                         |
| 4            | DC Washington | with exterior clear panel                      | Furnace / AC | 1411     | kWh          | 82       | MBtu        | 105.7  | MBtu   | 10.3%                   |
| 4            | DC Washington | with interior clear panel                      | Furnace / AC | 1390     | kWh          | 80.6     | MBtu        | 104.0  | MBtu   | 11.8%                   |
| 4            | DC Washington | with exterior low-e panel                      | Furnace / AC | 1309     | kWh          | 77.2     | MBtu        | 99.3   | MBtu   | 15.7%                   |
| 4            | DC Washington | with interior low-e panel                      | Furnace / AC | 1341     | kWh          | 75.3     | MBtu        | 97.6   | MBtu   | 17.2%                   |
| 4            | DC Washington | with exterior solar-E panel                    | Furnace / AC | 1116     | kWh          | 80.8     | MBtu        | 101.0  | MBtu   | 14.3%                   |
| 4            | DC Washington | with exterior clear panel, worst case mounting | Furnace / AC | 1383     | kWh          | 86.1     | MBtu        | 109.9  | MBtu   | 6.8%                    |
| 4            | DC Washington | with exterior low-e panel, worst case mounting | Furnace / AC | 1284     | kWh          | 83.4     | MBtu        | 105.8  | MBtu   | 10.2%                   |
| 4            | DC Washington | with exterior solar-E panel, worst case mount  | Furnace / AC | 1121     | kWh          | 86.4     | MBtu        | 107.2  | MBtu   | 9.1%                    |

| Climate Zone | Location       | Window  | HVAC         | Whole H | ouse Cooling | Whole Ho | use Heating | Source | Energy | % source energy savings |
|--------------|----------------|---|--------------|---------|--------------|----------|-------------|--------|--------|-------------------------|
| 4            | MO Kansas City | Wood frame, single pane                         | Furnace / AC | 2235    | kWh          | 95.7     | MBtu        | 130.2  | MBtu   |                         |
| 4            | MO Kansas City | with exterior clear panel                       | Furnace / AC | 1955    | kWh          | 73       | MBtu        | 102.2  | MBtu   | 21.5%                   |
| 4            | MO Kansas City | with interior clear panel                       | Furnace / AC | 1947    | kWh          | 71.8     | MBtu        | 100.8  | MBtu   | 22.6%                   |
| 4            | MO Kansas City | with exterior low-e panel                       | Furnace / AC | 1815    | kWh          | 68.6     | MBtu        | 95.8   | MBtu   | 26.4%                   |
| 4            | MO Kansas City | with interior low-e panel                       | Furnace / AC | 1895    | kWh          | 65.6     | MBtu        | 93.4   | MBtu   | 28.3%                   |
| 4            | MO Kansas City | with exterior solar-E panel                     | Furnace / AC | 1561    | kWh          | 72.2     | MBtu        | 96.8   | MBtu   | 25.7%                   |
| 4            | MO Kansas City | Wood frame, double pane                         | Furnace / AC | 2061    | kWh          | 78       | MBtu        | 108.8  | MBtu   |                         |
| 4            | MO Kansas City | with exterior clear panel                       | Furnace / AC | 1900    | kWh          | 72.1     | MBtu        | 100.5  | MBtu   | 7.6%                    |
| 4            | MO Kansas City | with interior clear panel                       | Furnace / AC | 1928    | kWh          | 70.5     | MBtu        | 99.1   | MBtu   | 8.9%                    |
| 4            | MO Kansas City | with exterior low-e panel                       | Furnace / AC | 1764    | kWh          | 68.5     | MBtu        | 95.1   | MBtu   | 12.7%                   |
| 4            | MO Kansas City | with interior low-e panel                       | Furnace / AC | 1858    | kWh          | 66       | MBtu        | 93.4   | MBtu   | 14.2%                   |
| 4            | MO Kansas City | with exterior solar-E panel                     | Furnace / AC | 1525    | kWh          | 71.9     | MBtu        | 96.0   | MBtu   | 11.8%                   |
| 4            | MO Kansas City | Metal frame, double pane                        | Furnace / AC | 2021    | kWh          | 86.8     | MBtu        | 118.0  | MBtu   |                         |
| 4            | MO Kansas City | with exterior clear panel                       | Furnace / AC | 1950    | kWh          | 75.4     | MBtu        | 104.7  | MBtu   | 11.2%                   |
| 4            | MO Kansas City | with interior clear panel                       | Furnace / AC | 1919    | kWh          | 73.9     | MBtu        | 102.7  | MBtu   | 12.9%                   |
| 4            | MO Kansas City | with exterior low-e panel                       | Furnace / AC | 1807    | kWh          | 70.4     | MBtu        | 97.6   | MBtu   | 17.3%                   |
| 4            | MO Kansas City | with interior low-e panel                       | Furnace / AC | 1843    | kWh          | 68.4     | MBtu        | 95.9   | MBtu   | 18.8%                   |
| 4            | MO Kansas City | with exterior solar-E panel                     | Furnace / AC | 1560    | kWh          | 73.9     | MBtu        | 98.6   | MBtu   | 16.4%                   |
| 4            | MO Kansas City | with exterior clear panel, worst case mounting  | Furnace / AC | 1919    | kWh          | 79.7     | MBtu        | 109.1  | MBtu   | 7.6%                    |
| 4            | MO Kansas City | with exterior low-e panel, worst case mounting  | Furnace / AC | 1780    | kWh          | 76.8     | MBtu        | 104.3  | MBtu   | 11.6%                   |
| 4            | MO Kansas City | with exterior solar-E panel, worst case mountin | Furnace / AC | 1574    | kWh          | 79.8     | MBtu        | 105.2  | MBtu   | 10.8%                   |
| 4            | NC Raleigh     | Wood frame, single pane                         | Furnace / AC | 2682    | kWh          | 88.9     | MBtu        | 127.9  | MBtu   |                         |
| 4            | NC Raleigh     | with exterior clear panel                       | Furnace / AC | 2444    | kWh          | 73.4     | MBtu        | 108.2  | MBtu   | 15.4%                   |
| 4            | NC Raleigh     | with interior clear panel                       | Furnace / AC | 2438    | kWh          | 72.4     | MBtu        | 107.1  | MBtu   | 16.3%                   |
| 4            | NC Raleigh     | with exterior low-e panel                       | Furnace / AC | 2312    | kWh          | 70.3     | MBtu        | 103.3  | MBtu   | 19.2%                   |
| 4            | NC Raleigh     | with interior low-e panel                       | Furnace / AC | 2397    | kWh          | 67.8     | MBtu        | 101.6  | MBtu   | 20.6%                   |
| 4            | NC Raleigh     | with exterior solar-E panel                     | Furnace / AC | 2066    | kWh          | 73.5     | MBtu        | 104.0  | MBtu   | 18.7%                   |
| 4            | NC Raleigh     | Wood frame, double pane                         | Furnace / AC | 2545    | kWh          | 76.8     | MBtu        | 113.1  | MBtu   |                         |
| 4            | NC Raleigh     | with exterior clear panel                       | Furnace / AC | 2390    | kWh          | 72.9     | MBtu        | 107.0  | MBtu   | 5.3%                    |
| 4            | NC Raleigh     | with interior clear panel                       | Furnace / AC | 2420    | kWh          | 71.7     | MBtu        | 106.1  | MBtu   | 6.2%                    |
| 4            | NC Raleigh     | with exterior low-e panel                       | Furnace / AC | 2262    | kWh          | 70.4     | MBtu        | 102.8  | MBtu   | 9.1%                    |
| 4            | NC Raleigh     | with interior low-e panel                       | Furnace / AC | 2360    | kWh          | 68.3     | MBtu        | 101.7  | MBtu   | 10.1%                   |
| 4            | NC Raleigh     | with exterior solar-E panel                     | Furnace / AC | 2031    | kWh          | 73.5     | MBtu        | 103.6  | MBtu   | 8.4%                    |
| 4            | NC Raleigh     | Metal frame, double pane                        | Furnace / AC | 2497    | kWh          | 83.7     | MBtu        | 120.1  | MBtu   |                         |
| 4            | NC Raleigh     | with exterior clear panel                       | Furnace / AC | 2438    | kWh          | 75.4     | MBtu        | 110.3  | MBtu   | 8.1%                    |
| 4            | NC Raleigh     | with interior clear panel                       | Furnace / AC | 2408    | kWh          | 74.4     | MBtu        | 108.9  | MBtu   | 9.3%                    |
| 4            | NC Raleigh     | with exterior low-e panel                       | Furnace / AC | 2303    | kWh          | 71.7     | MBtu        | 104.7  | MBtu   | 12.8%                   |
| 4            | NC Raleigh     | with interior low-e panel                       | Furnace / AC | 2344    | kWh          | 70.2     | MBtu        | 103.6  | MBtu   | 13.7%                   |
| 4            | NC Raleigh     | with exterior solar-E panel                     | Furnace / AC | 2064    | kWh          | 75       | MBtu        | 105.6  | MBtu   | 12.1%                   |
| 4            | NC Raleigh     | with exterior clear panel, worst case mounting  | Furnace / AC | 2402    | kWh          | 78.8     | MBtu        | 113.6  | MBtu   | 5.4%                    |
| 4            | NC Raleigh     | with exterior low-e panel, worst case mounting  | Furnace / AC | 2276    | kWh          | 76.8     | MBtu        | 110.0  | MBtu   | 8.4%                    |
| 4            | NC Raleigh     | with exterior solar-E panel, worst case mountin | Furnace / AC | 2073    | kWh          | 79.5     | MBtu        | 110.6  | MBtu   | 7.9%                    |

| Climate | Location       | Window   | Cooling Cost | <b>Heating Cost</b> | Total Cost | Energy cost | % energy     | Simple  | Payback   |
|---------|----------------|--|--------------|---------------------|------------|-------------|--------------|---------|-----------|
| Zone    |                |  | (\$)         | (\$)                | (\$)       | savings     | cost savings | payback | for low-e |
| 4       | MO Kansas City | Wood frame, single pane                          | 225.74       | 1150.84             | 1376.58    |             |              |         |           |
| 4       | MO Kansas City | with exterior clear panel                        | 197.46       | 878.73              | 1076.19    | \$300.39    | 21.8%        | 7.5     |           |
| 4       | MO Kansas City | with interior clear panel                        | 196.65       | 863.74              | 1060.39    | \$316.19    | 23.0%        | 7.9     |           |
| 4       | MO Kansas City | with exterior low-e panel                        | 183.32       | 825.7               | 1009.02    | \$367.56    | 26.7%        | 6.8     | 3.8       |
| 4       | MO Kansas City | with interior low-e panel                        | 191.4        | 789.53              | 980.93     | \$395.65    | 28.7%        | 5.7     | 3.2       |
| 4       | MO Kansas City | with exterior solar-E panel                      | 157.66       | 868.47              | 1026.13    | \$350.45    | 25.5%        | 7.2     | 5.1       |
| 4       | MO Kansas City | Wood frame, double pane                          | 208.16       | 937.75              | 1145.91    |             |              |         |           |
| 4       | MO Kansas City | with exterior clear panel                        | 191.9        | 866.99              | 1058.89    | \$87.02     | 7.6%         | 25.9    |           |
| 4       | MO Kansas City | with interior clear panel                        | 194.73       | 848.57              | 1043.3     | \$102.61    | 9.0%         | 24.5    |           |
| 4       | MO Kansas City | with exterior low-e panel                        | 178.16       | 823.83              | 1001.99    | \$143.92    | 12.6%        | 17.5    | 4.5       |
| 4       | MO Kansas City | with interior low-e panel                        | 187.66       | 793.82              | 981.48     | \$164.43    | 14.3%        | 13.7    | 4.1       |
| 4       | MO Kansas City | with exterior solar-E panel                      | 154.03       | 864.42              | 1018.45    | \$127.46    | 11.1%        | 19.7    | 6.3       |
| 4       | MO Kansas City | Metal frame, double pane                         | 204.12       | 1044.25             | 1248.37    |             |              |         |           |
| 4       | MO Kansas City | with exterior clear panel                        | 196.95       | 906.87              | 1103.82    | \$144.55    | 11.6%        | 15.6    |           |
| 4       | MO Kansas City | with interior clear panel                        | 193.82       | 888.98              | 1082.8     | \$165.57    | 13.3%        | 15.2    |           |
| 4       | MO Kansas City | with exterior low-e panel                        | 182.51       | 846.37              | 1028.88    | \$219.49    | 17.6%        | 11.4    | 3.4       |
| 4       | MO Kansas City | with interior low-e panel                        | 186.14       | 823.29              | 1009.43    | \$238.94    | 19.1%        | 9.4     | 3.5       |
| 4       | MO Kansas City | with exterior solar-E panel                      | 157.56       | 888.6               | 1046.16    | \$202.21    | 16.2%        | 12.4    | 4.4       |
| 4       | MO Kansas City | with exterior clear panel, worst case mounting   | 193.82       | 958.49              | 1152.31    | \$96.06     | 7.7%         | 23.5    |           |
| 4       | MO Kansas City | with exterior low-e panel, worst case mounting   | 179.78       | 923.56              | 1103.34    | \$145.03    | 11.6%        | 17.3    |           |
| 4       | MO Kansas City | with exterior solar-E panel, worst case mounting | 158.97       | 959.73              | 1118.7     | \$129.67    | 10.4%        | 19.4    |           |
| 4       | NC Raleigh     | Wood frame, single pane                          | 289.66       | 1091.01             | 1380.67    |             |              |         |           |
| 4       | NC Raleigh     | with exterior clear panel                        | 263.95       | 900.2               | 1164.15    | \$216.52    | 15.7%        | 10.4    |           |
| 4       | NC Raleigh     | with interior clear panel                        | 263.3        | 888.9               | 1152.2     | \$228.47    | 16.5%        | 11.0    |           |
| 4       | NC Raleigh     | with exterior low-e panel                        | 249.7        | 862.29              | 1111.99    | \$268.68    | 19.5%        | 9.3     | 4.9       |
| 4       | NC Raleigh     | with interior low-e panel                        | 258.88       | 832.45              | 1091.33    | \$289.34    | 21.0%        | 7.8     | 4.2       |
| 4       | NC Raleigh     | with exterior solar-E panel                      | 223.13       | 902.4               | 1125.53    | \$255.14    | 18.5%        | 9.8     | 6.6       |
| 4       | NC Raleigh     | Wood frame, double pane                          | 274.86       | 942.31              | 1217.17    |             |              |         |           |
| 4       | NC Raleigh     | with exterior clear panel                        | 258.12       | 895.02              | 1153.14    | \$64.03     | 5.3%         | 35.2    |           |
| 4       | NC Raleigh     | with interior clear panel                        | 261.36       | 880.24              | 1141.6     | \$75.57     | 6.2%         | 33.2    |           |
| 4       | NC Raleigh     | with exterior low-e panel                        | 244.3        | 863.39              | 1107.69    | \$109.48    | 9.0%         | 22.9    | 5.6       |
| 4       | NC Raleigh     | with interior low-e panel                        | 254.88       | 837.76              | 1092.64    | \$124.53    | 10.2%        | 18.1    | 5.2       |
| 4       | NC Raleigh     | with exterior solar-E panel                      | 219.35       | 901.44              | 1120.79    | \$96.38     | 7.9%         | 26.1    | 7.9       |
| 4       | NC Raleigh     | Metal frame, double pane                         | 269.68       | 1027.1              | 1296.78    |             |              |         |           |
| 4       | NC Raleigh     | with exterior clear panel                        | 263.3        | 925.59              | 1188.89    | \$107.89    | 8.3%         | 20.9    |           |
| 4       | NC Raleigh     | with interior clear panel                        | 260.06       | 912.63              | 1172.69    | \$124.09    | 9.6%         | 20.2    |           |
| 4       | NC Raleigh     | with exterior low-e panel                        | 248.72       | 880.26              | 1128.98    | \$167.80    | 12.9%        | 15.0    | 4.3       |
| 4       | NC Raleigh     | with interior low-e panel                        | 253.15       | 861.45              | 1114.6     | \$182.18    | 14.0%        | 12.4    | 4.4       |
| 4       | NC Raleigh     | with exterior solar-E panel                      | 222.91       | 919.83              | 1142.74    | \$154.04    | 11.9%        | 16.3    | 5.5       |
| 4       | NC Raleigh     | with exterior clear panel, worst case mounting   | 259.42       | 966.97              | 1226.39    | \$70.39     | 5.4%         | 32.1    |           |
| 4       | NC Raleigh     | with exterior low-e panel, worst case mounting   | 245.81       | 941.97              | 1187.78    | \$109.00    | 8.4%         | 23.0    |           |
| 4       | NC Raleigh     | with exterior solar-E panel, worst case mounting | 223.88       | 975.92              | 1199.8     | \$96.98     | 7.5%         | 25.9    |           |

| Climate Zone | Location      | Window  | HVAC         | Whole H | ouse Cooling | Whole Ho | use Heating | Source | e Energy | % source energy savings |
|--------------|---------------|---|--------------|---------|--------------|----------|-------------|--------|----------|-------------------------|
| 3            | GA Atlanta    | Wood frame, single pane                         | Furnace / AC | 2904    | kWh          | 43.9     | MBtu        | 81.3   | MBtu     |                         |
| 3            | GA Atlanta    | with exterior clear panel                       | Furnace / AC | 2696    | kWh          | 31.7     | MBtu        | 65.6   | MBtu     | 19.3%                   |
| 3            | GA Atlanta    | with interior clear panel                       | Furnace / AC | 2689    | kWh          | 31       | MBtu        | 64.7   | MBtu     | 20.4%                   |
| 3            | GA Atlanta    | with exterior low-e panel                       | Furnace / AC | 2566    | kWh          | 29.3     | MBtu        | 61.5   | MBtu     | 24.4%                   |
| 3            | GA Atlanta    | with interior low-e panel                       | Furnace / AC | 2665    | kWh          | 27.4     | MBtu        | 60.5   | MBtu     | 25.5%                   |
| 3            | GA Atlanta    | with exterior solar-E panel                     | Furnace / AC | 2288    | kWh          | 31.8     | MBtu        | 61.0   | MBtu     | 25.0%                   |
| 3            | GA Atlanta    | Wood frame, double pane                         | Furnace / AC | 2790    | kWh          | 34.3     | MBtu        | 69.5   | MBtu     |                         |
| 3            | GA Atlanta    | with exterior clear panel                       | Furnace / AC | 2640    | kWh          | 31.3     | MBtu        | 64.5   | MBtu     | 7.2%                    |
| 3            | GA Atlanta    | with interior clear panel                       | Furnace / AC | 2674    | kWh          | 30.3     | MBtu        | 63.8   | MBtu     | 8.2%                    |
| 3            | GA Atlanta    | with exterior low-e panel                       | Furnace / AC | 2512    | kWh          | 29.3     | MBtu        | 60.8   | MBtu     | 12.5%                   |
| 3            | GA Atlanta    | with interior low-e panel                       | Furnace / AC | 2621    | kWh          | 27.7     | MBtu        | 60.3   | MBtu     | 13.2%                   |
| 3            | GA Atlanta    | with exterior solar-E panel                     | Furnace / AC | 2251    | kWh          | 31.6     | MBtu        | 60.4   | MBtu     | 13.1%                   |
| 3            | GA Atlanta    | Metal frame, double pane                        | Furnace / AC | 2729    | kWh          | 39.6     | MBtu        | 74.6   | MBtu     |                         |
| 3            | GA Atlanta    | with exterior clear panel                       | Furnace / AC | 2685    | kWh          | 33.2     | MBtu        | 67.1   | MBtu     | 10.0%                   |
| 3            | GA Atlanta    | with interior clear panel                       | Furnace / AC | 2657    | kWh          | 32.4     | MBtu        | 65.9   | MBtu     | 11.7%                   |
| 3            | GA Atlanta    | with exterior low-e panel                       | Furnace / AC | 2558    | kWh          | 30.3     | MBtu        | 62.5   | MBtu     | 16.3%                   |
| 3            | GA Atlanta    | with interior low-e panel                       | Furnace / AC | 2605    | kWh          | 29.1     | MBtu        | 61.7   | MBtu     | 17.3%                   |
| 3            | GA Atlanta    | with exterior solar-E panel                     | Furnace / AC | 2285    | kWh          | 32.8     | MBtu        | 62.1   | MBtu     | 16.8%                   |
| 3            | GA Atlanta    | with exterior clear panel, worst case mounting  | Furnace / AC | 2644    | kWh          | 35.8     | MBtu        | 69.5   | MBtu     | 6.9%                    |
| 3            | GA Atlanta    | with exterior low-e panel, worst case mounting  | Furnace / AC | 2513    | kWh          | 34.1     | MBtu        | 66.1   | MBtu     | 11.4%                   |
| 3            | GA Atlanta    | with exterior solar-E panel, worst case mountin | Furnace / AC | 2283    | kWh          | 36.4     | MBtu        | 66.0   | MBtu     | 11.6%                   |
| 3            | TX Fort Worth | Wood frame, single pane                         | Furnace / AC | 4607    | kWh          | 33.7     | MBtu        | 89.7   | MBtu     |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Furnace / AC | 4130    | kWh          | 22.9     | MBtu        | 72.4   | MBtu     | 19.3%                   |
| 3            | TX Fort Worth | with interior clear panel                       | Furnace / AC | 4112    | kWh          | 22.3     | MBtu        | 71.6   | MBtu     | 20.2%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Furnace / AC | 3910    | kWh          | 20.9     | MBtu        | 67.7   | MBtu     | 24.5%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Furnace / AC | 3990    | kWh          | 19.3     | MBtu        | 66.9   | MBtu     | 25.4%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Furnace / AC | 3544    | kWh          | 23.2     | MBtu        | 66.0   | MBtu     | 26.4%                   |
| 3            | TX Fort Worth | Wood frame, double pane                         | Furnace / AC | 4304    | kWh          | 25.2     | MBtu        | 76.9   | MBtu     |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Furnace / AC | 4054    | kWh          | 22.6     | MBtu        | 71.2   | MBtu     | 7.4%                    |
| 3            | TX Fort Worth | with interior clear panel                       | Furnace / AC | 4091    | kWh          | 21.8     | MBtu        | 70.8   | MBtu     | 8.0%                    |
| 3            | TX Fort Worth | with exterior low-e panel                       | Furnace / AC | 3839    | kWh          | 20.9     | MBtu        | 66.9   | MBtu     | 13.0%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Furnace / AC | 3943    | kWh          | 19.6     | MBtu        | 66.7   | MBtu     | 13.3%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Furnace / AC | 3492    | kWh          | 23.1     | MBtu        | 65.3   | MBtu     | 15.1%                   |
| 3            | TX Fort Worth | Metal frame, double pane                        | Furnace / AC | 4285    | kWh          | 29.7     | MBtu        | 81.6   | MBtu     |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Furnace / AC | 4141    | kWh          | 24.2     | MBtu        | 74.0   | MBtu     | 9.4%                    |
| 3            | TX Fort Worth | with interior clear panel                       | Furnace / AC | 4086    | kWh          | 23.5     | MBtu        | 72.6   | MBtu     | 11.1%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Furnace / AC | 3910    | kWh          | 21.8     | MBtu        | 68.7   | MBtu     | 15.8%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Furnace / AC | 3960    | kWh          | 20.8     | MBtu        | 68.2   | MBtu     | 16.5%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Furnace / AC | 3553    | kWh          | 24.1     | MBtu        | 67.1   | MBtu     | 17.8%                   |
| 3            | TX Fort Worth | with exterior clear panel, worst case mounting  | Furnace / AC | 4112    | kWh          | 26.4     | MBtu        | 76.0   | MBtu     | 6.8%                    |
| 3            | TX Fort Worth | with exterior low-e panel, worst case mounting  | Furnace / AC | 3892    | kWh          | 25.1     | MBtu        | 72.1   | MBtu     | 11.7%                   |
| 3            | TX Fort Worth | with exterior solar-E panel, worst case mountin | Furnace / AC | 3591    | kWh          | 27.1     | MBtu        | 70.8   | MBtu     | 13.2%                   |

| Climate | Location      | Window  | Cooling Cost | Heating Cost | Total Cost | Energy cost          | % energy     | Simple       | Payback   |
|---------|---------------|---|--------------|--------------|------------|----------------------|--------------|--------------|-----------|
| Zone    | ~             |   | (\$)         | (\$)         | (\$)       | savings              | cost savings | payback      | for low-e |
| 3       | GA Atlanta    | Wood frame, single pane                               | 319.44       | 675.36       | 994.8      |                      |              |              |           |
| 3       | GA Atlanta    | with exterior clear panel                             | 296.56       | 487.12       | 783.68     | \$211.12             | 21.2%        | 10.7         |           |
| 3       | GA Atlanta    | with interior clear panel                             | 295.79       | 476.15       | 771.94     | \$222.86             | 22.4%        | 11.3         |           |
| 3       | GA Atlanta    | with exterior low-e panel                             | 282.26       | 449.68       | 731.94     | \$262.86             | 26.4%        | 9.6          | 4.9       |
| 3       | GA Atlanta    | with interior low-e panel                             | 293.15       | 421.31       | 714.46     | \$280.34             | 28.2%        | 8.1          | 4.4       |
| 3       | GA Atlanta    | with exterior solar-E panel                           | 251.68       | 488.24       | 739.92     | \$254.88             | 25.6%        | 9.9          | 5.8       |
| 3       | GA Atlanta    | Wood frame, double pane                               | 306.9        | 527.11       | 834.01     |                      |              |              |           |
| 3       | GA Atlanta    | with exterior clear panel                             | 290.4        | 480.62       | 771.02     | \$62.99              | 7.6%         | 35.8         |           |
| 3       | GA Atlanta    | with interior clear panel                             | 294.14       | 466.45       | 760.59     | \$73.42              | 8.8%         | 34.2         |           |
| 3       | GA Atlanta    | with exterior low-e panel                             | 276.32       | 449.76       | 726.08     | \$107.93             | 12.9%        | 23.3         | 5.7       |
| 3       | GA Atlanta    | with interior low-e panel                             | 288.31       | 425.38       | 713.69     | \$120.32             | 14.4%        | 18.8         | 5.4       |
| 3       | GA Atlanta    | with exterior solar-E panel                           | 247.61       | 486.46       | 734.07     | \$99.94              | 12.0%        | 25.1         | 6.9       |
| 3       | GA Atlanta    | Metal frame, double pane                              | 300.19       | 608.79       | 908.98     |                      |              |              |           |
| 3       | GA Atlanta    | with exterior clear panel                             | 295.35       | 509.73       | 805.08     | \$103.90             | 11.4%        | 21.7         |           |
| 3       | GA Atlanta    | with interior clear panel                             | 292.27       | 497.33       | 789.6      | \$119.38             | 13.1%        | 21.0         |           |
| 3       | GA Atlanta    | with exterior low-e panel                             | 281.38       | 465.68       | 747.06     | \$161.92             | 17.8%        | 15.5         | 4.4       |
| 3       | GA Atlanta    | with interior low-e panel                             | 286.55       | 447.59       | 734.14     | \$174.84             | 19.2%        | 12.9         | 4.6       |
| 3       | GA Atlanta    | with exterior solar-E panel                           | 251.35       | 504.04       | 755.39     | \$153.59             | 16.9%        | 16.4         | 5.1       |
| 3       | GA Atlanta    | with exterior clear panel, worst case mounting        | 290.84       | 549.49       | 840.33     | \$68.65              | 7.6%         | 32.9         |           |
| 3       | GA Atlanta    | with exterior low-e panel, worst case mounting        | 276.43       | 524.7        | 801.13     | \$107.85             | 11.9%        | 23.3         |           |
| 3       | GA Atlanta    | with exterior solar-E panel, worst case mounting      | 251.13       | 558.9        | 810.03     | \$98.95              | 10.9%        | 25.4         |           |
| 3       | TX Fort Worth | Wood frame, single pane                               | 506.77       | 358.7        | 865.47     |                      |              |              |           |
| 3       | TX Fort Worth | with exterior clear panel                             | 454.3        | 244.14       | 698.44     | \$167.03             | 19.3%        | 13.5         |           |
| 3       | TX Fort Worth | with interior clear panel                             | 452.32       | 237.53       | 689.85     | \$175.62             | 20.3%        | 14.3         |           |
| 3       | TX Fort Worth | with exterior low-e panel                             | 430.1        | 222.96       | 653.06     | \$212.41             | 24.5%        | 11.8         | 5.6       |
| 3       | TX Fort Worth | with interior low-e panel                             | 438.9        | 206.03       | 644.93     | \$220.54             | 25.5%        | 10.2         | 5.7       |
| 3       | TX Fort Worth | with exterior solar-E panel                           | 389.84       | 246.94       | 636.78     | \$228.69             | 26.4%        | 11.0         | 4.1       |
| 3       | TX Fort Worth | Wood frame, double pane                               | 473.44       | 267.89       | 741.33     |                      |              |              |           |
| 3       | TX Fort Worth | with exterior clear panel                             | 445.94       | 240.62       | 686.56     | \$54.77              | 7.4%         | 41.2         |           |
| 3       | TX Fort Worth | with interior clear panel                             | 450.01       | 231.88       | 681.89     | \$59.44              | 8.0%         | 42.3         |           |
| 3       | TX Fort Worth | with exterior low-e panel                             | 422.29       | 223.1        | 645.39     | \$95.94              | 12.9%        | 26.2         | 6.2       |
| 3       | TX Fort Worth | with exterior low-e panel                             | 433.73       | 208.34       | 642.07     | \$99.26              | 13.4%        | 22.7         | 6.4       |
| 3       | TX Fort Worth | with exterior solar-E panel                           | 384.12       | 246.1        | 630.22     | \$111.11             | 15.0%        | 22.6         | 4.5       |
| 3       | TX Fort Worth | Metal frame, double pane                              | 471.35       | 316.65       | 788        |                      |              |              | 7.0       |
| 3       | TX Fort Worth | with exterior clear panel                             | 455.51       | 257.38       | 712.89     | \$75.11              | 9.5%         | 30.0         |           |
| 3       | TX Fort Worth | with interior clear panel                             | 449.46       | 249.99       | 699.45     | \$88.55              | 11.2%        | 28.4         |           |
| 3       | TX Fort Worth | with exterior low-e panel                             | 430.1        | 232.23       | 662.33     | \$125.67             | 15.9%        | 20.4         | 5.0       |
| 3       | TX Fort Worth | with interior low-e panel                             | 435.6        | 232.23       | 656.79     | \$123.67<br>\$131.21 | 16.7%        | 17.2         | 6.0       |
| 3       | TX Fort Worth | with interior low-e panel with exterior solar-E panel | 390.83       | 256.3        | 647.13     | \$131.21<br>\$140.87 | 17.9%        | 17.2<br>17.8 | 3.9       |
| 3       | TX Fort Worth | with exterior clear panel, worst case mounting        | 452.32       | 281.01       | 733.33     | \$140.87<br>\$54.67  | 6.9%         | 41.3         | 3.9       |
| _       | TX Fort Worth |   |              |              |            |                      |              | 27.1         |           |
| 3       |               | with exterior low-e panel, worst case mounting        | 428.12       | 267.29       | 695.41     | \$92.59              | 11.8%        | 24.0         |           |
| 3       | TX Fort Worth | with exterior solar-E panel, worst case mounting      | 395.01       | 288.41       | 683.42     | \$104.58             | 13.3%        | 24.0         |           |

| Climate Zone | Location      | Window  | HVAC           | Whole H | ouse Cooling | Whole Hou | se Heating | Source | Energy | % source energy savings |
|--------------|---------------|---|----------------|---------|--------------|-----------|------------|--------|--------|-------------------------|
| 3            | TX Fort Worth | Wood frame, single pane                         | Heat pump / AC | 4607    | kWh          | 2857      | kWh        | 85.7   | MBtu   |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Heat pump / AC | 4130    | kWh          | 2115      | kWh        | 71.7   | MBtu   | 16.3%                   |
| 3            | TX Fort Worth | with interior clear panel                       | Heat pump / AC | 4112    | kWh          | 2074      | kWh        | 71.0   | MBtu   | 17.1%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Heat pump / AC | 3910    | kWh          | 1970      | kWh        | 67.5   | MBtu   | 21.2%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Heat pump / AC | 3990    | kWh          | 1841      | kWh        | 67.0   | MBtu   | 21.9%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Heat pump / AC | 3544    | kWh          | 2123      | kWh        | 65.1   | MBtu   | 24.1%                   |
| 3            | TX Fort Worth | Wood frame, double pane                         | Heat pump / AC | 4304    | kWh          | 2279      | kWh        | 75.6   | MBtu   |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Heat pump / AC | 4054    | kWh          | 2087      | kWh        | 70.5   | MBtu   | 6.7%                    |
| 3            | TX Fort Worth | with interior clear panel                       | Heat pump / AC | 4091    | kWh          | 2037      | kWh        | 70.4   | MBtu   | 6.9%                    |
| 3            | TX Fort Worth | with exterior low-e panel                       | Heat pump / AC | 3839    | kWh          | 1970      | kWh        | 66.7   | MBtu   | 11.8%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Heat pump / AC | 3943    | kWh          | 1856      | kWh        | 66.6   | MBtu   | 11.9%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Heat pump / AC | 3492    | kWh          | 2117      | kWh        | 64.4   | MBtu   | 14.8%                   |
| 3            | TX Fort Worth | Metal frame, double pane                        | Heat pump / AC | 4285    | kWh          | 2569      | kWh        | 78.7   | MBtu   |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Heat pump / AC | 4141    | kWh          | 2202      | kWh        | 72.8   | MBtu   | 7.5%                    |
| 3            | TX Fort Worth | with interior clear panel                       | Heat pump / AC | 4086    | kWh          | 2152      | kWh        | 71.6   | MBtu   | 9.0%                    |
| 3            | TX Fort Worth | with exterior low-e panel                       | Heat pump / AC | 3910    | kWh          | 2032      | kWh        | 68.2   | MBtu   | 13.3%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Heat pump / AC | 3960    | kWh          | 1961      | kWh        | 68.0   | MBtu   | 13.6%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Heat pump / AC | 3553    | kWh          | 2186      | kWh        | 65.9   | MBtu   | 16.3%                   |
| 3            | TX Fort Worth | with exterior clear panel, worst case mounting  | Heat pump / AC | 4112    | kWh          | 2345      | kWh        | 74.1   | MBtu   | 5.8%                    |
| 3            | TX Fort Worth | with exterior low-e panel, worst case mounting  | Heat pump / AC | 3892    | kWh          | 2251      | kWh        | 70.5   | MBtu   | 10.4%                   |
| 3            | TX Fort Worth | with exterior solar-E panel, worst case mountin | Heat pump / AC | 3591    | kWh          | 2382      | kWh        | 68.6   | MBtu   | 12.9%                   |
| 2            | AZ Phoenix    | Wood frame, single pane                         | Heat pump / AC | 8512    | kWh          | 1105      | kWh        | 110.4  | MBtu   |                         |
| 2            | AZ Phoenix    | with exterior clear panel                       | Heat pump / AC | 7591    | kWh          | 791       | kWh        | 96.2   | MBtu   | 12.8%                   |
| 2            | AZ Phoenix    | with interior clear panel                       | Heat pump / AC | 7559    | kWh          | 775       | kWh        | 95.7   | MBtu   | 13.3%                   |
| 2            | AZ Phoenix    | with exterior low-e panel                       | Heat pump / AC | 7157    | kWh          | 724       | kWh        | 90.5   | MBtu   | 18.1%                   |
| 2            | AZ Phoenix    | with interior low-e panel                       | Heat pump / AC | 7295    | kWh          | 677       | kWh        | 91.5   | MBtu   | 17.1%                   |
| 2            | AZ Phoenix    | with exterior solar-E panel                     | Heat pump / AC | 6634    | kWh          | 800       | kWh        | 85.4   | MBtu   | 22.7%                   |
| 2            | AZ Phoenix    | Wood frame, double pane                         | Heat pump / AC | 7903    | kWh          | 860       | kWh        | 100.6  | MBtu   |                         |
| 2            | AZ Phoenix    | with exterior clear panel                       | Heat pump / AC | 7470    | kWh          | 782       | kWh        | 94.7   | MBtu   | 5.8%                    |
| 2            | AZ Phoenix    | with interior clear panel                       | Heat pump / AC | 7516    | kWh          | 756       | kWh        | 95.0   | MBtu   | 5.6%                    |
| 2            | AZ Phoenix    | with exterior low-e panel                       | Heat pump / AC | 7042    | kWh          | 725       | kWh        | 89.2   | MBtu   | 11.4%                   |
| 2            | AZ Phoenix    | with interior low-e panel                       | Heat pump / AC | 7225    | kWh          | 685       | kWh        | 90.8   | MBtu   | 9.7%                    |
| 2            | AZ Phoenix    | with exterior solar-E panel                     | Heat pump / AC | 6549    | kWh          | 799       | kWh        | 84.4   | MBtu   | 16.1%                   |
| 2            | AZ Phoenix    | Metal frame, double pane                        | Heat pump / AC | 8016    | kWh          | 1002      | kWh        | 103.5  | MBtu   |                         |
| 2            | AZ Phoenix    | with exterior clear panel                       | Heat pump / AC | 7669    | kWh          | 834       | kWh        | 97.6   | MBtu   | 5.7%                    |
| 2            | AZ Phoenix    | with interior clear panel                       | Heat pump / AC | 7571    | kWh          | 813       | kWh        | 96.3   | MBtu   | 7.0%                    |
| 2            | AZ Phoenix    | with exterior low-e panel                       | Heat pump / AC | 7191    | kWh          | 752       | kWh        | 91.2   | MBtu   | 11.9%                   |
| 2            | AZ Phoenix    | with interior low-e panel                       | Heat pump / AC | 7249    | kWh          | 722       | kWh        | 91.5   | MBtu   | 11.6%                   |
| 2            | AZ Phoenix    | with exterior solar-E panel                     | Heat pump / AC | 6679    | kWh          | 834       | kWh        | 86.3   | MBtu   | 16.7%                   |
| 2            | AZ Phoenix    | with exterior clear panel, worst case mounting  | Heat pump / AC | 7691    | kWh          | 905       | kWh        | 98.7   | MBtu   | 4.7%                    |
| 2            | AZ Phoenix    | with exterior low-e panel, worst case mounting  | Heat pump / AC | 7277    | kWh          | 858       | kWh        | 93.4   | MBtu   | 9.8%                    |
| 2            | AZ Phoenix    | with exterior solar-E panel, worst case mountin | Heat pump / AC | 6841    | kWh          | 929       | kWh        | 89.2   | MBtu   | 13.8%                   |

| Climate | Location      | Window  | Cooling Cost | Heating Cost | Total Cost | Energy cost | % energy     | Simple  | Payback   |
|---------|---------------|---|--------------|--------------|------------|-------------|--------------|---------|-----------|
| Zone    |               |   | (\$)         | (\$)         | (\$)       | savings     | cost savings | payback | for low-e |
| 3       | TX Fort Worth | Wood frame, single pane                             | 506.77       | 314.27       | 821.04     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                           | 454.3        | 232.65       | 686.95     | \$134.09    | 16.3%        | 16.8    |           |
| 3       | TX Fort Worth | with interior clear panel                           | 452.32       | 228.14       | 680.46     | \$140.58    | 17.1%        | 17.9    |           |
| 3       | TX Fort Worth | with exterior low-e panel                           | 430.1        | 216.7        | 646.8      | \$174.24    | 21.2%        | 14.4    | 6.4       |
| 3       | TX Fort Worth | with interior low-e panel                           | 438.9        | 202.51       | 641.41     | \$179.63    | 21.9%        | 12.6    | 6.5       |
| 3       | TX Fort Worth | with exterior solar-E panel                         | 389.84       | 233.53       | 623.37     | \$197.67    | 24.1%        | 12.7    | 4.0       |
| 3       | TX Fort Worth | Wood frame, double pane                             | 473.44       | 250.69       | 724.13     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                           | 445.94       | 229.57       | 675.51     | \$48.62     | 6.7%         | 46.4    |           |
| 3       | TX Fort Worth | with interior clear panel                           | 450.01       | 224.07       | 674.08     | \$50.05     | 6.9%         | 50.2    |           |
| 3       | TX Fort Worth | with exterior low-e panel                           | 422.29       | 216.7        | 638.99     | \$85.14     | 11.8%        | 29.5    | 7.0       |
| 3       | TX Fort Worth | with interior low-e panel                           | 433.73       | 204.16       | 637.89     | \$86.24     | 11.9%        | 26.2    | 7.0       |
| 3       | TX Fort Worth | with exterior solar-E panel                         | 384.12       | 232.87       | 616.99     | \$107.14    | 14.8%        | 23.4    | 4.4       |
| 3       | TX Fort Worth | Metal frame, double pane                            | 471.35       | 282.59       | 753.94     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                           | 455.51       | 242.22       | 697.73     | \$56.21     | 7.5%         | 40.1    |           |
| 3       | TX Fort Worth | with interior clear panel                           | 449.46       | 236.72       | 686.18     | \$67.76     | 9.0%         | 37.1    |           |
| 3       | TX Fort Worth | with exterior low-e panel                           | 430.1        | 223.52       | 653.62     | \$100.32    | 13.3%        | 25.0    | 5.8       |
| 3       | TX Fort Worth | with interior low-e panel                           | 435.6        | 215.71       | 651.31     | \$102.63    | 13.6%        | 22.0    | 7.3       |
| 3       | TX Fort Worth | with exterior solar-E panel                         | 390.83       | 240.46       | 631.29     | \$122.65    | 16.3%        | 20.5    | 3.8       |
| 3       | TX Fort Worth | with exterior clear panel, worst case mounting      | 452.32       | 257.95       | 710.27     | \$43.67     | 5.8%         | 51.7    |           |
| 3       | TX Fort Worth | with exterior low-e panel, worst case mounting      | 428.12       | 247.61       | 675.73     | \$78.21     | 10.4%        | 32.1    |           |
| 3       | TX Fort Worth | with exterior solar-E panel, worst case mounting    | 395.01       | 262.02       | 657.03     | \$96.91     | 12.9%        | 25.9    |           |
| 2       | AZ Phoenix    | Wood frame, single pane                             | 961.86       | 124.86       | 1086.72    |             |              |         |           |
| 2       | AZ Phoenix    | with exterior clear panel                           | 857.78       | 89.38        | 947.16     | \$139.56    | 12.8%        | 16.2    |           |
| 2       | AZ Phoenix    | with interior clear panel                           | 854.17       | 87.57        | 941.74     | \$144.98    | 13.3%        | 17.3    |           |
| 2       | AZ Phoenix    | with exterior low-e panel                           | 808.74       | 81.81        | 890.55     | \$196.17    | 18.1%        | 12.8    | 4.5       |
| 2       | AZ Phoenix    | with interior low-e panel                           | 824.33       | 76.5         | 900.83     | \$185.89    | 17.1%        | 12.1    | 6.2       |
| 2       | AZ Phoenix    | with exterior solar-E panel                         | 749.64       | 90.4         | 840.04     | \$246.68    | 22.7%        | 10.2    | 2.4       |
| 2       | AZ Phoenix    | Wood frame, double pane                             | 893.04       | 97.18        | 990.22     |             |              |         |           |
| 2       | AZ Phoenix    | with exterior clear panel                           | 844.11       | 88.37        | 932.48     | \$57.74     | 5.8%         | 39.1    |           |
| 2       | AZ Phoenix    | with interior clear panel                           | 849.31       | 85.43        | 934.74     | \$55.48     | 5.6%         | 45.3    |           |
| 2       | AZ Phoenix    | with exterior low-e panel                           | 795.75       | 81.92        | 877.67     | \$112.55    | 11.4%        | 22.3    | 4.7       |
| 2       | AZ Phoenix    | with interior low-e panel                           | 816.42       | 77.4         | 893.82     | \$96.40     | 9.7%         | 23.4    | 6.2       |
| 2       | AZ Phoenix    | with exterior solar-E panel                         | 740.04       | 90.29        | 830.33     | \$159.89    | 16.1%        | 15.7    | 2.5       |
| 2       | AZ Phoenix    | Metal frame, double pane                            | 905.81       | 113.23       | 1019.04    |             |              |         |           |
| 2       | AZ Phoenix    | with exterior clear panel                           | 866.6        | 94.24        | 960.84     | \$58.20     | 5.7%         | 38.8    |           |
| 2       | AZ Phoenix    | with exertor clear panel                            | 855.52       | 91.87        | 947.39     | \$71.65     | 7.0%         | 35.1    |           |
| 2       | AZ Phoenix    | with interior clear panel with exterior low-e panel | 812.58       | 84.98        | 897.56     | \$121.48    | 11.9%        | 20.7    | 4.0       |
| 2       | AZ Phoenix    | with interior low-e panel                           | 819.14       | 81.59        | 900.73     | \$118.31    | 11.6%        | 19.1    | 5.5       |
| 2       | AZ Phoenix    | with exterior solar-E panel                         | 754.73       | 94.24        | 848.97     | \$170.07    | 16.7%        | 14.8    | 2.3       |
| 2       | AZ Phoenix    | with exterior clear panel, worst case mounting      | 869.08       | 102.26       | 971.34     | \$47.70     | 4.7%         | 47.3    |           |
| 2       | AZ Phoenix    | with exterior low-e panel, worst case mounting      | 822.3        | 96.95        | 919.25     | \$99.79     | 9.8%         | 25.2    |           |
| 2       | AZ Phoenix    | with exterior solar-E panel, worst case mounting    | 773.03       | 104.98       | 878.01     | \$141.03    | 13.8%        | 17.8    |           |

| Climate Zone | Location        | Window  | HVAC           | Whole F | Iouse Cooling | Whole Hou | ise Heating | Source | e Energy | % source energy savings |
|--------------|-----------------|---|----------------|---------|---------------|-----------|-------------|--------|----------|-------------------------|
| 2            | FL Jacksonville | Wood frame, single pane                         | Heat pump / AC | 4829    | kWh           | 1635      | kWh         | 74.2   | MBtu     |                         |
| 2            | FL Jacksonville | with exterior clear panel                       | Heat pump / AC | 4379    | kWh           | 1207      | kWh         | 64.1   | MBtu     | 13.6%                   |
| 2            | FL Jacksonville | with interior clear panel                       | Heat pump / AC | 4363    | kWh           | 1184      | kWh         | 63.7   | MBtu     | 14.2%                   |
| 2            | FL Jacksonville | with exterior low-e panel                       | Heat pump / AC | 4171    | kWh           | 1122      | kWh         | 60.8   | MBtu     | 18.1%                   |
|              | FL Jacksonville | with interior low-e panel                       | Heat pump / AC | 4304    | kWh           | 1053      | kWh         | 61.5   | MBtu     | 17.1%                   |
| 2            | FL Jacksonville | with exterior solar-E panel                     | Heat pump / AC | 3782    | kWh           | 1223      | kWh         | 57.5   | MBtu     | 22.6%                   |
|              | FL Jacksonville | Wood frame, double pane                         | Heat pump / AC | 4553    | kWh           | 1301      | kWh         | 67.2   | MBtu     |                         |
| 2            | FL Jacksonville | with exterior clear panel                       | Heat pump / AC | 4300    | kWh           | 1195      | kWh         | 63.1   | MBtu     | 6.1%                    |
|              | FL Jacksonville | with interior clear panel                       | Heat pump / AC | 4338    | kWh           | 1163      | kWh         | 63.2   | MBtu     | 6.0%                    |
| 2            | FL Jacksonville | with exterior low-e panel                       | Heat pump / AC | 4101    | kWh           | 1123      | kWh         | 60.0   | MBtu     | 10.8%                   |
| 2            | FL Jacksonville | with interior low-e panel                       | Heat pump / AC | 4248    | kWh           | 1065      | kWh         | 61.0   | MBtu     | 9.2%                    |
| 2            | FL Jacksonville | with exterior solar-E panel                     | Heat pump / AC | 3731    | kWh           | 1221      | kWh         | 56.9   | MBtu     | 15.4%                   |
| 2            | FL Jacksonville | Metal frame, double pane                        | Heat pump / AC | 4491    | kWh           | 1487      | kWh         | 68.6   | MBtu     |                         |
| 2            | FL Jacksonville | with exterior clear panel                       | Heat pump / AC | 4375    | kWh           | 1264      | kWh         | 64.7   | MBtu     | 5.7%                    |
| 2            | FL Jacksonville | with interior clear panel                       | Heat pump / AC | 4324    | kWh           | 1235      | kWh         | 63.8   | MBtu     | 7.0%                    |
| 2            | FL Jacksonville | with exterior low-e panel                       | Heat pump / AC | 4168    | kWh           | 1162      | kWh         | 61.2   | MBtu     | 10.8%                   |
| 2            | FL Jacksonville | with interior low-e panel                       | Heat pump / AC | 4224    | kWh           | 1116      | kWh         | 61.3   | MBtu     | 10.7%                   |
| 2            | FL Jacksonville | with exterior solar-E panel                     | Heat pump / AC | 3783    | kWh           | 1262      | kWh         | 57.9   | MBtu     | 15.6%                   |
| 2            | FL Jacksonville | with exterior clear panel, worst case mounting  | Heat pump / AC | 4327    | kWh           | 1353      | kWh         | 65.2   | MBtu     | 5.0%                    |
|              | FL Jacksonville | with exterior low-e panel, worst case mounting  | Heat pump / AC | 4127    | kWh           | 1297      | kWh         | 62.3   | MBtu     | 9.3%                    |
| 2            | FL Jacksonville | with exterior solar-E panel, worst case mountin | Heat pump / AC | 3805    | kWh           | 1384      | kWh         | 59.6   | MBtu     | 13.2%                   |
| 2            | TX Houston      | Wood frame, single pane                         | Furnace / AC   | 4945    | kWh           | 21.4      | MBtu        | 80.1   | MBtu     |                         |
| 2            | TX Houston      | with exterior clear panel                       | Furnace / AC   | 4459    | kWh           | 14.4      | MBtu        | 66.9   | MBtu     | 16.5%                   |
| 2            | TX Houston      | with interior clear panel                       | Furnace / AC   | 4437    | kWh           | 14        | MBtu        | 66.2   | MBtu     | 17.4%                   |
| 2            | TX Houston      | with exterior low-e panel                       | Furnace / AC   | 4245    | kWh           | 13        | MBtu        | 62.9   | MBtu     | 21.5%                   |
| 2            | TX Houston      | with interior low-e panel                       | Furnace / AC   | 4371    | kWh           | 12        | MBtu        | 63.3   | MBtu     | 21.0%                   |
| 2            | TX Houston      | with exterior solar-E panel                     | Furnace / AC   | 3839    | kWh           | 14.3      | MBtu        | 59.7   | MBtu     | 25.5%                   |
| 2            | TX Houston      | Wood frame, double pane                         | Furnace / AC   | 4646    | kWh           | 15.9      | MBtu        | 70.7   | MBtu     |                         |
| 2            | TX Houston      | with exterior clear panel                       | Furnace / AC   | 4378    | kWh           | 14.2      | MBtu        | 65.8   | MBtu     | 7.0%                    |
| 2            | TX Houston      | with interior clear panel                       | Furnace / AC   | 4415    | kWh           | 13.7      | MBtu        | 65.7   | MBtu     | 7.1%                    |
| 2            | TX Houston      | with exterior low-e panel                       | Furnace / AC   | 4164    | kWh           | 13        | MBtu        | 62.0   | MBtu     | 12.3%                   |
| 2            | TX Houston      | with interior low-e panel                       | Furnace / AC   | 4317    | kWh           | 12.2      | MBtu        | 62.9   | MBtu     | 11.1%                   |
| 2            | TX Houston      | with exterior solar-E panel                     | Furnace / AC   | 3783    | kWh           | 14.2      | MBtu        | 58.9   | MBtu     | 16.6%                   |
| 2            | TX Houston      | Metal frame, double pane                        | Furnace / AC   | 4589    | kWh           | 18.8      | MBtu        | 73.2   | MBtu     |                         |
| 2            | TX Houston      | with exterior clear panel                       | Furnace / AC   | 4457    | kWh           | 15.2      | MBtu        | 67.8   | MBtu     | 7.4%                    |
| 2            | TX Houston      | with interior clear panel                       | Furnace / AC   | 4401    | kWh           | 14.7      | MBtu        | 66.6   | MBtu     | 9.1%                    |
| 2            | TX Houston      | with exterior low-e panel                       | Furnace / AC   | 4237    | kWh           | 13.6      | MBtu        | 63.5   | MBtu     | 13.3%                   |
| 2            | TX Houston      | with interior low-e panel                       | Furnace / AC   | 4290    | kWh           | 12.9      | MBtu        | 63.3   | MBtu     | 13.5%                   |
| 2            | TX Houston      | with exterior solar-E panel                     | Furnace / AC   | 3840    | kWh           | 14.9      | MBtu        | 60.4   | MBtu     | 17.6%                   |
| 2            | TX Houston      | with exterior clear panel, worst case mounting  | Furnace / AC   | 4412    | kWh           | 16.6      | MBtu        | 68.8   | MBtu     | 6.1%                    |
| 2            | TX Houston      | with exterior low-e panel, worst case mounting  | Furnace / AC   | 4197    | kWh           | 15.7      | MBtu        | 65.3   | MBtu     | 10.8%                   |
| 2            | TX Houston      | with exterior solar-E panel, worst case mountin | Furnace / AC   | 3863    | kWh           | 16.8      | MBtu        | 62.7   | MBtu     | 14.4%                   |

| Climate<br>Zone | Location        | Window  | Cooling Cost         | Heating Cost            | Total Cost         | Energy cost          | % energy       | Simple<br>payback   | Payback<br>for low-e |
|-----------------|-----------------|---|----------------------|-------------------------|--------------------|----------------------|----------------|---------------------|----------------------|
|                 | FL Jacksonville | W16   | ( <b>\$</b> ) 555.34 | ( <b>\$</b> )<br>188.03 | <b>(\$)</b> 743.37 | savings              | cost savings   | раураск             | ior iow-e            |
| 2<br>2          | FL Jacksonville | Wood frame, single pane with exterior clear panel | 503.59               | 138.81                  | 642.4              | \$100.97             | 13.6%          | 22.4                |                      |
| 2               | FL Jacksonville | with interior clear panel                         | 503.39               | 136.16                  | 637.91             | \$100.97<br>\$105.46 | 14.2%          | 23.8                |                      |
| 2               | FL Jacksonville | with exterior low-e panel                         | 479.67               | 129.03                  | 608.7              | \$105.46<br>\$134.67 | 14.2%<br>18.1% | 23.8<br><b>18.7</b> | 7.6                  |
|                 | FL Jacksonville | 1   | 494.96               | 129.03                  | 616.06             | \$134.67<br>\$127.31 | 18.1%<br>17.1% | 17.7                | 11.7                 |
| 2 2             | FL Jacksonville | with interior low-e panel                         | 494.96               | 140.65                  | 575.58             |                      | 22.6%          | 17.7                | 3.8                  |
|                 | FL Jacksonville | with exterior solar-E panel                       | 523.6                | 149.62                  | 673.22             | \$167.79             | 22.0%          |                     | 3.8                  |
| 2               | FL Jacksonville | Wood frame, double pane                           |                      |                         |                    | 641.20               | <br>( 10/      | <br>54.7            |                      |
| 2               |                 | with exterior clear panel                         | 494.5                | 137.43                  | 631.93             | \$41.29              | 6.1%           |                     |                      |
| 2               | FL Jacksonville | with interior clear panel                         | 498.87               | 133.75                  | 632.62             | \$40.60              | 6.0%           | 61.9                | 0.2                  |
| 2               | FL Jacksonville | with exterior low-e panel                         | 471.62               | 129.15                  | 600.77             | \$72.45              | 10.8%          | 34.7                | 8.2                  |
| 2               | FL Jacksonville | with interior low-e panel                         | 488.52               | 122.48                  | 611                | \$62.22              | 9.2%           | 36.3                | 11.8                 |
| 2               | FL Jacksonville | with exterior solar-E panel                       | 429.07               | 140.42                  | 569.49             | \$103.73             | 15.4%          | 24.2                | 4.1                  |
| 2               | FL Jacksonville | Metal frame, double pane                          | 516.47               | 171.01                  | 687.48             |                      |                |                     |                      |
| 2               | FL Jacksonville | with exterior clear panel                         | 503.13               | 145.36                  | 648.49             | \$38.99              | 5.7%           | 57.9                |                      |
| 2               | FL Jacksonville | with interior clear panel                         | 497.26               | 142.03                  | 639.29             | \$48.19              | 7.0%           | 52.1                |                      |
| 2               | FL Jacksonville | with exterior low-e panel                         | 479.32               | 133.63                  | 612.95             | \$74.53              | 10.8%          | 33.7                | 7.2                  |
| 2               | FL Jacksonville | with interior low-e panel                         | 485.76               | 128.34                  | 614.1              | \$73.38              | 10.7%          | 30.8                | 10.1                 |
| 2               | FL Jacksonville | with exterior solar-E panel                       | 435.05               | 145.13                  | 580.18             | \$107.30             | 15.6%          | 23.4                | 3.7                  |
| 2               | FL Jacksonville | with exterior clear panel, worst case mounting    | 497.61               | 155.6                   | 653.21             | \$34.27              | 5.0%           | 65.9                |                      |
| 2               | FL Jacksonville | with exterior low-e panel, worst case mounting    | 474.61               | 149.16                  | 623.77             | \$63.71              | 9.3%           | 39.4                |                      |
| 2               | FL Jacksonville | with exterior solar-E panel, worst case mounting  | 437.58               | 159.16                  | 596.74             | \$90.74              | 13.2%          | 27.7                |                      |
| 2               | TX Houston      | Wood frame, single pane                           | 543.95               | 227.43                  | 771.38             |                      |                |                     |                      |
| 2               | TX Houston      | with exterior clear panel                         | 490.49               | 153.73                  | 644.22             | \$127.16             | 16.5%          | 17.7                |                      |
| 2               | TX Houston      | with interior clear panel                         | 488.07               | 149.55                  | 637.62             | \$133.76             | 17.3%          | 18.8                |                      |
| 2               | TX Houston      | with exterior low-e panel                         | 466.95               | 138.59                  | 605.54             | \$165.84             | 21.5%          | 15.1                | 6.6                  |
| 2               | TX Houston      | with interior low-e panel                         | 480.81               | 128.25                  | 609.06             | \$162.32             | 21.0%          | 13.9                | 8.9                  |
| 2               | TX Houston      | with exterior solar-E panel                       | 422.29               | 152.43                  | 574.72             | \$196.66             | 25.5%          | 12.8                | 3.7                  |
| 2               | TX Houston      | Wood frame, double pane                           | 511.06               | 169.43                  | 680.49             |                      |                |                     |                      |
| 2               | TX Houston      | with exterior clear panel                         | 481.58               | 150.85                  | 632.43             | \$48.06              | 7.1%           | 47.0                |                      |
| 2               | TX Houston      | with interior clear panel                         | 485.65               | 145.65                  | 631.3              | \$49.19              | 7.2%           | 51.1                |                      |
| 2               | TX Houston      | with exterior low-e panel                         | 458.04               | 138.46                  | 596.5              | \$83.99              | 12.3%          | 29.9                | 7.1                  |
| 2               | TX Houston      | with interior low-e panel                         | 474.87               | 129.51                  | 604.38             | \$76.11              | 11.2%          | 29.7                | 9.5                  |
| 2               | TX Houston      | with exterior solar-E panel                       | 416.13               | 151.47                  | 567.6              | \$112.89             | 16.6%          | 22.2                | 3.9                  |
| 2               | TX Houston      | Metal frame, double pane                          | 504.79               | 200.2                   | 704.99             |                      |                |                     |                      |
| 2               | TX Houston      | with exterior clear panel                         | 490.27               | 162                     | 652.27             | \$52.72              | 7.5%           | 42.8                |                      |
| 2               | TX Houston      | with interior clear panel                         | 484.11               | 157.08                  | 641.19             | \$63.80              | 9.0%           | 39.4                |                      |
| 2               | TX Houston      | with exterior low-e panel                         | 466.07               | 144.66                  | 610.73             | \$94.26              | 13.4%          | 26.6                | 6.1                  |
| 2               | TX Houston      | with interior low-e panel                         | 471.9                | 137.74                  | 609.64             | \$95.35              | 13.5%          | 23.7                | 8.1                  |
| 2               | TX Houston      | with exterior solar-E panel                       | 422.4                | 158.25                  | 580.65             | \$124.34             | 17.6%          | 20.2                | 3.6                  |
| 2               | TX Houston      | with exterior clear panel, worst case mounting    | 485.32               | 176.73                  | 662.05             | \$42.94              | 6.1%           | 52.6                |                      |
| 2               | TX Houston      | with exterior low-e panel, worst case mounting    | 461.67               | 166.78                  | 628.45             | \$76.54              | 10.9%          | 32.8                |                      |
| 2               | TX Houston      | with exterior solar-E panel, worst case mounting  | 424.93               | 179.02                  | 603.95             | \$101.04             | 14.3%          | 24.9                |                      |

| Climate Zone | Location   | Window  | HVAC           | Whole H | ouse Cooling | Whole Ho | use Heating | Source | Energy | % source energy savings |
|--------------|------------|---|----------------|---------|--------------|----------|-------------|--------|--------|-------------------------|
| 2            | TX Houston | Wood frame, single pane                         | Heat pump / AC | 4945    | kWh          | 1913     | kWh         | 78.7   | MBtu   |                         |
| 2            | TX Houston | with exterior clear panel                       | Heat pump / AC | 4459    | kWh          | 1420     | kWh         | 67.5   | MBtu   | 14.3%                   |
| 2            | TX Houston | with interior clear panel                       | Heat pump / AC | 4437    | kWh          | 1396     | kWh         | 67.0   | MBtu   | 14.9%                   |
| 2            | TX Houston | with exterior low-e panel                       | Heat pump / AC | 4245    | kWh          | 1313     | kWh         | 63.8   | MBtu   | 19.0%                   |
| 2            | TX Houston | with interior low-e panel                       | Heat pump / AC | 4371    | kWh          | 1243     | kWh         | 64.5   | MBtu   | 18.1%                   |
| 2            | TX Houston | with exterior solar-E panel                     | Heat pump / AC | 3839    | kWh          | 1404     | kWh         | 60.2   | MBtu   | 23.5%                   |
| 2            | TX Houston | Wood frame, double pane                         | Heat pump / AC | 4646    | kWh          | 1530     | kWh         | 70.9   | MBtu   |                         |
| 2            | TX Houston | with exterior clear panel                       | Heat pump / AC | 4378    | kWh          | 1397     | kWh         | 66.3   | MBtu   | 6.5%                    |
| 2            | TX Houston | with interior clear panel                       | Heat pump / AC | 4415    | kWh          | 1368     | kWh         | 66.4   | MBtu   | 6.4%                    |
| 2            | TX Houston | with exterior low-e panel                       | Heat pump / AC | 4165    | kWh          | 1311     | kWh         | 62.9   | MBtu   | 11.3%                   |
| 2            | TX Houston | with interior low-e panel                       | Heat pump / AC | 4317    | kWh          | 1252     | kWh         | 63.9   | MBtu   | 9.8%                    |
| 2            | TX Houston | with exterior solar-E panel                     | Heat pump / AC | 3783    | kWh          | 1397     | kWh         | 59.5   | MBtu   | 16.1%                   |
| 2            | TX Houston | Metal frame, double pane                        | Heat pump / AC | 4589    | kWh          | 1723     | kWh         | 72.5   | MBtu   |                         |
| 2            | TX Houston | with exterior clear panel                       | Heat pump / AC | 4457    | kWh          | 1475     | kWh         | 68.1   | MBtu   | 6.0%                    |
| 2            | TX Houston | with interior clear panel                       | Heat pump / AC | 4401    | kWh          | 1440     | kWh         | 67.1   | MBtu   | 7.5%                    |
| 2            | TX Houston | with exterior low-e panel                       | Heat pump / AC | 4237    | kWh          | 1356     | kWh         | 64.2   | MBtu   | 11.4%                   |
| 2            | TX Houston | with interior low-e panel                       | Heat pump / AC | 4290    | kWh          | 1307     | kWh         | 64.3   | MBtu   | 11.3%                   |
| 2            | TX Houston | with exterior solar-E panel                     | Heat pump / AC | 3840    | kWh          | 1443     | kWh         | 60.7   | MBtu   | 16.3%                   |
| 2            | TX Houston | with exterior clear panel, worst case mounting  | Heat pump / AC | 4412    | kWh          | 1568     | kWh         | 68.7   | MBtu   | 5.3%                    |
| 2            | TX Houston | with exterior low-e panel, worst case mounting  | Heat pump / AC | 4197    | kWh          | 1497     | kWh         | 65.4   | MBtu   | 9.8%                    |
| 2            | TX Houston | with exterior solar-E panel, worst case mountin | Heat pump / AC | 3863    | kWh          | 1576     | kWh         | 62.4   | MBtu   | 13.8%                   |
| 1            | FL Miami   | Wood frame, single pane                         | Heat pump / AC | 7601    | kWh          | 79       | kWh         | 88.2   | MBtu   |                         |
| 1            | FL Miami   | with exterior clear panel                       | Heat pump / AC | 6920    | kWh          | 43       | kWh         | 79.9   | MBtu   | 9.3%                    |
| 1            | FL Miami   | with interior clear panel                       | Heat pump / AC | 6890    | kWh          | 41       | kWh         | 79.6   | MBtu   | 9.8%                    |
| 1            | FL Miami   | with exterior low-e panel                       | Heat pump / AC | 6625    | kWh          | 36       | kWh         | 76.5   | MBtu   | 13.3%                   |
| 1            | FL Miami   | with interior low-e panel                       | Heat pump / AC | 6797    | kWh          | 32       | kWh         | 78.4   | MBtu   | 11.1%                   |
| 1            | FL Miami   | with exterior solar-E panel                     | Heat pump / AC | 6051    | kWh          | 41       | kWh         | 69.9   | MBtu   | 20.7%                   |
| 1            | FL Miami   | Wood frame, double pane                         | Heat pump / AC | 7193    | kWh          | 50       | kWh         | 83.2   | MBtu   |                         |
| 1            | FL Miami   | with exterior clear panel                       | Heat pump / AC | 6813    | kWh          | 42       | kWh         | 78.7   | MBtu   | 5.4%                    |
| 1            | FL Miami   | with interior clear panel                       | Heat pump / AC | 6862    | kWh          | 40       | kWh         | 79.2   | MBtu   | 4.7%                    |
| 1            | FL Miami   | with exterior low-e panel                       | Heat pump / AC | 6517    | kWh          | 35       | kWh         | 75.2   | MBtu   | 9.5%                    |
| 1            | FL Miami   | with interior low-e panel                       | Heat pump / AC | 6724    | kWh          | 33       | kWh         | 77.6   | MBtu   | 6.7%                    |
| 1            | FL Miami   | with exterior solar-E panel                     | Heat pump / AC | 5972    | kWh          | 41       | kWh         | 69.0   | MBtu   | 17.0%                   |
| 1            | FL Miami   | Metal frame, double pane                        | Heat pump / AC | 7100    | kWh          | 65       | kWh         | 82.3   | MBtu   |                         |
| 1            | FL Miami   | with exterior clear panel                       | Heat pump / AC | 6921    | kWh          | 47       | kWh         | 80.0   | MBtu   | 2.7%                    |
| 1            | FL Miami   | with interior clear panel                       | Heat pump / AC | 6842    | kWh          | 44       | kWh         | 79.1   | MBtu   | 3.9%                    |
| 1            | FL Miami   | with exterior low-e panel                       | Heat pump / AC | 6613    | kWh          | 38       | kWh         | 76.4   | MBtu   | 7.2%                    |
| 1            | FL Miami   | with interior low-e panel                       | Heat pump / AC | 6690    | kWh          | 36       | kWh         | 77.2   | MBtu   | 6.1%                    |
| 1            | FL Miami   | with exterior solar-E panel                     | Heat pump / AC | 6052    | kWh          | 44       | kWh         | 70.0   | MBtu   | 14.9%                   |
| 1            | FL Miami   | with exterior clear panel, worst case mounting  | Heat pump / AC | 6855    | kWh          | 54       | kWh         | 79.3   | MBtu   | 3.6%                    |
| 1            | FL Miami   | with exterior low-e panel, worst case mounting  | Heat pump / AC | 6554    | kWh          | 48       | kWh         | 75.8   | MBtu   | 7.9%                    |
| 1            | FL Miami   | with exterior solar-E panel, worst case mountin | Heat pump / AC | 6068    | kWh          | 55       | kWh         | 70.3   | MBtu   | 14.5%                   |

| Climate | Location   | Window   | <b>Cooling Cost</b> | <b>Heating Cost</b> | Total Cost | Energy cost | % energy     | Simple  | Payback   |
|---------|------------|--|---------------------|---------------------|------------|-------------|--------------|---------|-----------|
| Zone    |            |  | (\$)                | (\$)                | (\$)       | savings     | cost savings | payback | for low-e |
| 2       | TX Houston | Wood frame, single pane                          | 543.95              | 210.43              | 754.38     |             |              |         |           |
| 2       | TX Houston | with exterior clear panel                        | 490.49              | 156.2               | 646.69     | \$107.69    | 14.3%        | 21.0    |           |
| 2       | TX Houston | with interior clear panel                        | 488.07              | 153.56              | 641.63     | \$112.75    | 14.9%        | 22.3    |           |
| 2       | TX Houston | with exterior low-e panel                        | 466.95              | 144.43              | 611.38     | \$143.00    | 19.0%        | 17.6    | 7.2       |
| 2       | TX Houston | with interior low-e panel                        | 480.81              | 136.73              | 617.54     | \$136.84    | 18.1%        | 16.5    | 10.6      |
| 2       | TX Houston | with exterior solar-E panel                      | 422.29              | 154.44              | 576.73     | \$177.65    | 23.5%        | 14.1    | 3.6       |
| 2       | TX Houston | Wood frame, double pane                          | 511.06              | 168.3               | 679.36     |             |              |         |           |
| 2       | TX Houston | with exterior clear panel                        | 481.58              | 153.67              | 635.25     | \$44.11     | 6.5%         | 51.2    |           |
| 2       | TX Houston | with interior clear panel                        | 485.65              | 150.48              | 636.13     | \$43.23     | 6.4%         | 58.1    |           |
| 2       | TX Houston | with exterior low-e panel                        | 458.15              | 144.21              | 602.36     | \$77.00     | 11.3%        | 32.6    | 7.8       |
| 2       | TX Houston | with interior low-e panel                        | 474.87              | 137.72              | 612.59     | \$66.77     | 9.8%         | 33.8    | 10.8      |
| 2       | TX Houston | with exterior solar-E panel                      | 416.13              | 153.67              | 569.8      | \$109.56    | 16.1%        | 22.9    | 3.9       |
| 2       | TX Houston | Metal frame, double pane                         | 504.79              | 189.53              | 694.32     |             |              |         |           |
| 2       | TX Houston | with exterior clear panel                        | 490.27              | 162.25              | 652.52     | \$41.80     | 6.0%         | 54.0    |           |
| 2       | TX Houston | with interior clear panel                        | 484.11              | 158.4               | 642.51     | \$51.81     | 7.5%         | 48.5    |           |
| 2       | TX Houston | with exterior low-e panel                        | 466.07              | 149.16              | 615.23     | \$79.09     | 11.4%        | 31.8    | 6.8       |
| 2       | TX Houston | with interior low-e panel                        | 471.9               | 143.77              | 615.67     | \$78.65     | 11.3%        | 28.7    | 9.5       |
| 2       | TX Houston | with exterior solar-E panel                      | 422.4               | 158.73              | 581.13     | \$113.19    | 16.3%        | 22.2    | 3.6       |
| 2       | TX Houston | with exterior clear panel, worst case mounting   | 485.32              | 172.48              | 657.8      | \$36.52     | 5.3%         | 61.8    |           |
| 2       | TX Houston | with exterior low-e panel, worst case mounting   | 461.67              | 164.67              | 626.34     | \$67.98     | 9.8%         | 36.9    |           |
| 2       | TX Houston | with exterior solar-E panel, worst case mounting | 424.93              | 173.36              | 598.29     | \$96.03     | 13.8%        | 26.2    |           |
| 1       | FL Miami   | Wood frame, single pane                          | 874.12              | 9.09                | 883.21     |             |              |         |           |
| 1       | FL Miami   | with exterior clear panel                        | 795.8               | 4.95                | 800.75     | \$82.46     | 9.3%         | 27.4    |           |
| 1       | FL Miami   | with interior clear panel                        | 792.35              | 4.72                | 797.07     | \$86.14     | 9.8%         | 29.2    |           |
| 1       | FL Miami   | with exterior low-e panel                        | 761.88              | 4.14                | 766.02     | \$117.19    | 13.3%        | 21.4    | 7.3       |
| 1       | FL Miami   | with interior low-e panel                        | 781.66              | 3.68                | 785.34     | \$97.87     | 11.1%        | 23.1    | 21.7      |
| 1       | FL Miami   | with exterior solar-E panel                      | 695.87              | 4.72                | 700.59     | \$182.62    | 20.7%        | 13.8    | 2.5       |
| 1       | FL Miami   | Wood frame, double pane                          | 827.2               | 5.75                | 832.95     |             |              |         |           |
| 1       | FL Miami   | with exterior clear panel                        | 783.5               | 4.83                | 788.33     | \$44.62     | 5.4%         | 50.6    |           |
| 1       | FL Miami   | with interior clear panel                        | 789.13              | 4.6                 | 793.73     | \$39.22     | 4.7%         | 64.0    |           |
| 1       | FL Miami   | with exterior low-e panel                        | 749.46              | 4.03                | 753.49     | \$79.46     | 9.5%         | 31.6    | 7.3       |
| 1       | FL Miami   | with interior low-e panel                        | 773.26              | 3.8                 | 777.06     | \$55.89     | 6.7%         | 40.4    | 15.3      |
| 1       | FL Miami   | with exterior solar-E panel                      | 686.78              | 4.72                | 691.5      | \$141.45    | 17.0%        | 17.8    | 2.6       |
| 1       | FL Miami   | Metal frame, double pane                         | 816.5               | 7.48                | 823.98     |             |              |         |           |
| 1       | FL Miami   | with exterior clear panel                        | 795.92              | 5.41                | 801.33     | \$22.65     | 2.7%         | 99.6    |           |
| 1       | FL Miami   | with interior clear panel                        | 786.83              | 5.06                | 791.89     | \$32.09     | 3.9%         | 78.3    |           |
| 1       | FL Miami   | with exterior low-e panel                        | 760.5               | 4.37                | 764.87     | \$59.11     | 7.2%         | 42.5    | 7.0       |
| 1       | FL Miami   | with interior low-e panel                        | 769.35              | 4.14                | 773.49     | \$50.49     | 6.1%         | 44.7    | 13.9      |
| ĺ       | FL Miami   | with exterior solar-E panel                      | 695.98              | 5.06                | 701.04     | \$122.94    | 14.9%        | 20.4    | 2.5       |
| l î     | FL Miami   | with exterior clear panel, worst case mounting   | 788.33              | 6.21                | 794.54     | \$29.44     | 3.6%         | 76.7    |           |
| 1       | FL Miami   | with exterior low-e panel, worst case mounting   | 753.71              | 5.52                | 759.23     | \$64.75     | 7.9%         | 38.8    |           |
| 1       | FL Miami   | with exterior solar-E panel, worst case mounting | 697.82              | 6.33                | 704.15     | \$119.83    | 14.5%        | 21.0    |           |

Larger, Newer Home (2-story, 2800 ft<sup>2</sup>)

| Climate Zone | Location     | Window   | HVAC         | Whole H | louse Cooling | Whole Ho | use Heating | Source | Energy | % source energy savings |
|--------------|--------------|--|--------------|---------|---------------|----------|-------------|--------|--------|-------------------------|
| 8            | AK Fairbanks | Wood frame, single pane                        | Furnace / AC | 137     | kWh           | 247.8    | MBtu        | 272.2  | MBtu   |                         |
| 8            | AK Fairbanks | with exterior clear panel                      | Furnace / AC | 117     | kWh           | 166.7    | MBtu        | 183.4  | MBtu   | 32.6%                   |
| 8            | AK Fairbanks | with interior clear panel                      | Furnace / AC | 119     | kWh           | 162.2    | MBtu        | 178.5  | MBtu   | 34.4%                   |
| 8            | AK Fairbanks | with exterior low-e panel                      | Furnace / AC | 98      | kWh           | 149.1    | MBtu        | 163.9  | MBtu   | 39.8%                   |
| 8            | AK Fairbanks | with interior low-e panel                      | Furnace / AC | 113     | kWh           | 141.2    | MBtu        | 155.5  | MBtu   | 42.9%                   |
| 8            | AK Fairbanks | Wood frame, double pane                        | Furnace / AC | 129     | kWh           | 185.7    | MBtu        | 204.3  | MBtu   |                         |
| 8            | AK Fairbanks | with exterior clear panel                      | Furnace / AC | 108     | kWh           | 160.8    | MBtu        | 176.8  | MBtu   | 13.4%                   |
| 8            | AK Fairbanks | with interior clear panel                      | Furnace / AC | 115     | kWh           | 156.2    | MBtu        | 171.9  | MBtu   | 15.8%                   |
| 8            | AK Fairbanks | with exterior low-e panel                      | Furnace / AC | 90      | kWh           | 146.8    | MBtu        | 161.3  | MBtu   | 21.0%                   |
| 8            | AK Fairbanks | with interior low-e panel                      | Furnace / AC | 106     | kWh           | 141      | MBtu        | 155.2  | MBtu   | 24.0%                   |
| 8            | AK Fairbanks | Metal frame, double pane                       | Furnace / AC | 118     | kWh           | 212.5    | MBtu        | 233.4  | MBtu   |                         |
| 8            | AK Fairbanks | with exterior clear panel                      | Furnace / AC | 112     | kWh           | 172.6    | MBtu        | 189.8  | MBtu   | 18.7%                   |
| 8            | AK Fairbanks | with interior clear panel                      | Furnace / AC | 110     | kWh           | 167.2    | MBtu        | 183.8  | MBtu   | 21.2%                   |
| 8            | AK Fairbanks | with exterior low-e panel                      | Furnace / AC | 95      | kWh           | 153.9    | MBtu        | 169.1  | MBtu   | 27.5%                   |
| 8            | AK Fairbanks | with interior low-e panel                      | Furnace / AC | 102     | kWh           | 148.7    | MBtu        | 163.6  | MBtu   | 29.9%                   |
| 8            | AK Fairbanks | with exterior clear panel, worst case mounting | Furnace / AC | 108     | kWh           | 185.7    | MBtu        | 204.0  | MBtu   | 12.6%                   |
| 8            | AK Fairbanks | with exterior low-e panel, worst case mounting | Furnace / AC | 92      | kWh           | 173.9    | MBtu        | 191.0  | MBtu   | 18.2%                   |
| 7            | AK Anchorage | Wood frame, single pane                        | Furnace / AC | 24      | kWh           | 166.7    | MBtu        | 182.3  | MBtu   |                         |
| 7            | AK Anchorage | with exterior clear panel                      | Furnace / AC | 18      | kWh           | 105.8    | MBtu        | 115.7  | MBtu   | 36.5%                   |
| 7            | AK Anchorage | with interior clear panel                      | Furnace / AC | 22      | kWh           | 102.7    | MBtu        | 112.4  | MBtu   | 38.3%                   |
| 7            | AK Anchorage | with exterior low-e panel                      | Furnace / AC | 14      | kWh           | 92.2     | MBtu        | 100.8  | MBtu   | 44.7%                   |
| 7            | AK Anchorage | with interior low-e panel                      | Furnace / AC | 19      | kWh           | 86.5     | MBtu        | 94.7   | MBtu   | 48.1%                   |
| 7            | AK Anchorage | Wood frame, double pane                        | Furnace / AC | 24      | kWh           | 119.6    | MBtu        | 130.9  | MBtu   |                         |
| 7            | AK Anchorage | with exterior clear panel                      | Furnace / AC | 16      | kWh           | 101.9    | MBtu        | 111.5  | MBtu   | 14.8%                   |
| 7            | AK Anchorage | with interior clear panel                      | Furnace / AC | 19      | kWh           | 98.7     | MBtu        | 108.0  | MBtu   | 17.5%                   |
| 7            | AK Anchorage | with exterior low-e panel                      | Furnace / AC | 14      | kWh           | 90.7     | MBtu        | 99.2   | MBtu   | 24.2%                   |
| 7            | AK Anchorage | with interior low-e panel                      | Furnace / AC | 16      | kWh           | 86.5     | MBtu        | 94.6   | MBtu   | 27.7%                   |
| 7            | AK Anchorage | Metal frame, double pane                       | Furnace / AC | 17      | kWh           | 141.3    | MBtu        | 154.5  | MBtu   |                         |
| 7            | AK Anchorage | with exterior clear panel                      | Furnace / AC | 17      | kWh           | 111      | MBtu        | 121.4  | MBtu   | 21.4%                   |
| 7            | AK Anchorage | with interior clear panel                      | Furnace / AC | 16      | kWh           | 106.9    | MBtu        | 116.9  | MBtu   | 24.3%                   |
| 7            | AK Anchorage | with exterior low-e panel                      | Furnace / AC | 14      | kWh           | 96       | MBtu        | 105.0  | MBtu   | 32.0%                   |
| 7            | AK Anchorage | with interior low-e panel                      | Furnace / AC | 15      | kWh           | 92.2     | MBtu        | 100.9  | MBtu   | 34.7%                   |
| 7            | AK Anchorage | with exterior clear panel, worst case mounting | Furnace / AC | 16      | kWh           | 121.4    | MBtu        | 132.8  | MBtu   | 14.1%                   |
| 7            | AK Anchorage | with exterior low-e panel, worst case mounting | Furnace / AC | 12      | kWh           | 111.8    | MBtu        | 122.2  | MBtu   | 20.9%                   |

| Climate<br>Zone | Location     | Window   | Cooling<br>Cost (\$) | Heating Cost (\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|--------------|--|----------------------|-------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 8               | AK Fairbanks | Wood frame, single pane                        | 12.82                | 2051.88           | 2076.27         |                     |                       |                   |                      |
| 8               | AK Fairbanks | with exterior clear panel                      | 10.5                 | 1380.33           | 1401.16         | \$675.11            | 32.5%                 | 3.3               |                      |
| 8               | AK Fairbanks | with interior clear panel                      | 10.5                 | 1342.88           | 1364.06         | \$712.21            | 34.3%                 | 3.2               |                      |
| 8               | AK Fairbanks | with exterior low-e panel                      | 8.01                 | 1234.92           | 1252.36         | \$823.91            | 39.7%                 | 3.0               | 1.7                  |
| 8               | AK Fairbanks | with interior low-e panel                      | 9.97                 | 1168.9            | 1189.01         | \$887.26            | 42.7%                 | 2.8               | 1.5                  |
| 8               | AK Fairbanks | Wood frame, double pane                        | 11.75                | 1537.83           | 1560.79         |                     |                       |                   |                      |
| 8               | AK Fairbanks | with exterior clear panel                      | 9.43                 | 1331.07           | 1350.29         | \$210.50            | 13.5%                 | 10.7              |                      |
| 8               | AK Fairbanks | with interior clear panel                      | 10.32                | 1293.38           | 1313.85         | \$246.94            | 15.8%                 | 9.1               |                      |
| 8               | AK Fairbanks | with exterior low-e panel                      | 7.12                 | 1215.31           | 1231.33         | \$329.46            | 21.1%                 | 7.6               | 2.1                  |
| 8               | AK Fairbanks | with interior low-e panel                      | 9.26                 | 1167.36           | 1186.23         | \$374.56            | 24.0%                 | 6.7               | 2.0                  |
| 8               | AK Fairbanks | Metal frame, double pane                       | 10.32                | 1759.86           | 1780.86         |                     |                       |                   |                      |
| 8               | AK Fairbanks | with exterior clear panel                      | 10.15                | 1429.48           | 1449.42         | \$331.44            | 18.6%                 | 6.8               |                      |
| 8               | AK Fairbanks | with interior clear panel                      | 9.79                 | 1384.13           | 1403.71         | \$377.15            | 21.2%                 | 6.0               |                      |
| 8               | AK Fairbanks | with exterior low-e panel                      | 7.83                 | 1274.35           | 1291.26         | \$489.60            | 27.5%                 | 5.1               | 1.6                  |
| 8               | AK Fairbanks | with interior low-e panel                      | 8.72                 | 1231.48           | 1249.64         | \$531.22            | 29.8%                 | 4.7               | 1.7                  |
| 8               | AK Fairbanks | with exterior clear panel, worst case mounting | 9.26                 | 1537.46           | 1556.68         | \$224.18            | 12.6%                 | 10.1              |                      |
| 8               | AK Fairbanks | with exterior low-e panel, worst case mounting | 6.94                 | 1440.04           | 1456.42         | \$324.44            | 18.2%                 | 7.7               |                      |
| 7               | AK Anchorage | Wood frame, single pane                        | 2.14                 | 1380.68           | 1384.95         |                     |                       |                   |                      |
| 7               | AK Anchorage | with exterior clear panel                      | 1.78                 | 876.35            | 879.55          | \$505.40            | 36.5%                 | 4.5               |                      |
| 7               | AK Anchorage | with interior clear panel                      | 1.78                 | 850.54            | 854.46          | \$530.49            | 38.3%                 | 4.3               |                      |
| 7               | AK Anchorage | with exterior low-e panel                      | 1.25                 | 763.71            | 766.2           | \$618.75            | 44.7%                 | 4.1               | 2.2                  |
| 7               | AK Anchorage | with interior low-e panel                      | 1.6                  | 716.5             | 719.88          | \$665.07            | 48.0%                 | 3.8               | 1.9                  |
| 7               | AK Anchorage | Wood frame, double pane                        | 1.96                 | 990.34            | 994.61          |                     |                       |                   |                      |
| 7               | AK Anchorage | with exterior clear panel                      | 1.6                  | 843.71            | 846.56          | \$148.05            | 14.9%                 | 15.2              |                      |
| 7               | AK Anchorage | with interior clear panel                      | 1.6                  | 817.57            | 820.95          | \$173.66            | 17.5%                 | 13.0              |                      |
| 7               | AK Anchorage | with exterior low-e panel                      | 1.25                 | 750.58            | 753.07          | \$241.54            | 24.3%                 | 10.4              | 2.7                  |
| 7               | AK Anchorage | with interior low-e panel                      | 1.6                  | 716.24            | 719.09          | \$275.52            | 27.7%                 | 9.1               | 2.5                  |
| 7               | AK Anchorage | Metal frame, double pane                       | 1.6                  | 1169.81           | 1172.84         |                     |                       |                   |                      |
| 7               | AK Anchorage | with exterior clear panel                      | 1.6                  | 918.81            | 921.84          | \$251.00            | 21.4%                 | 9.0               |                      |
| 7               | AK Anchorage | with interior clear panel                      | 1.6                  | 885.41            | 888.26          | \$284.58            | 24.3%                 | 7.9               |                      |
| 7               | AK Anchorage | with exterior low-e panel                      | 1.25                 | 795.1             | 797.59          | \$375.25            | 32.0%                 | 6.7               | 2.1                  |
| 7               | AK Anchorage | with interior low-e panel                      | 1.42                 | 763.37            | 766.04          | \$406.80            | 34.7%                 | 6.2               | 2.1                  |
| 7               | AK Anchorage | with exterior clear panel, worst case mounting | 1.6                  | 1005.06           | 1007.91         | \$164.93            | 14.1%                 | 13.7              |                      |
| 7               | AK Anchorage | with exterior low-e panel, worst case mounting | 1.07                 | 925.74            | 927.88          | \$244.96            | 20.9%                 | 10.3              |                      |

| Climate Zon | eLocation      | Window   | HVAC         | Whole H | ouse Cooling | Whole Ho | use Heating | Source | Energy | % source energy savings |
|-------------|----------------|--|--------------|---------|--------------|----------|-------------|--------|--------|-------------------------|
| 7           | MN Duluth      | Wood frame, single pane                        | Furnace / AC | 337     | kWh          | 175.2    | MBtu        | 195.2  | MBtu   |                         |
| 7           | MN Duluth      | with exterior clear panel                      | Furnace / AC | 319     | kWh          | 106.6    | MBtu        | 120.1  | MBtu   | 38.5%                   |
| 7           | MN Duluth      | with interior clear panel                      | Furnace / AC | 322     | kWh          | 103      | MBtu        | 116.2  | MBtu   | 40.5%                   |
| 7           | MN Duluth      | with exterior low-e panel                      | Furnace / AC | 289     | kWh          | 93.2     | MBtu        | 105.1  | MBtu   | 46.2%                   |
| 7           | MN Duluth      | with interior low-e panel                      | Furnace / AC | 331     | kWh          | 86.1     | MBtu        | 97.8   | MBtu   | 49.9%                   |
| 7           | MN Duluth      | Wood frame, double pane                        | Furnace / AC | 331     | kWh          | 121.6    | MBtu        | 136.6  | MBtu   |                         |
| 7           | MN Duluth      | with exterior clear panel                      | Furnace / AC | 301     | kWh          | 102.6    | MBtu        | 115.5  | MBtu   | 15.4%                   |
| 7           | MN Duluth      | with interior clear panel                      | Furnace / AC | 319     | kWh          | 98.7     | MBtu        | 111.4  | MBtu   | 18.4%                   |
| 7           | MN Duluth      | with exterior low-e panel                      | Furnace / AC | 280     | kWh          | 91.9     | MBtu        | 103.6  | MBtu   | 24.2%                   |
| 7           | MN Duluth      | with interior low-e panel                      | Furnace / AC | 318     | kWh          | 86.4     | MBtu        | 98.0   | MBtu   | 28.3%                   |
| 7           | MN Duluth      | Metal frame, double pane                       | Furnace / AC | 296     | kWh          | 145.2    | MBtu        | 162.0  | MBtu   |                         |
| 7           | MN Duluth      | with exterior clear panel                      | Furnace / AC | 307     | kWh          | 112      | MBtu        | 125.8  | MBtu   | 22.3%                   |
| 7           | MN Duluth      | with interior clear panel                      | Furnace / AC | 297     | kWh          | 107.6    | MBtu        | 120.9  | MBtu   | 25.3%                   |
| 7           | MN Duluth      | with exterior low-e panel                      | Furnace / AC | 286     | kWh          | 97.4     | MBtu        | 109.6  | MBtu   | 32.3%                   |
| 7           | MN Duluth      | with interior low-e panel                      | Furnace / AC | 307     | kWh          | 92.7     | MBtu        | 104.8  | MBtu   | 35.3%                   |
| 7           | MN Duluth      | with exterior clear panel, worst case mounting | Furnace / AC | 284     | kWh          | 123.4    | MBtu        | 138.0  | MBtu   | 14.8%                   |
| 7           | MN Duluth      | with exterior low-e panel, worst case mounting | Furnace / AC | 258     | kWh          | 114.4    | MBtu        | 127.9  | MBtu   | 21.0%                   |
| 6           | MN Minneapolis | Wood frame, single pane                        | Furnace / AC | 1161    | kWh          | 137.4    | MBtu        | 163.4  | MBtu   |                         |
| 6           | MN Minneapolis | with exterior clear panel                      | Furnace / AC | 1064    | kWh          | 84       | MBtu        | 103.9  | MBtu   | 36.4%                   |
| 6           | MN Minneapolis | with interior clear panel                      | Furnace / AC | 1067    | kWh          | 81.2     | MBtu        | 100.9  | MBtu   | 38.2%                   |
| 6           | MN Minneapolis | with exterior low-e panel                      | Furnace / AC | 987     | kWh          | 73.6     | MBtu        | 91.7   | MBtu   | 43.9%                   |
| 6           | MN Minneapolis | with interior low-e panel                      | Furnace / AC | 1064    | kWh          | 68.1     | MBtu        | 86.6   | MBtu   | 47.0%                   |
| 6           | MN Minneapolis | Wood frame, double pane                        | Furnace / AC | 1116    | kWh          | 95.7     | MBtu        | 117.3  | MBtu   |                         |
| 6           | MN Minneapolis | with exterior clear panel                      | Furnace / AC | 1025    | kWh          | 81       | MBtu        | 100.2  | MBtu   | 14.6%                   |
| 6           | MN Minneapolis | with interior clear panel                      | Furnace / AC | 1056    | kWh          | 77.9     | MBtu        | 97.2   | MBtu   | 17.2%                   |
| 6           | MN Minneapolis | with exterior low-e panel                      | Furnace / AC | 948     | kWh          | 72.7     | MBtu        | 90.3   | MBtu   | 23.1%                   |
| 6           | MN Minneapolis | with interior low-e panel                      | Furnace / AC | 1030    | kWh          | 68.3     | MBtu        | 86.4   | MBtu   | 26.3%                   |
| 6           | MN Minneapolis | Metal frame, double pane                       | Furnace / AC | 1040    | kWh          | 114.2    | MBtu        | 136.6  | MBtu   |                         |
| 6           | MN Minneapolis | with exterior clear panel                      | Furnace / AC | 1043    | kWh          | 88.3     | MBtu        | 108.4  | MBtu   | 20.7%                   |
| 6           | MN Minneapolis | with interior clear panel                      | Furnace / AC | 1031    | kWh          | 84.9     | MBtu        | 104.5  | MBtu   | 23.5%                   |
| 6           | MN Minneapolis | with exterior low-e panel                      | Furnace / AC | 971     | kWh          | 77       | MBtu        | 95.2   | MBtu   | 30.3%                   |
| 6           | MN Minneapolis | with interior low-e panel                      | Furnace / AC | 1005    | kWh          | 73.2     | MBtu        | 91.5   | MBtu   | 33.1%                   |
| 6           | MN Minneapolis | with exterior clear panel, worst case mounting | Furnace / AC | 994     | kWh          | 97.2     | MBtu        | 117.6  | MBtu   | 14.0%                   |
| 6           | MN Minneapolis | with exterior low-e panel, worst case mounting | Furnace / AC | 914     | kWh          | 90.2     | MBtu        | 109.0  | MBtu   | 20.2%                   |

| Climate<br>Zone | Location                | Window   | Cooling<br>Cost (\$) | Heating Cost (\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|-------------------------|--|----------------------|-------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 7               | MN Duluth               | Wood frame, single pane                        | 22.06                | 1365.1            | 1403.42         |                     |                       |                   |                      |
| 7               | MN Duluth               | with exterior clear panel                      | 18.31                | 830.25            | 866.52          | \$536.90            | 38.3%                 | 4.2               |                      |
| 7               | MN Duluth               | with interior clear panel                      | 19.04                | 802.48            | 839.19          | \$564.23            | 40.2%                 | 4.0               |                      |
| 7               | MN Duluth               | with exterior low-e panel                      | 15.62                | 725.84            | 758.79          | \$644.63            | 45.9%                 | 3.9               | 2.4                  |
| 7               | MN Duluth               | with interior low-e panel                      | 18.13                | 670.7             | 708.43          | \$694.99            | 49.5%                 | 3.6               | 2.0                  |
| 7               | MN Duluth               | Wood frame, double pane                        | 20.63                | 947.44            | 985.17          |                     |                       |                   |                      |
| 7               | MN Duluth               | with exterior clear panel                      | 16.76                | 799.19            | 833.5           | \$151.67            | 15.4%                 | 14.9              |                      |
| 7               | MN Duluth               | with interior clear panel                      | 17.9                 | 768.65            | 805.02          | \$180.15            | 18.3%                 | 12.5              |                      |
| 7               | MN Duluth               | with exterior low-e panel                      | 14.59                | 716.17            | 748.09          | \$237.08            | 24.1%                 | 10.6              | 3.0                  |
| 7               | MN Duluth               | with interior low-e panel                      | 16.76                | 672.78            | 709.03          | \$276.14            | 28.0%                 | 9.1               | 2.7                  |
| 7               | MN Duluth               | Metal frame, double pane                       | 18.13                | 1131.08           | 1164.82         |                     |                       |                   |                      |
| 7               | MN Duluth               | with exterior clear panel                      | 17.56                | 872.81            | 907.81          | \$257.01            | 22.1%                 | 8.8               |                      |
| 7               | MN Duluth               | with interior clear panel                      | 17.1                 | 838.43            | 872.29          | \$292.53            | 25.1%                 | 7.7               |                      |
| 7               | MN Duluth               | with exterior low-e panel                      | 15.73                | 758.98            | 791.58          | \$373.24            | 32.0%                 | 6.7               | 2.2                  |
| 7               | MN Duluth               | with interior low-e panel                      | 16.3                 | 721.78            | 756.78          | \$408.04            | 35.0%                 | 6.2               | 2.2                  |
| 7               | MN Duluth               | with exterior clear panel, worst case mounting | 16.76                | 961.08            | 993.46          | \$171.36            | 14.7%                 | 13.2              |                      |
| 7               | MN Duluth               | with exterior low-e panel, worst case mounting | 14.14                | 891.18            | 920.59          | \$244.23            | 21.0%                 | 10.3              |                      |
| 6               | MN<br>Minneapolis<br>MN | Wood frame, single pane                        | 90.96                | 1070.4            | 1202.41         |                     |                       |                   |                      |
| 6               | Minneapolis<br>MN       | with exterior clear panel                      | 78.57                | 654.27            | 775.25          | \$427.16            | 35.5%                 | 5.3               |                      |
| 6               | Minneapolis<br>MN       | with interior clear panel                      | 78.66                | 632.17            | 753.81          | \$448.60            | 37.3%                 | 5.0               |                      |
| 6               | Minneapolis<br>MN       | with exterior low-e panel                      | 70.57                | 573.53            | 686.05          | \$516.36            | 42.9%                 | 4.9               | 2.9                  |
| 6               | Minneapolis             | with interior low-e panel                      | 76.49                | 530.44            | 651.74          | \$550.67            | 45.8%                 | 4.6               | 2.5                  |
| 6               | MN<br>Minneapolis       | Wood frame, double pane                        | 84.25                | 745.6             | 872.82          |                     |                       |                   |                      |
| 6               | MN<br>Minneapolis<br>MN | with exterior clear panel                      | 75.01                | 630.73            | 747.58          | \$125.24            | 14.3%                 | 18.0              |                      |
| 6               | Minneapolis<br>MN       | with interior clear panel                      | 77.41                | 607               | 727.38          | \$145.44            | 16.7%                 | 15.5              |                      |
| 6               | Minneapolis<br>MN       | with exterior low-e panel                      | 67.26                | 566.4             | 674.47          | \$198.35            | 22.7%                 | 12.7              | 3.5                  |
| 6               | Minneapolis             | with interior low-e panel                      | 73.87                | 532.22            | 649.64          | \$223.18            | 25.6%                 | 11.3              | 3.3                  |
| 6               | MN<br>Minneapolis<br>MN | Metal frame, double pane                       | 79.8                 | 889.39            | 1007.95         |                     |                       |                   |                      |
| 6               | Minneapolis<br>MN       | with exterior clear panel                      | 77.75                | 688.02            | 806.92          | \$201.03            | 19.9%                 | 11.2              |                      |
| 6               | Minneapolis<br>MN       | with interior clear panel                      | 76.27                | 661               | 778.53          | \$229.42            | 22.8%                 | 9.8               |                      |
| 6               | Minneapolis             | with exterior low-e panel                      | 69.54                | 599.47            | 710.16          | \$297.79            | 29.5%                 | 8.4               | 2.6                  |

| 6 | MN<br>Minneapolis<br>MN | with interior low-e panel                      | 72.39 | 570.05 | 684.62 | \$323.33 | 32.1% | 7.8  | 2.7 |
|---|-------------------------|--|-------|--------|--------|----------|-------|------|-----|
| 6 | Minneapolis<br>MN       | with exterior clear panel, worst case mounting | 74.78 | 757.01 | 870.33 | \$137.62 | 13.7% | 16.4 | 1   |
| 6 | Minneapolis             | with exterior low-e panel, worst case mounting | 66.46 | 702.95 | 807.15 | \$200.80 | 19.9% | 12.5 |     |

| Climate Zone | Location      | Window   | HVAC         | Whole H | ouse Cooling | Whole Ho | use Heating | Source | Energy | % source energy savings |
|--------------|---------------|--|--------------|---------|--------------|----------|-------------|--------|--------|-------------------------|
| 6            | VT Burlington | Wood frame, single pane                        | Furnace / AC | 714     | kWh          | 128.1    | MBtu        | 148.1  | MBtu   |                         |
| 6            | VT Burlington | with exterior clear panel                      | Furnace / AC | 675     | kWh          | 78.7     | MBtu        | 93.7   | MBtu   | 36.7%                   |
| 6            | VT Burlington | with interior clear panel                      | Furnace / AC | 679     | kWh          | 76.1     | MBtu        | 90.9   | MBtu   | 38.6%                   |
| 6            | VT Burlington | with exterior low-e panel                      | Furnace / AC | 628     | kWh          | 68.7     | MBtu        | 82.2   | MBtu   | 44.5%                   |
| 6            | VT Burlington | with interior low-e panel                      | Furnace / AC | 681     | kWh          | 63.5     | MBtu        | 77.2   | MBtu   | 47.9%                   |
| 6            | VT Burlington | Wood frame, double pane                        | Furnace / AC | 703     | kWh          | 89.5     | MBtu        | 105.8  | MBtu   |                         |
| 6            | VT Burlington | with exterior clear panel                      | Furnace / AC | 648     | kWh          | 75.9     | MBtu        | 90.3   | MBtu   | 14.6%                   |
| 6            | VT Burlington | with interior clear panel                      | Furnace / AC | 672     | kWh          | 73.1     | MBtu        | 87.5   | MBtu   | 17.3%                   |
| 6            | VT Burlington | with exterior low-e panel                      | Furnace / AC | 605     | kWh          | 67.8     | MBtu        | 81.0   | MBtu   | 23.5%                   |
| 6            | VT Burlington | with interior low-e panel                      | Furnace / AC | 659     | kWh          | 63.7     | MBtu        | 77.1   | MBtu   | 27.1%                   |
| 6            | VT Burlington | Metal frame, double pane                       | Furnace / AC | 637     | kWh          | 106.8    | MBtu        | 123.9  | MBtu   |                         |
| 6            | VT Burlington | with exterior clear panel                      | Furnace / AC | 660     | kWh          | 82.9     | MBtu        | 98.1   | MBtu   | 20.8%                   |
| 6            | VT Burlington | with interior clear panel                      | Furnace / AC | 655     | kWh          | 79.7     | MBtu        | 94.6   | MBtu   | 23.7%                   |
| 6            | VT Burlington | with exterior low-e panel                      | Furnace / AC | 616     | kWh          | 71.8     | MBtu        | 85.5   | MBtu   | 31.0%                   |
| 6            | VT Burlington | with interior low-e panel                      | Furnace / AC | 639     | kWh          | 68.4     | MBtu        | 82.0   | MBtu   | 33.8%                   |
| 6            | VT Burlington | with exterior clear panel, worst case mounting | Furnace / AC | 622     | kWh          | 91.1     | MBtu        | 106.6  | MBtu   | 14.0%                   |
| 6            | VT Burlington | with exterior low-e panel, worst case mounting | Furnace / AC | 568     | kWh          | 84.3     | MBtu        | 98.6   | MBtu   | 20.5%                   |
| 5            | CO Denver     | Wood frame, single pane                        | Furnace / AC | 1078    | kWh          | 77.8     | MBtu        | 97.3   | MBtu   |                         |
| 5            | CO Denver     | with exterior clear panel                      | Furnace / AC | 983     | kWh          | 45.4     | MBtu        | 60.9   | MBtu   | 37.5%                   |
| 5            | CO Denver     | with interior clear panel                      | Furnace / AC | 989     | kWh          | 43.7     | MBtu        | 59.1   | MBtu   | 39.3%                   |
| 5            | CO Denver     | with exterior low-e panel                      | Furnace / AC | 886     | kWh          | 38.3     | MBtu        | 52.0   | MBtu   | 46.6%                   |
| 5            | CO Denver     | with interior low-e panel                      | Furnace / AC | 966     | kWh          | 34.2     | MBtu        | 48.4   | MBtu   | 50.2%                   |
| 5            | CO Denver     | Wood frame, double pane                        | Furnace / AC | 1040    | kWh          | 52.2     | MBtu        | 68.9   | MBtu   |                         |
| 5            | CO Denver     | with exterior clear panel                      | Furnace / AC | 942     | kWh          | 43.6     | MBtu        | 58.4   | MBtu   | 15.3%                   |
| 5            | CO Denver     | with interior clear panel                      | Furnace / AC | 973     | kWh          | 41.5     | MBtu        | 56.5   | MBtu   | 18.1%                   |
| 5            | CO Denver     | with exterior low-e panel                      | Furnace / AC | 847     | kWh          | 37.9     | MBtu        | 51.1   | MBtu   | 25.9%                   |
| 5            | CO Denver     | with interior low-e panel                      | Furnace / AC | 929     | kWh          | 34.6     | MBtu        | 48.4   | MBtu   | 29.7%                   |
| 5            | CO Denver     | Metal frame, double pane                       | Furnace / AC | 972     | kWh          | 65.9     | MBtu        | 83.1   | MBtu   |                         |
| 5            | CO Denver     | with exterior clear panel                      | Furnace / AC | 968     | kWh          | 48.8     | MBtu        | 64.4   | MBtu   | 22.5%                   |
| 5            | CO Denver     | with interior clear panel                      | Furnace / AC | 954     | kWh          | 46.7     | MBtu        | 62.0   | MBtu   | 25.5%                   |
| 5            | CO Denver     | with exterior low-e panel                      | Furnace / AC | 879     | kWh          | 40.8     | MBtu        | 54.6   | MBtu   | 34.3%                   |
| 5            | CO Denver     | with interior low-e panel                      | Furnace / AC | 917     | kWh          | 38.2     | MBtu        | 52.2   | MBtu   | 37.1%                   |
| 5            | CO Denver     | with exterior clear panel, worst case mounting | Furnace / AC | 925     | kWh          | 55.4     | MBtu        | 71.1   | MBtu   | 14.4%                   |
| 5            | CO Denver     | with exterior low-e panel, worst case mounting | Furnace / AC | 827     | kWh          | 50.6     | MBtu        | 64.8   | MBtu   | 22.1%                   |

| Climate<br>Zone | Location      | Window   | Cooling Cost (\$) | Heating Cost (\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|---------------|--|-------------------|-------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 6               | VT Burlington | Wood frame, single pane                        | 78.59             | 2093.85           | 2217.44         |                     |                       |                   |                      |
| 6               | VT Burlington | with exterior clear panel                      | 67.12             | 1286.71           | 1403.48         | \$813.96            | 36.7%                 | 2.8               |                      |
| 6               | VT Burlington | with interior clear panel                      | 67.3              | 1244.69           | 1362.16         | \$855.28            | 38.6%                 | 2.6               |                      |
| 6               | VT Burlington | with exterior low-e panel                      | 58.82             | 1122.74           | 1231.38         | \$986.06            | 44.5%                 | 2.5               | 1.5                  |
| 6               | VT Burlington | with interior low-e panel                      | 65.22             | 1038.39           | 1156.2          | \$1,061.24          | 47.9%                 | 2.4               | 1.2                  |
| 6               | VT Burlington | Wood frame, double pane                        | 72.31             | 1462.98           | 1584.6          |                     |                       |                   |                      |
| 6               | VT Burlington | with exterior clear panel                      | 63.49             | 1241.62           | 1353.72         | \$230.88            | 14.6%                 | 9.8               |                      |
| 6               | VT Burlington | with interior clear panel                      | 65.74             | 1195.59           | 1311.85         | \$272.75            | 17.2%                 | 8.3               |                      |
| 6               | VT Burlington | with exterior low-e panel                      | 55.36             | 1108.04           | 1212.7          | \$371.90            | 23.5%                 | 6.8               | 1.8                  |
| 6               | VT Burlington | with interior low-e panel                      | 62.63             | 1042.2            | 1156.21         | \$428.39            | 27.0%                 | 5.9               | 1.6                  |
| 6               | VT Burlington | Metal frame, double pane                       | 67.64             | 1747              | 1857.2          |                     |                       |                   |                      |
| 6               | VT Burlington | with exterior clear panel                      | 65.91             | 1355.06           | 1469.24         | \$387.96            | 20.9%                 | 5.8               |                      |
| 6               | VT Burlington | with interior clear panel                      | 64.36             | 1302.72           | 1416.03         | \$441.17            | 23.8%                 | 5.1               |                      |
| 6               | VT Burlington | with exterior low-e panel                      | 57.78             | 1174.34           | 1280.91         | \$576.29            | 31.0%                 | 4.4               | 1.4                  |
| 6               | VT Burlington | with interior low-e panel                      | 60.9              | 1117.91           | 1228.46         | \$628.74            | 33.9%                 | 4.0               | 1.4                  |
| 6               | VT Burlington | with exterior clear panel, worst case mounting | 62.8              | 1490.11           | 1597.72         | \$259.48            | 14.0%                 | 8.7               |                      |
| 6               | VT Burlington | with exterior low-e panel, worst case mounting | 54.84             | 1377.5            | 1475.76         | \$381.44            | 20.5%                 | 6.6               |                      |
| 5               | CO Denver     | Wood frame, single pane                        | 110.63            | 627.47            | 750.04          |                     |                       |                   |                      |
| 5               | CO Denver     | with exterior clear panel                      | 98.61             | 366.1             | 478.16          | \$271.88            | 36.2%                 | 8.3               |                      |
| 5               | CO Denver     | with interior clear panel                      | 98.84             | 352.27            | 465.02          | \$285.02            | 38.0%                 | 7.9               |                      |
| 5               | CO Denver     | with exterior low-e panel                      | 88.81             | 309.19            | 410.19          | \$339.85            | 45.3%                 | 7.4               | 3.8                  |
| 5               | CO Denver     | with interior low-e panel                      | 95.99             | 276.02            | 386.14          | \$363.90            | 48.5%                 | 6.9               | 3.2                  |
| 5               | CO Denver     | Wood frame, double pane                        | 104.54            | 421.57            | 540.13          |                     |                       |                   |                      |
| 5               | CO Denver     | with exterior clear panel                      | 94.28             | 352.01            | 459.4           | \$80.73             | 14.9%                 | 28.0              |                      |
| 5               | CO Denver     | with interior clear panel                      | 97.24             | 335.24            | 446.16          | \$93.97             | 17.4%                 | 24.0              |                      |
| 5               | CO Denver     | with exterior low-e panel                      | 84.93             | 305.96            | 402.52          | \$137.61            | 25.5%                 | 18.3              | 4.5                  |
| 5               | CO Denver     | with interior low-e panel                      | 92.68             | 278.94            | 384.85          | \$155.28            | 28.7%                 | 16.2              | 4.2                  |
| 5               | CO Denver     | Metal frame, double pane                       | 100.21            | 531.8             | 642.61          |                     |                       |                   |                      |
| 5               | CO Denver     | with exterior clear panel                      | 97.58             | 393.64            | 503.99          | \$138.62            | 21.6%                 | 16.3              |                      |
| 5               | CO Denver     | with interior clear panel                      | 95.87             | 376.75            | 485.51          | \$157.10            | 24.4%                 | 14.4              |                      |
| 5               | CO Denver     | with exterior low-e panel                      | 87.89             | 329.24            | 429.45          | \$213.16            | 33.2%                 | 11.8              | 3.4                  |
| 5               | CO Denver     | with interior low-e panel                      | 91.2              | 308.1             | 412.64          | \$229.97            | 35.8%                 | 10.9              | 3.5                  |
| 5               | CO Denver     | with exterior clear panel, worst case mounting | 94.62             | 446.82            | 552.27          | \$90.34             | 14.1%                 | 25.0              |                      |
| 5               | CO Denver     | with exterior low-e panel, worst case mounting | 85.04             | 408.47            | 502.75          | \$139.86            | 21.8%                 | 18.0              |                      |

| Climate Zone | Location   | Window   | HVAC         | Whole House Cooling Whole House Heating |     |       |      | Source | Energy | % source energy savings |
|--------------|------------|--|--------------|---|-----|-------|------|--------|--------|-------------------------|
| 5            | ID Boise   | Wood frame, single pane                        | Furnace / AC | 1348                                    | kWh | 84.3  | MBtu | 107.5  | MBtu   |                         |
| 5            | ID Boise   | with exterior clear panel                      | Furnace / AC | 1180                                    | kWh | 50.2  | MBtu | 68.4   | MBtu   | 36.4%                   |
| 5            | ID Boise   | with interior clear panel                      | Furnace / AC | 1183                                    | kWh | 48.5  | MBtu | 66.5   | MBtu   | 38.1%                   |
| 5            | ID Boise   | with exterior low-e panel                      | Furnace / AC | 1067                                    | kWh | 42.9  | MBtu | 59.1   | MBtu   | 45.0%                   |
| 5            | ID Boise   | with interior low-e panel                      | Furnace / AC | 1139                                    | kWh | 38.9  | MBtu | 55.6   | MBtu   | 48.3%                   |
| 5            | ID Boise   | Wood frame, double pane                        | Furnace / AC | 1258                                    | kWh | 57.6  | MBtu | 77.3   | MBtu   |                         |
| 5            | ID Boise   | with exterior clear panel                      | Furnace / AC | 1143                                    | kWh | 48.4  | MBtu | 66.0   | MBtu   | 14.7%                   |
| 5            | ID Boise   | with interior clear panel                      | Furnace / AC | 1165                                    | kWh | 46.4  | MBtu | 64.0   | MBtu   | 17.2%                   |
| 5            | ID Boise   | with exterior low-e panel                      | Furnace / AC | 1023                                    | kWh | 42.4  | MBtu | 58.0   | MBtu   | 24.9%                   |
| 5            | ID Boise   | with interior low-e panel                      | Furnace / AC | 1105                                    | kWh | 39.2  | MBtu | 55.5   | MBtu   | 28.3%                   |
| 5            | ID Boise   | Metal frame, double pane                       | Furnace / AC | 1218                                    | kWh | 71.2  | MBtu | 91.7   | MBtu   |                         |
| 5            | ID Boise   | with exterior clear panel                      | Furnace / AC | 1183                                    | kWh | 53.7  | MBtu | 72.2   | MBtu   | 21.3%                   |
| 5            | ID Boise   | with interior clear panel                      | Furnace / AC | 1163                                    | kWh | 51.5  | MBtu | 69.6   | MBtu   | 24.1%                   |
| 5            | ID Boise   | with exterior low-e panel                      | Furnace / AC | 1059                                    | kWh | 45.3  | MBtu | 61.6   | MBtu   | 32.8%                   |
| 5            | ID Boise   | with interior low-e panel                      | Furnace / AC | 1095                                    | kWh | 42.8  | MBtu | 59.3   | MBtu   | 35.3%                   |
| 5            | ID Boise   | with exterior clear panel, worst case mounting | Furnace / AC | 1152                                    | kWh | 60.2  | MBtu | 79.0   | MBtu   | 13.9%                   |
| 5            | ID Boise   | with exterior low-e panel, worst case mounting | Furnace / AC | 1041                                    | kWh | 55.1  | MBtu | 72.1   | MBtu   | 21.4%                   |
| 5            | IL Chicago | Wood frame, single pane                        | Furnace / AC | 1303                                    | kWh | 110.9 | MBtu | 136.1  | MBtu   |                         |
| 5            | IL Chicago | with exterior clear panel                      | Furnace / AC | 1207                                    | kWh | 67.1  | MBtu | 87.1   | MBtu   | 36.0%                   |
| 5            | IL Chicago | with interior clear panel                      | Furnace / AC | 1214                                    | kWh | 64.9  | MBtu | 84.8   | MBtu   | 37.7%                   |
| 5            | IL Chicago | with exterior low-e panel                      | Furnace / AC | 1126                                    | kWh | 58.4  | MBtu | 76.7   | MBtu   | 43.6%                   |
| 5            | IL Chicago | with interior low-e panel                      | Furnace / AC | 1219                                    | kWh | 53.8  | MBtu | 72.7   | MBtu   | 46.5%                   |
| 5            | IL Chicago | Wood frame, double pane                        | Furnace / AC | 1261                                    | kWh | 76.6  | MBtu | 98.1   | MBtu   |                         |
| 5            | IL Chicago | with exterior clear panel                      | Furnace / AC | 1162                                    | kWh | 64.9  | MBtu | 84.2   | MBtu   | 14.2%                   |
| 5            | IL Chicago | with interior clear panel                      | Furnace / AC | 1200                                    | kWh | 62.3  | MBtu | 81.8   | MBtu   | 16.6%                   |
| 5            | IL Chicago | with exterior low-e panel                      | Furnace / AC | 1078                                    | kWh | 57.7  | MBtu | 75.4   | MBtu   | 23.2%                   |
| 5            | IL Chicago | with interior low-e panel                      | Furnace / AC | 1183                                    | kWh | 54.1  | MBtu | 72.7   | MBtu   | 26.0%                   |
| 5            | IL Chicago | Metal frame, double pane                       | Furnace / AC | 1178                                    | kWh | 92.2  | MBtu | 114.2  | MBtu   |                         |
| 5            | IL Chicago | with exterior clear panel                      | Furnace / AC | 1180                                    | kWh | 71    | MBtu | 91.1   | MBtu   | 20.3%                   |
| 5            | IL Chicago | with interior clear panel                      | Furnace / AC | 1166                                    | kWh | 68.1  | MBtu | 87.8   | MBtu   | 23.2%                   |
| 5            | IL Chicago | with exterior low-e panel                      | Furnace / AC | 1102                                    | kWh | 61.2  | MBtu | 79.5   | MBtu   | 30.4%                   |
| 5            | IL Chicago | with interior low-e panel                      | Furnace / AC | 1151                                    | kWh | 58.1  | MBtu | 76.7   | MBtu   | 32.9%                   |
| 5            | IL Chicago | with exterior clear panel, worst case mounting | Furnace / AC | 1131                                    | kWh | 78.3  | MBtu | 98.5   | MBtu   | 13.8%                   |
| 5            | IL Chicago | with exterior low-e panel, worst case mounting | Furnace / AC | 1042                                    | kWh | 72.3  | MBtu | 90.9   | MBtu   | 20.4%                   |

| Climate<br>Zone | Location   | Window   | Cooling Cost (\$) | Heating Cost<br>(\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|------------|--|-------------------|----------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 5               | ID Boise   | Wood frame, single pane                        | 100.28            | 689.79               | 803.97          |                     |                       |                   |                      |
| 5               | ID Boise   | with exterior clear panel                      | 88.49             | 410.99               | 511.29          | \$292.68            | 36.4%                 | 7.7               |                      |
| 5               | ID Boise   | with interior clear panel                      | 88.57             | 396.41               | 496.97          | \$307.00            | 38.2%                 | 7.4               |                      |
| 5               | ID Boise   | with exterior low-e panel                      | 80.33             | 350.72               | 441.42          | \$362.55            | 45.1%                 | 6.9               | 3.6                  |
| 5               | ID Boise   | with interior low-e panel                      | 85.51             | 318.16               | 414.98          | \$388.99            | 48.4%                 | 6.5               | 3.1                  |
| 5               | ID Boise   | Wood frame, double pane                        | 93.59             | 471.19               | 578.12          |                     |                       |                   |                      |
| 5               | ID Boise   | with exterior clear panel                      | 85.26             | 396.21               | 493.37          | \$84.75             | 14.7%                 | 26.6              |                      |
| 5               | ID Boise   | with interior clear panel                      | 87.21             | 379.4                | 478.43          | \$99.69             | 17.2%                 | 22.6              |                      |
| 5               | ID Boise   | with exterior low-e panel                      | 76.93             | 346.46               | 433.42          | \$144.70            | 25.0%                 | 17.4              | 4.3                  |
| 5               | ID Boise   | with interior low-e panel                      | 83.05             | 320.57               | 414.5           | \$163.62            | 28.3%                 | 15.4              | 4.0                  |
| 5               | ID Boise   | Metal frame, double pane                       | 91.38             | 582.74               | 686.27          |                     |                       |                   |                      |
| 5               | ID Boise   | with exterior clear panel                      | 88.32             | 439.24               | 539.8           | \$146.47            | 21.3%                 | 15.4              |                      |
| 5               | ID Boise   | with interior clear panel                      | 86.79             | 420.92               | 519.78          | \$166.49            | 24.3%                 | 13.6              |                      |
| 5               | ID Boise   | with exterior low-e panel                      | 79.65             | 370.84               | 460.86          | \$225.41            | 32.8%                 | 11.1              | 3.2                  |
| 5               | ID Boise   | with interior low-e panel                      | 82.28             | 349.74               | 442.82          | \$243.45            | 35.5%                 | 10.3              | 3.3                  |
| 5               | ID Boise   | with exterior clear panel, worst case mounting | 86.45             | 492.62               | 590.54          | \$95.73             | 13.9%                 | 23.6              |                      |
| 5               | ID Boise   | with exterior low-e panel, worst case mounting | 78.12             | 450.54               | 539.03          | \$147.24            | 21.5%                 | 17.1              |                      |
| 5               | IL Chicago | Wood frame, single pane                        | 111.31            | 892.01               | 1040.16         |                     |                       |                   |                      |
| 5               | IL Chicago | with exterior clear panel                      | 98.27             | 539.75               | 677.35          | \$362.81            | 34.9%                 | 6.2               |                      |
| 5               | IL Chicago | with interior clear panel                      | 98.5              | 521.48               | 659.88          | \$380.28            | 36.6%                 | 5.9               |                      |
| 5               | IL Chicago | with exterior low-e panel                      | 89.72             | 469.75               | 598.11          | \$442.05            | 42.5%                 | 5.7               | 3.2                  |
| 5               | IL Chicago | with interior low-e panel                      | 96.56             | 432.79               | 571.76          | \$468.40            | 45.0%                 | 5.4               | 2.9                  |
| 5               | IL Chicago | Wood frame, double pane                        | 103.97            | 615.87               | 759.62          |                     |                       | -                 |                      |
| 5               | IL Chicago | with exterior clear panel                      | 94.73             | 521.4                | 653.87          | \$105.75            | 13.9%                 | 21.3              |                      |
| 5               | IL Chicago | with interior clear panel                      | 97.01             | 501.19               | 637.99          | \$121.63            | 16.0%                 | 18.6              |                      |
| 5               | IL Chicago | with exterior low-e panel                      | 85.5              | 464.11               | 587             | \$172.62            | 22.7%                 | 14.6              | 3.8                  |
| 5               | IL Chicago | with interior low-e panel                      | 93.48             | 434.76               | 569.62          | \$190.00            | 25.0%                 | 13.2              | 3.7                  |
| 5               | IL Chicago | Metal frame, double pane                       | 99.75             | 741.25               | 875.54          |                     |                       |                   |                      |
| 5               | IL Chicago | with exterior clear panel                      | 97.13             | 570.52               | 705.04          | \$170.50            | 19.5%                 | 13.2              |                      |
| 5               | IL Chicago | with interior clear panel                      | 95.99             | 547.66               | 680.58          | \$194.96            | 22.3%                 | 11.6              |                      |
| 5               | IL Chicago | with exterior low-e panel                      | 88.58             | 492.43               | 618.06          | \$257.48            | 29.4%                 | 9.8               | 2.9                  |
| 5               | IL Chicago | with interior low-e panel                      | 92                | 467.48               | 598.69          | \$276.85            | 31.6%                 | 9.1               | 3.1                  |
| 5               | IL Chicago | with exterior clear panel, worst case mounting | 94.28             | 629.46               | 758.39          | \$117.15            | 13.4%                 | 19.3              |                      |
| 5               | IL Chicago | with exterior low-e panel, worst case mounting | 85.61             | 581.41               | 700.2           | \$175.34            | 20.0%                 | 14.3              |                      |

| Climate Zone | Location     | Window   | HVAC         | Whole H | Whole House Cooling Whole House Heating |       | Source | Energy | % source energy savings |       |
|--------------|--------------|--|--------------|---------|---|-------|--------|--------|-------------------------|-------|
| 5            | MA Boston    | Wood frame, single pane                        | Furnace / AC | 888     | kWh                                     | 102.6 | MBtu   | 122.2  | MBtu                    |       |
| 5            | MA Boston    | with exterior clear panel                      | Furnace / AC | 876     | kWh                                     | 60.3  | MBtu   | 75.9   | MBtu                    | 37.9% |
| 5            | MA Boston    | with interior clear panel                      | Furnace / AC | 884     | kWh                                     | 58.1  | MBtu   | 73.6   | MBtu                    | 39.8% |
| 5            | MA Boston    | with exterior low-e panel                      | Furnace / AC | 813     | kWh                                     | 52.5  | MBtu   | 66.7   | MBtu                    | 45.5% |
| 5            | MA Boston    | with interior low-e panel                      | Furnace / AC | 886     | kWh                                     | 47.8  | MBtu   | 62.4   | MBtu                    | 49.0% |
| 5            | MA Boston    | Wood frame, double pane                        | Furnace / AC | 915     | kWh                                     | 69.3  | MBtu   | 86.2   | MBtu                    |       |
| 5            | MA Boston    | with exterior clear panel                      | Furnace / AC | 844     | kWh                                     | 58.4  | MBtu   | 73.5   | MBtu                    | 14.8% |
| 5            | MA Boston    | with interior clear panel                      | Furnace / AC | 875     | kWh                                     | 55.8  | MBtu   | 71.0   | MBtu                    | 17.6% |
| 5            | MA Boston    | with exterior low-e panel                      | Furnace / AC | 777     | kWh                                     | 52    | MBtu   | 65.7   | MBtu                    | 23.8% |
| 5            | MA Boston    | with interior low-e panel                      | Furnace / AC | 863     | kWh                                     | 48.2  | MBtu   | 62.5   | MBtu                    | 27.4% |
| 5            | MA Boston    | Metal frame, double pane                       | Furnace / AC | 815     | kWh                                     | 84.3  | MBtu   | 101.4  | MBtu                    |       |
| 5            | MA Boston    | with exterior clear panel                      | Furnace / AC | 848     | kWh                                     | 64    | MBtu   | 79.6   | MBtu                    | 21.5% |
| 5            | MA Boston    | with interior clear panel                      | Furnace / AC | 847     | kWh                                     | 61.3  | MBtu   | 76.7   | MBtu                    | 24.4% |
| 5            | MA Boston    | with exterior low-e panel                      | Furnace / AC | 803     | kWh                                     | 55.2  | MBtu   | 69.5   | MBtu                    | 31.5% |
| 5            | MA Boston    | with interior low-e panel                      | Furnace / AC | 829     | kWh                                     | 52    | MBtu   | 66.3   | MBtu                    | 34.6% |
| 5            | MA Boston    | with exterior clear panel, worst case mounting | Furnace / AC | 797     | kWh                                     | 71.2  | MBtu   | 86.9   | MBtu                    | 14.3% |
| 5            | MA Boston    | with exterior low-e panel, worst case mounting | Furnace / AC | 734     | kWh                                     | 65.8  | MBtu   | 80.3   | MBtu                    | 20.8% |
| 5            | NY Rochester | Wood frame, single pane                        | Furnace / AC | 1123    | kWh                                     | 116.6 | MBtu   | 140.2  | MBtu                    |       |
| 5            | NY Rochester | with exterior clear panel                      | Furnace / AC | 1047    | kWh                                     | 71.8  | MBtu   | 90.4   | MBtu                    | 35.5% |
| 5            | NY Rochester | with interior clear panel                      | Furnace / AC | 1053    | kWh                                     | 69.4  | MBtu   | 87.9   | MBtu                    | 37.3% |
| 5            | NY Rochester | with exterior low-e panel                      | Furnace / AC | 976     | kWh                                     | 62.6  | MBtu   | 79.6   | MBtu                    | 43.3% |
| 5            | NY Rochester | with interior low-e panel                      | Furnace / AC | 1055    | kWh                                     | 58    | MBtu   | 75.4   | MBtu                    | 46.2% |
| 5            | NY Rochester | Wood frame, double pane                        | Furnace / AC | 1093    | kWh                                     | 81.7  | MBtu   | 101.8  | MBtu                    |       |
| 5            | NY Rochester | with exterior clear panel                      | Furnace / AC | 1006    | kWh                                     | 69.3  | MBtu   | 87.2   | MBtu                    | 14.3% |
| 5            | NY Rochester | with interior clear panel                      | Furnace / AC | 1040    | kWh                                     | 66.8  | MBtu   | 84.9   | MBtu                    | 16.6% |
| 5            | NY Rochester | with exterior low-e panel                      | Furnace / AC | 938     | kWh                                     | 61.8  | MBtu   | 78.3   | MBtu                    | 23.1% |
| 5            | NY Rochester | with interior low-e panel                      | Furnace / AC | 1028    | kWh                                     | 58.3  | MBtu   | 75.5   | MBtu                    | 25.8% |
| 5            | NY Rochester | Metal frame, double pane                       | Furnace / AC | 1011    | kWh                                     | 97.3  | MBtu   | 117.9  | MBtu                    |       |
| 5            | NY Rochester | with exterior clear panel                      | Furnace / AC | 1023    | kWh                                     | 75.7  | MBtu   | 94.4   | MBtu                    | 19.9% |
| 5            | NY Rochester | with interior clear panel                      | Furnace / AC | 1010    | kWh                                     | 72.7  | MBtu   | 91.0   | MBtu                    | 22.8% |
| 5            | NY Rochester | with exterior low-e panel                      | Furnace / AC | 956     | kWh                                     | 65.5  | MBtu   | 82.5   | MBtu                    | 30.0% |
| 5            | NY Rochester | with interior low-e panel                      | Furnace / AC | 998     | kWh                                     | 62.4  | MBtu   | 79.6   | MBtu                    | 32.5% |
| 5            | NY Rochester | with exterior clear panel, worst case mounting | Furnace / AC | 976     | kWh                                     | 83.1  | MBtu   | 102.0  | MBtu                    | 13.5% |
| 5            | NY Rochester | with exterior low-e panel, worst case mounting | Furnace / AC | 897     | kWh                                     | 76.7  | MBtu   | 94.1   | MBtu                    | 20.2% |

| Climate<br>Zone | Location     | Window   | Cooling Cost (\$) | Heating Cost<br>(\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|--------------|--|-------------------|----------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 5               | MA Boston    | Wood frame, single pane                        | 91.34             | 1384.96              | 1517.27         |                     |                       |                   |                      |
| 5               | MA Boston    | with exterior clear panel                      | 81.35             | 813.82               | 944.34          | \$572.93            | 37.8%                 | 3.9               |                      |
| 5               | MA Boston    | with interior clear panel                      | 81.5              | 784.04               | 915.76          | \$601.51            | 39.6%                 | 3.8               |                      |
| 5               | MA Boston    | with exterior low-e panel                      | 73.46             | 708.1                | 829.24          | \$688.03            | 45.3%                 | 3.7               | 2.2                  |
| 5               | MA Boston    | with interior low-e panel                      | 80.31             | 645.87               | 777.88          | \$739.39            | 48.7%                 | 3.4               | 1.8                  |
| 5               | MA Boston    | Wood frame, double pane                        | 86.42             | 935.63               | 1071.97         |                     |                       |                   |                      |
| 5               | MA Boston    | with exterior clear panel                      | 77.78             | 787.89               | 913.65          | \$158.32            | 14.8%                 | 14.3              |                      |
| 5               | MA Boston    | with interior clear panel                      | 80.31             | 753.77               | 884.15          | \$187.82            | 17.5%                 | 12.0              |                      |
| 5               | MA Boston    | with exterior low-e panel                      | 69.58             | 701.37               | 817.14          | \$254.83            | 23.8%                 | 9.9               | 2.6                  |
| 5               | MA Boston    | with interior low-e panel                      | 77.63             | 650.31               | 778.9           | \$293.07            | 27.3%                 | 8.6               | 2.4                  |
| 5               | MA Boston    | Metal frame, double pane                       | 81.95             | 1138.37              | 1259.81         |                     |                       |                   |                      |
| 5               | MA Boston    | with exterior clear panel                      | 80.01             | 864.57               | 990.92          | \$268.89            | 21.3%                 | 8.4               |                      |
| 5               | MA Boston    | with interior clear panel                      | 78.52             | 827.46               | 953.66          | \$306.15            | 24.3%                 | 7.4               |                      |
| 5               | MA Boston    | with exterior low-e panel                      | 71.97             | 744.9                | 864.55          | \$395.26            | 31.4%                 | 6.4               | 2.0                  |
| 5               | MA Boston    | with interior low-e panel                      | 75.39             | 702.58               | 826.1           | \$433.71            | 34.4%                 | 5.8               | 2.0                  |
| 5               | MA Boston    | with exterior clear panel, worst case mounting | 77.48             | 961.35               | 1080.1          | \$179.71            | 14.3%                 | 12.6              |                      |
| 5               | MA Boston    | with exterior low-e panel, worst case mounting | 69.73             | 888.49               | 997.86          | \$261.95            | 20.8%                 | 9.6               |                      |
| 5               | NY Rochester | Wood frame, single pane                        | 150.8             | 1561.78              | 1760.55         |                     |                       |                   |                      |
| 5               | NY Rochester | with exterior clear panel                      | 133.28            | 961.83               | 1147.15         | \$613.40            | 34.8%                 | 3.7               |                      |
| 5               | NY Rochester | with interior clear panel                      | 133.46            | 930.63               | 1117.01         | \$643.54            | 36.6%                 | 3.5               |                      |
| 5               | NY Rochester | with exterior low-e panel                      | 120.89            | 839.13               | 1011.88         | \$748.67            | 42.5%                 | 3.4               | 1.9                  |
| 5               | NY Rochester | with interior low-e panel                      | 130.45            | 777.7                | 964.44          | \$796.11            | 45.2%                 | 3.2               | 1.7                  |
| 5               | NY Rochester | Wood frame, double pane                        | 141.6             | 1095.16              | 1288.62         |                     |                       |                   |                      |
| 5               | NY Rochester | with exterior clear panel                      | 127.62            | 929.17               | 1107.23         | \$181.39            | 14.1%                 | 12.4              |                      |
| 5               | NY Rochester | with interior clear panel                      | 131.33            | 895.63               | 1079.71         | \$208.91            | 16.2%                 | 10.8              |                      |
| 5               | NY Rochester | with exterior low-e panel                      | 115.94            | 827.96               | 993.99          | \$294.63            | 22.9%                 | 8.5               | 2.3                  |
| 5               | NY Rochester | with interior low-e panel                      | 126.56            | 780.56               | 962.52          | \$326.10            | 25.3%                 | 7.7               | 2.2                  |
| 5               | NY Rochester | Metal frame, double pane                       | 134.87            | 1304.32              | 1483.27         |                     |                       |                   |                      |
| 5               | NY Rochester | with exterior clear panel                      | 131.69            | 1013.88              | 1194.95         | \$288.32            | 19.4%                 | 7.8               |                      |
| 5               | NY Rochester | with interior clear panel                      | 129.39            | 974.01               | 1152.78         | \$330.49            | 22.3%                 | 6.8               |                      |
| 5               | NY Rochester | with exterior low-e panel                      | 119.48            | 877.51               | 1046.72         | \$436.55            | 29.4%                 | 5.8               | 1.7                  |
| 5               | NY Rochester | with interior low-e panel                      | 124.08            | 835.96               | 1012.61         | \$470.66            | 31.7%                 | 5.3               | 1.8                  |
| 5               | NY Rochester | with exterior clear panel, worst case mounting | 127.44            | 1113.69              | 1286.44         | \$196.83            | 13.3%                 | 11.5              |                      |
| 5               | NY Rochester | with exterior low-e panel, worst case mounting | 115.05            | 1027.38              | 1186.15         | \$297.12            | 20.0%                 | 8.5               | 1                    |

| Climate Zone | Location         | Window   | HVAC         | Whole H | ouse Cooling | Whole Hou | use Heating | Source | Energy | % source energy savings |
|--------------|------------------|--|--------------|---------|--------------|-----------|-------------|--------|--------|-------------------------|
| 5            | PA Pittsburgh    | Wood frame, single pane                        | Furnace / AC | 1172    | kWh          | 95.6      | MBtu        | 117.9  | MBtu   |                         |
| 5            | PA Pittsburgh    | with exterior clear panel                      | Furnace / AC | 1092    | kWh          | 58.4      | MBtu        | 76.3   | MBtu   | 35.2%                   |
| 5            | PA Pittsburgh    | with interior clear panel                      | Furnace / AC | 1094    | kWh          | 56.4      | MBtu        | 74.1   | MBtu   | 37.1%                   |
| 5            | PA Pittsburgh    | with exterior low-e panel                      | Furnace / AC | 1020    | kWh          | 50.5      | MBtu        | 66.9   | MBtu   | 43.3%                   |
| 5            | PA Pittsburgh    | with interior low-e panel                      | Furnace / AC | 1104    | kWh          | 46.6      | MBtu        | 63.6   | MBtu   | 46.1%                   |
| 5            | PA Pittsburgh    | Wood frame, double pane                        | Furnace / AC | 1143    | kWh          | 66.5      | MBtu        | 85.7   | MBtu   |                         |
| 5            | PA Pittsburgh    | with exterior clear panel                      | Furnace / AC | 1052    | kWh          | 56.3      | MBtu        | 73.6   | MBtu   | 14.2%                   |
| 5            | PA Pittsburgh    | with interior clear panel                      | Furnace / AC | 1084    | kWh          | 54.2      | MBtu        | 71.6   | MBtu   | 16.5%                   |
| 5            | PA Pittsburgh    | with exterior low-e panel                      | Furnace / AC | 985     | kWh          | 49.8      | MBtu        | 65.7   | MBtu   | 23.4%                   |
| 5            | PA Pittsburgh    | with interior low-e panel                      | Furnace / AC | 1072    | kWh          | 46.8      | MBtu        | 63.4   | MBtu   | 26.0%                   |
| 5            | PA Pittsburgh    | Metal frame, double pane                       | Furnace / AC | 1055    | kWh          | 80.2      | MBtu        | 99.7   | MBtu   |                         |
| 5            | PA Pittsburgh    | with exterior clear panel                      | Furnace / AC | 1075    | kWh          | 61.8      | MBtu        | 79.8   | MBtu   | 19.9%                   |
| 5            | PA Pittsburgh    | with interior clear panel                      | Furnace / AC | 1062    | kWh          | 59.3      | MBtu        | 76.9   | MBtu   | 22.8%                   |
| 5            | PA Pittsburgh    | with exterior low-e panel                      | Furnace / AC | 1005    | kWh          | 53        | MBtu        | 69.4   | MBtu   | 30.4%                   |
| 5            | PA Pittsburgh    | with interior low-e panel                      | Furnace / AC | 1043    | kWh          | 50.4      | MBtu        | 67.0   | MBtu   | 32.8%                   |
| 5            | PA Pittsburgh    | with exterior clear panel, worst case mounting | Furnace / AC | 1021    | kWh          | 68.3      | MBtu        | 86.3   | MBtu   | 13.4%                   |
| 5            | PA Pittsburgh    | with exterior low-e panel, worst case mounting | Furnace / AC | 948     | kWh          | 62.8      | MBtu        | 79.5   | MBtu   | 20.3%                   |
| 4            | NY New York City | Wood frame, single pane                        | Furnace / AC | 1453    | kWh          | 91.5      | MBtu        | 116.6  | MBtu   |                         |
| 4            | NY New York City | with exterior clear panel                      | Furnace / AC | 1330    | kWh          | 55.2      | MBtu        | 75.5   | MBtu   | 35.2%                   |
| 4            | NY New York City | with interior clear panel                      | Furnace / AC | 1329    | kWh          | 53.3      | MBtu        | 73.5   | MBtu   | 37.0%                   |
| 4            | NY New York City | with exterior low-e panel                      | Furnace / AC | 1242    | kWh          | 48.3      | MBtu        | 67.0   | MBtu   | 42.5%                   |
| 4            | NY New York City | with interior low-e panel                      | Furnace / AC | 1318    | kWh          | 44.3      | MBtu        | 63.5   | MBtu   | 45.5%                   |
| 4            | NY New York City | Wood frame, double pane                        | Furnace / AC | 1393    | kWh          | 63        | MBtu        | 84.8   | MBtu   |                         |
| 4            | NY New York City | with exterior clear panel                      | Furnace / AC | 1290    | kWh          | 53.6      | MBtu        | 73.3   | MBtu   | 13.5%                   |
| 4            | NY New York City | with interior clear panel                      | Furnace / AC | 1317    | kWh          | 51.4      | MBtu        | 71.3   | MBtu   | 16.0%                   |
| 4            | NY New York City | with exterior low-e panel                      | Furnace / AC | 1201    | kWh          | 47.9      | MBtu        | 66.1   | MBtu   | 22.0%                   |
| 4            | NY New York City | with interior low-e panel                      | Furnace / AC | 1284    | kWh          | 44.6      | MBtu        | 63.4   | MBtu   | 25.2%                   |
| 4            | NY New York City | Metal frame, double pane                       | Furnace / AC | 1331    | kWh          | 76.1      | MBtu        | 98.4   | MBtu   |                         |
| 4            | NY New York City | with exterior clear panel                      | Furnace / AC | 1316    | kWh          | 58.6      | MBtu        | 79.1   | MBtu   | 19.6%                   |
| 4            | NY New York City | 1  | Furnace / AC | 1300    | kWh          | 56.2      | MBtu        | 76.3   | MBtu   | 22.4%                   |
| 4            | NY New York City | with exterior low-e panel                      | Furnace / AC | 1230    | kWh          | 50.7      | MBtu        | 69.5   | MBtu   | 29.4%                   |
| 4            | NY New York City | with interior low-e panel                      | Furnace / AC | 1266    | kWh          | 48        | MBtu        | 67.0   | MBtu   | 31.9%                   |
| 4            | NY New York City | with exterior clear panel, worst case mounting | Furnace / AC | 1278    | kWh          | 64.8      | MBtu        | 85.4   | MBtu   | 13.2%                   |
| 4            | NY New York City | with exterior low-e panel, worst case mounting | Furnace / AC | 1187    | kWh          | 60.1      | MBtu        | 79.3   | MBtu   | 19.4%                   |

| Climate<br>Zone | Location         | Window   | Cooling Cost (\$) | Heating Cost<br>(\$) | Total Cost<br>(\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|------------------|--|-------------------|----------------------|--------------------|---------------------|-----------------------|-------------------|----------------------|
| 5               | PA Pittsburgh    | Wood frame, single pane                        | 117.25            | 1118.64              | 1268.66            |                     |                       |                   |                      |
| 5               | PA Pittsburgh    | with exterior clear panel                      | 104.7             | 682.92               | 822.7              | \$445.96            | 35.2%                 | 5.1               |                      |
| 5               | PA Pittsburgh    | with interior clear panel                      | 104.7             | 660.38               | 800.41             | \$468.25            | 36.9%                 | 4.8               |                      |
| 5               | PA Pittsburgh    | with exterior low-e panel                      | 95.36             | 590.67               | 721.23             | \$547.43            | 43.2%                 | 4.6               | 2.5                  |
| 5               | PA Pittsburgh    | with interior low-e panel                      | 102.53            | 544.76               | 686.07             | \$582.59            | 45.9%                 | 4.3               | 2.2                  |
| 5               | PA Pittsburgh    | Wood frame, double pane                        | 110.46            | 778.31               | 924.61             |                     |                       |                   |                      |
| 5               | PA Pittsburgh    | with exterior clear panel                      | 100.35            | 658.71               | 793.37             | \$131.24            | 14.2%                 | 17.2              |                      |
| 5               | PA Pittsburgh    | with interior clear panel                      | 103.17            | 634.2                | 772.95             | \$151.66            | 16.4%                 | 14.9              |                      |
| 5               | PA Pittsburgh    | with exterior low-e panel                      | 91.52             | 582.67               | 708.75             | \$215.86            | 23.3%                 | 11.6              | 3.0                  |
| 5               | PA Pittsburgh    | with interior low-e panel                      | 99.2              | 547.02               | 684.24             | \$240.37            | 26.0%                 | 10.4              | 2.9                  |
| 5               | PA Pittsburgh    | Metal frame, double pane                       | 105.6             | 938.09               | 1073.13            |                     |                       |                   |                      |
| 5               | PA Pittsburgh    | with exterior clear panel                      | 103.55            | 723.13               | 860.73             | \$212.40            | 19.8%                 | 10.6              |                      |
| 5               | PA Pittsburgh    | with interior clear panel                      | 101.63            | 694.32               | 830.26             | \$242.87            | 22.6%                 | 9.3               |                      |
| 5               | PA Pittsburgh    | with exterior low-e panel                      | 94.21             | 619.97               | 748.61             | \$324.52            | 30.2%                 | 7.7               | 2.3                  |
| 5               | PA Pittsburgh    | with interior low-e panel                      | 97.66             | 589.33               | 722.83             | \$350.30            | 32.6%                 | 7.2               | 2.4                  |
| 5               | PA Pittsburgh    | with exterior clear panel, worst case mounting | 99.71             | 799.54               | 930.23             | \$142.90            | 13.3%                 | 15.8              |                      |
| 5               | PA Pittsburgh    | with exterior low-e panel, worst case mounting | 90.88             | 734.67               | 856.01             | \$217.12            | 20.2%                 | 11.6              |                      |
| 4               | NY New York City | Wood frame, single pane                        | 209.75            | 1226.03              | 1483.21            |                     |                       |                   |                      |
| 4               | NY New York City | with exterior clear panel                      | 189.92            | 740.1                | 975.51             | \$507.70            | 34.2%                 | 4.4               |                      |
| 4               | NY New York City | with interior clear panel                      | 189.92            | 714.29               | 949.52             | \$533.69            | 36.0%                 | 4.2               |                      |
| 4               | NY New York City | with exterior low-e panel                      | 176.29            | 647.74               | 867.57             | \$615.64            | 41.5%                 | 4.1               | 2.4                  |
| 4               | NY New York City | with interior low-e panel                      | 186.2             | 593.97               | 827.26             | \$655.95            | 44.2%                 | 3.8               | 2.1                  |
| 4               | NY New York City | Wood frame, double pane                        | 199.66            | 844.05               | 1090.61            |                     |                       |                   |                      |
| 4               | NY New York City | with exterior clear panel                      | 184.26            | 718.27               | 946.6              | \$144.01            | 13.2%                 | 15.7              |                      |
| 4               | NY New York City | with interior clear panel                      | 188.33            | 688.83               | 921.94             | \$168.67            | 15.5%                 | 13.4              |                      |
| 4               | NY New York City | with exterior low-e panel                      | 170.63            | 642.29               | 854.87             | \$235.74            | 21.6%                 | 10.7              | 2.8                  |
| 4               | NY New York City | with interior low-e panel                      | 181.96            | 598.1                | 825.37             | \$265.24            | 24.3%                 | 9.5               | 2.6                  |
| 4               | NY New York City | Metal frame, double pane                       | 192.75            | 1019.53              | 1255.12            |                     |                       |                   |                      |
| 4               | NY New York City | with exterior clear panel                      | 188.51            | 784.72               | 1017.65            | \$237.47            | 18.9%                 | 9.5               |                      |
| 4               | NY New York City | with interior clear panel                      | 185.85            | 752.89               | 982.99             | \$272.13            | 21.7%                 | 8.3               |                      |
| 4               | NY New York City | with exterior low-e panel                      | 175.05            | 680.01               | 897.72             | \$357.40            | 28.5%                 | 7.0               | 2.1                  |
| 4               | NY New York City | with interior low-e panel                      | 179.83            | 643.35               | 867.43             | \$387.69            | 30.9%                 | 6.5               | 2.2                  |
| 4               | NY New York City | with exterior clear panel, worst case mounting | 183.9             | 868.95               | 1095.16            | \$159.96            | 12.7%                 | 14.1              |                      |
| 4               | NY New York City | with exterior low-e panel, worst case mounting | 170.63            | 804.98               | 1015.08            | \$240.04            | 19.1%                 | 10.5              |                      |

| Climate Zone | Location      | Window  | HVAC         | Whole House Cooling Whole House Heating S |     | Source | e Energy | % source energy savings |      |       |
|--------------|---------------|---|--------------|---|-----|--------|----------|-------------------------|------|-------|
| 4            | WA Seattle    | Wood frame, single pane                         | Furnace / AC | 257                                       | kWh | 72.1   | MBtu     | 81.7                    | MBtu |       |
| 4            | WA Seattle    | with exterior clear panel                       | Furnace / AC | 239                                       | kWh | 42.5   | MBtu     | 49.2                    | MBtu | 39.8% |
| 4            | WA Seattle    | with interior clear panel                       | Furnace / AC | 239                                       | kWh | 40.9   | MBtu     | 47.4                    | MBtu | 42.0% |
| 4            | WA Seattle    | with exterior low-e panel                       | Furnace / AC | 213                                       | kWh | 35.8   | MBtu     | 41.5                    | MBtu | 49.1% |
| 4            | WA Seattle    | with interior low-e panel                       | Furnace / AC | 230                                       | kWh | 32.7   | MBtu     | 38.3                    | MBtu | 53.1% |
| 4            | WA Seattle    | Wood frame, double pane                         | Furnace / AC | 251                                       | kWh | 49     | MBtu     | 56.4                    | MBtu |       |
| 4            | WA Seattle    | with exterior clear panel                       | Furnace / AC | 225                                       | kWh | 40.9   | MBtu     | 47.2                    | MBtu | 16.2% |
| 4            | WA Seattle    | with interior clear panel                       | Furnace / AC | 235                                       | kWh | 39.3   | MBtu     | 45.6                    | MBtu | 19.1% |
| 4            | WA Seattle    | with exterior low-e panel                       | Furnace / AC | 201                                       | kWh | 35.3   | MBtu     | 40.9                    | MBtu | 27.5% |
| 4            | WA Seattle    | with interior low-e panel                       | Furnace / AC | 217                                       | kWh | 32.9   | MBtu     | 38.4                    | MBtu | 31.9% |
| 4            | WA Seattle    | Metal frame, double pane                        | Furnace / AC | 221                                       | kWh | 60.4   | MBtu     | 68.5                    | MBtu |       |
| 4            | WA Seattle    | with exterior clear panel                       | Furnace / AC | 232                                       | kWh | 45.5   | MBtu     | 52.3                    | MBtu | 23.6% |
| 4            | WA Seattle    | with interior clear panel                       | Furnace / AC | 228                                       | kWh | 43.5   | MBtu     | 50.1                    | MBtu | 26.8% |
| 4            | WA Seattle    | with exterior low-e panel                       | Furnace / AC | 208                                       | kWh | 37.9   | MBtu     | 43.8                    | MBtu | 36.1% |
| 4            | WA Seattle    | with interior low-e panel                       | Furnace / AC | 215                                       | kWh | 35.8   | MBtu     | 41.6                    | MBtu | 39.3% |
| 4            | WA Seattle    | with exterior clear panel, worst case mounting  | Furnace / AC | 217                                       | kWh | 50.9   | MBtu     | 58.1                    | MBtu | 15.2% |
| 4            | WA Seattle    | with exterior low-e panel, worst case mounting  | Furnace / AC | 189                                       | kWh | 46     | MBtu     | 52.4                    | MBtu | 23.5% |
| 4            | DC Washington | Wood frame, single pane                         | Furnace / AC | 1860                                      | kWh | 79.8   | MBtu     | 108.5                   | MBtu |       |
| 4            | DC Washington | with exterior clear panel                       | Furnace / AC | 1676                                      | kWh | 49.1   | MBtu     | 72.9                    | MBtu | 32.8% |
| 4            | DC Washington | with interior clear panel                       | Furnace / AC | 1676                                      | kWh | 47.4   | MBtu     | 71.0                    | MBtu | 34.6% |
| 4            | DC Washington | with exterior low-e panel                       | Furnace / AC | 1574                                      | kWh | 42.8   | MBtu     | 64.8                    | MBtu | 40.3% |
| 4            | DC Washington | with interior low-e panel                       | Furnace / AC | 1671                                      | kWh | 39.1   | MBtu     | 61.9                    | MBtu | 43.0% |
| 4            | DC Washington | with exterior solar-E panel                     | Furnace / AC | 1313                                      | kWh | 46.8   | MBtu     | 66.2                    | MBtu | 39.0% |
| 4            | DC Washington | Wood frame, double pane                         | Furnace / AC | 1760                                      | kWh | 55.9   | MBtu     | 81.3                    | MBtu |       |
| 4            | DC Washington | with exterior clear panel                       | Furnace / AC | 1626                                      | kWh | 47.6   | MBtu     | 70.6                    | MBtu | 13.0% |
| 4            | DC Washington | with interior clear panel                       | Furnace / AC | 1664                                      | kWh | 45.6   | MBtu     | 68.9                    | MBtu | 15.2% |
| 4            | DC Washington | with exterior low-e panel                       | Furnace / AC | 1526                                      | kWh | 42.4   | MBtu     | 63.8                    | MBtu | 21.5% |
| 4            | DC Washington | with interior low-e panel                       | Furnace / AC | 1629                                      | kWh | 39.4   | MBtu     | 61.7                    | MBtu | 24.0% |
| 4            | DC Washington | with exterior solar-E panel                     | Furnace / AC | 1281                                      | kWh | 46.2   | MBtu     | 65.2                    | MBtu | 19.8% |
| 4            |               | Metal frame, double pane                        | Furnace / AC | 1687                                      | kWh | 67.8   | MBtu     | 93.4                    | MBtu |       |
| 4            | DC Washington | with exterior clear panel                       | Furnace / AC | 1657                                      | kWh | 52.2   | MBtu     | 76.0                    | MBtu | 18.6% |
| 4            | DC Washington | with interior clear panel                       | Furnace / AC | 1635                                      | kWh | 50.2   | MBtu     | 73.6                    | MBtu | 21.2% |
| 4            | DC Washington | with exterior low-e panel                       | Furnace / AC | 1558                                      | kWh | 45     | MBtu     | 67.0                    | MBtu | 28.2% |
| 4            | DC Washington | with interior low-e panel                       | Furnace / AC | 1597                                      | kWh | 42.6   | MBtu     | 64.9                    | MBtu | 30.6% |
| 4            | DC Washington | with exterior solar-E panel                     | Furnace / AC | 1305                                      | kWh | 49.1   | MBtu     | 68.6                    | MBtu | 26.6% |
| 4            | DC Washington | with exterior clear panel, worst case mounting  | Furnace / AC | 1612                                      | kWh | 58     | MBtu     | 81.8                    | MBtu | 12.4% |
| 4            | DC Washington | with exterior low-e panel, worst case mounting  | Furnace / AC | 1499                                      | kWh | 53.6   | MBtu     | 75.7                    | MBtu | 18.9% |
| 4            | DC Washington | with exterior solar-E panel, worst case mountin | Furnace / AC | 1290                                      | kWh | 57.2   | MBtu     | 77.3                    | MBtu | 17.3% |

| Climate<br>Zone | Location      | Window   | Cooling Cost (\$) | Heating Cost<br>(\$) | Total Cost (\$) | Energy cost savings | % energy cost savings | Simple<br>payback | Payback<br>for low-e |
|-----------------|---------------|--|-------------------|----------------------|-----------------|---------------------|-----------------------|-------------------|----------------------|
| 4               | WA Seattle    | Wood frame, single pane                          | 15.64             | 837.41               | 859.26          |                     |                       |                   |                      |
| 4               | WA Seattle    | with exterior clear panel                        | 13.6              | 493.57               | 513.89          | \$345.37            | 40.2%                 | 6.5               |                      |
| 4               | WA Seattle    | with interior clear panel                        | 13.77             | 475.83               | 496.15          | \$363.11            | 42.3%                 | 6.2               |                      |
| 4               | WA Seattle    | with exterior low-e panel                        | 11.99             | 415.69               | 433.8           | \$425.46            | 49.5%                 | 5.9               | 3.2                  |
| 4               | WA Seattle    | with interior low-e panel                        | 13.69             | 380.01               | 399.56          | \$459.70            | 53.5%                 | 5.5               | 2.6                  |
| 4               | WA Seattle    | Wood frame, double pane                          | 14.71             | 569.28               | 590.62          |                     |                       |                   |                      |
| 4               | WA Seattle    | with exterior clear panel                        | 12.75             | 475.82               | 494.95          | \$95.67             | 16.2%                 | 23.6              |                      |
| 4               | WA Seattle    | with interior clear panel                        | 13.52             | 456.7                | 476.68          | \$113.94            | 19.3%                 | 19.8              |                      |
| 4               | WA Seattle    | with exterior low-e panel                        | 11.05             | 409.69               | 426.78          | \$163.84            | 27.7%                 | 15.3              | 3.7                  |
| 4               | WA Seattle    | with interior low-e panel                        | 12.92             | 381.8                | 400.25          | \$190.37            | 32.2%                 | 13.2              | 3.3                  |
| 4               | WA Seattle    | Metal frame, double pane                         | 13.43             | 702.23               | 721.02          |                     |                       |                   |                      |
| 4               | WA Seattle    | with exterior clear panel                        | 13.43             | 529.29               | 549.01          | \$172.01            | 23.9%                 | 13.1              |                      |
| 4               | WA Seattle    | with interior clear panel                        | 13.18             | 505.68               | 525.06          | \$195.96            | 27.2%                 | 11.5              |                      |
| 4               | WA Seattle    | with exterior low-e panel                        | 11.65             | 440.21               | 457.89          | \$263.13            | 36.5%                 | 9.5               | 2.8                  |
| 4               | WA Seattle    | with interior low-e panel                        | 12.5              | 415.45               | 433.73          | \$287.29            | 39.8%                 | 8.7               | 2.8                  |
| 4               | WA Seattle    | with exterior clear panel, worst case mounting   | 12.58             | 592.02               | 610.47          | \$110.55            | 15.3%                 | 20.4              |                      |
| 4               | WA Seattle    | with exterior low-e panel, worst case mounting   | 10.54             | 534.9                | 550.97          | \$170.05            | 23.6%                 | 14.8              |                      |
| 4               | DC Washington | Wood frame, single pane                          | 195.94            | 1018.71              | 1247.49         |                     |                       |                   |                      |
| 4               | DC Washington | with exterior clear panel                        | 174.66            | 627.56               | 833.71          | \$413.78            | 33.2%                 | 5.5               |                      |
| 4               | DC Washington | with interior clear panel                        | 174.54            | 605.83               | 811.98          | \$435.51            | 34.9%                 | 5.8               |                      |
| 4               | DC Washington | with exterior low-e panel                        | 161.87            | 546.29               | 739.89          | \$507.60            | 40.7%                 | 4.9               | 2.7                  |
| 4               | DC Washington | with interior low-e panel                        | 169.86            | 498.86               | 704.39          | \$543.10            | 43.5%                 | 4.2               | 2.4                  |
| 4               | DC Washington | with exterior solar-E panel                      | 137.64            | 598.1                | 759.6           | \$487.89            | 39.1%                 | 5.1               | 3.4                  |
| 4               | DC Washington | Wood frame, double pane                          | 183.76            | 713.51               | 929.99          |                     |                       |                   |                      |
| 4               | DC Washington | with exterior clear panel                        | 169.25            | 608.21               | 808.21          | \$121.78            | 13.1%                 | 18.5              |                      |
| 4               | DC Washington | with interior clear panel                        | 172.32            | 582.9                | 787.57          | \$142.42            | 15.3%                 | 17.6              |                      |
| 4               | DC Washington | with exterior low-e panel                        | 157.07            | 541.18               | 728.88          | \$201.11            | 21.6%                 | 12.5              | 3.2                  |
| 4               | DC Washington | with interior low-e panel                        | 166.17            | 502.88               | 703.25          | \$226.74            | 24.4%                 | 10.0              | 3.0                  |
| 4               | DC Washington | with exterior solar-E panel                      | 134.19            | 590.46               | 748.02          | \$181.97            | 19.6%                 | 13.8              | 4.2                  |
| 4               | DC Washington | Metal frame, double pane                         | 178.6             | 865.36               | 1072.86         |                     |                       |                   |                      |
| 4               | DC Washington | with exterior clear panel                        | 173.55            | 666.87               | 870.68          | \$202.18            | 18.8%                 | 11.2              |                      |
| 4               | DC Washington | with interior clear panel                        | 170.97            | 640.68               | 841.79          | \$231.07            | 21.5%                 | 10.9              |                      |
| 4               | DC Washington | with exterior low-e panel                        | 161.01            | 574.32               | 765.95          | \$306.91            | 28.6%                 | 8.2               | 2.4                  |
| 4               | DC Washington | with interior low-e panel                        | 164.94            | 543.63               | 740.06          | \$332.80            | 31.0%                 | 6.8               | 2.5                  |
| 4               | DC Washington | with exterior solar-E panel                      | 137.27            | 626.39               | 786.91          | \$285.95            | 26.7%                 | 8.8               | 3.0                  |
| 4               | DC Washington | with exterior clear panel, worst case mounting   | 170.11            | 740.53               | 938.81          | \$134.05            | 12.5%                 | 16.8              |                      |
| 4               | DC Washington | with exterior low-e panel, worst case mounting   | 157.93            | 684.29               | 868.67          | \$204.19            | 19.0%                 | 12.3              |                      |
| 4               | DC Washington | with exterior solar-E panel, worst case mounting | 137.88            | 730.87               | 889.54          | \$183.32            | 17.1%                 | 13.7              |                      |

| Climate Zone | Location       | Window  | HVAC         | Whole H | ouse Cooling | Ü    |      | Source | Energy | % source energy savings |
|--------------|----------------|---|--------------|---------|--------------|------|------|--------|--------|-------------------------|
| 4            | MO Kansas City | Wood frame, single pane                         | Furnace / AC | 2692    | kWh          | 86   | MBtu | 124.8  | MBtu   |                         |
| 4            | MO Kansas City | with exterior clear panel                       | Furnace / AC | 2357    | kWh          | 52.8 | MBtu | 84.7   | MBtu   | 32.1%                   |
| 4            | MO Kansas City | with interior clear panel                       | Furnace / AC | 2356    | kWh          | 51   | MBtu | 82.7   | MBtu   | 33.7%                   |
| 4            | MO Kansas City | with exterior low-e panel                       | Furnace / AC | 2200    | kWh          | 46.1 | MBtu | 75.6   | MBtu   | 39.4%                   |
| 4            | MO Kansas City | with interior low-e panel                       | Furnace / AC | 2317    | kWh          | 42.2 | MBtu | 72.7   | MBtu   | 41.8%                   |
| 4            | MO Kansas City | with exterior solar-E panel                     | Furnace / AC | 1890    | kWh          | 50.1 | MBtu | 76.4   | MBtu   | 38.8%                   |
| 4            | MO Kansas City | Wood frame, double pane                         | Furnace / AC | 2510    | kWh          | 60   | MBtu | 94.3   | MBtu   |                         |
| 4            | MO Kansas City | with exterior clear panel                       | Furnace / AC | 2291    | kWh          | 51.1 | MBtu | 82.1   | MBtu   | 13.0%                   |
| 4            | MO Kansas City | with interior clear panel                       | Furnace / AC | 2335    | kWh          | 49.1 | MBtu | 80.4   | MBtu   | 14.7%                   |
| 4            | MO Kansas City | with exterior low-e panel                       | Furnace / AC | 2137    | kWh          | 45.6 | MBtu | 74.3   | MBtu   | 21.2%                   |
| 4            | MO Kansas City | with interior low-e panel                       | Furnace / AC | 2265    | kWh          | 42.5 | MBtu | 72.4   | MBtu   | 23.2%                   |
| 4            | MO Kansas City | with exterior solar-E panel                     | Furnace / AC | 1844    | kWh          | 49.5 | MBtu | 75.2   | MBtu   | 20.3%                   |
| 4            | MO Kansas City | Metal frame, double pane                        | Furnace / AC | 2425    | kWh          | 72.4 | MBtu | 106.9  | MBtu   |                         |
| 4            | MO Kansas City | with exterior clear panel                       | Furnace / AC | 2342    | kWh          | 56   | MBtu | 88.0   | MBtu   | 17.6%                   |
| 4            | MO Kansas City | with interior clear panel                       | Furnace / AC | 2309    | kWh          | 53.8 | MBtu | 85.3   | MBtu   | 20.2%                   |
| 4            | MO Kansas City | with exterior low-e panel                       | Furnace / AC | 2185    | kWh          | 48.4 | MBtu | 77.9   | MBtu   | 27.1%                   |
| 4            | MO Kansas City | with interior low-e panel                       | Furnace / AC | 2239    | kWh          | 45.8 | MBtu | 75.7   | MBtu   | 29.2%                   |
| 4            | MO Kansas City | with exterior solar-E panel                     | Furnace / AC | 1883    | kWh          | 52.4 | MBtu | 78.8   | MBtu   | 26.3%                   |
| 4            | MO Kansas City | with exterior clear panel, worst case mounting  | Furnace / AC | 2299    | kWh          | 62   | MBtu | 94.1   | MBtu   | 12.0%                   |
| 4            | MO Kansas City | with exterior low-e panel, worst case mounting  | Furnace / AC | 2141    | kWh          | 57.3 | MBtu | 87.2   | MBtu   | 18.5%                   |
| 4            | MO Kansas City | with exterior solar-E panel, worst case mountin | Furnace / AC | 1873    | kWh          | 60.9 | MBtu | 88.0   | MBtu   | 17.7%                   |
| 4            | NC Raleigh     | Wood frame, single pane                         | Furnace / AC | 2635    | kWh          | 56.5 | MBtu | 92.0   | MBtu   |                         |
| 4            | NC Raleigh     | with exterior clear panel                       | Furnace / AC | 2422    | kWh          | 34.1 | MBtu | 65.0   | MBtu   | 29.3%                   |
| 4            | NC Raleigh     | with interior clear panel                       | Furnace / AC | 2416    | kWh          | 32.8 | MBtu | 63.6   | MBtu   | 30.9%                   |
| 4            | NC Raleigh     | with exterior low-e panel                       | Furnace / AC | 2283    | kWh          | 29.4 | MBtu | 58.3   | MBtu   | 36.6%                   |
| 4            | NC Raleigh     | with interior low-e panel                       | Furnace / AC | 2393    | kWh          | 26.6 | MBtu | 56.5   | MBtu   | 38.5%                   |
| 4            | NC Raleigh     | with exterior solar-E panel                     | Furnace / AC | 1940    | kWh          | 33.1 | MBtu | 58.4   | MBtu   | 36.5%                   |
| 4            | NC Raleigh     | Wood frame, double pane                         | Furnace / AC | 2525    | kWh          | 38.9 | MBtu | 71.5   | MBtu   |                         |
| 4            | NC Raleigh     | with exterior clear panel                       | Furnace / AC | 2353    | kWh          | 33.1 | MBtu | 63.2   | MBtu   | 11.6%                   |
| 4            | NC Raleigh     | with interior clear panel                       | Furnace / AC | 2393    | kWh          | 31.6 | MBtu | 62.0   | MBtu   | 13.3%                   |
| 4            | NC Raleigh     | with exterior low-e panel                       | Furnace / AC | 2222    | kWh          | 29.2 | MBtu | 57.4   | MBtu   | 19.7%                   |
| 4            | NC Raleigh     | with interior low-e panel                       | Furnace / AC | 2342    | kWh          | 26.8 | MBtu | 56.2   | MBtu   | 21.4%                   |
| 4            | NC Raleigh     | with exterior solar-E panel                     | Furnace / AC | 1898    | kWh          | 32.7 | MBtu | 57.5   | MBtu   | 19.5%                   |
| 4            | NC Raleigh     | Metal frame, double pane                        | Furnace / AC | 2414    | kWh          | 48.1 | MBtu | 80.2   | MBtu   |                         |
| 4            | NC Raleigh     | with exterior clear panel                       | Furnace / AC | 2397    | kWh          | 36.5 | MBtu | 67.4   | MBtu   | 16.0%                   |
| 4            | NC Raleigh     | with interior clear panel                       | Furnace / AC | 2366    | kWh          | 35   | MBtu | 65.4   | MBtu   | 18.5%                   |
| 4            | NC Raleigh     | with exterior low-e panel                       | Furnace / AC | 2262    | kWh          | 31.2 | MBtu | 60.0   | MBtu   | 25.2%                   |
| 4            | NC Raleigh     | with interior low-e panel                       | Furnace / AC | 2318    | kWh          | 29.3 | MBtu | 58.6   | MBtu   | 27.0%                   |
| 4            | NC Raleigh     | with exterior solar-E panel                     | Furnace / AC | 1926    | kWh          | 34.8 | MBtu | 60.1   | MBtu   | 25.1%                   |
| 4            | NC Raleigh     | with exterior clear panel, worst case mounting  | Furnace / AC | 2325    | kWh          | 40.9 | MBtu | 71.4   | MBtu   | 11.1%                   |
| 4            | NC Raleigh     | with exterior low-e panel, worst case mounting  | Furnace / AC | 2186    | kWh          | 37.8 | MBtu | 66.4   | MBtu   | 17.3%                   |
| 4            | NC Raleigh     | with exterior solar-E panel, worst case mountin | Furnace / AC | 1903    | kWh          | 41.2 | MBtu | 66.8   | MBtu   | 16.7%                   |

| Climate | Location       | Window  | Cooling Cost | Heating Cost | Total Cost | Energy cost | % energy     | Simple  | Payback   |
|---------|----------------|---|--------------|--------------|------------|-------------|--------------|---------|-----------|
| Zone    |                |   | (\$)         | (\$)         | (\$)       | savings     | cost savings | payback | for low-e |
| 4       | MO Kansas City | Wood frame, single pane                             | 225.74       | 1034.07      | 1305.96    |             |              |         |           |
| 4       | MO Kansas City | with exterior clear panel                           | 197.46       | 635.35       | 873.41     | \$432.55    | 33.1%        | 5.2     |           |
| 4       | MO Kansas City | with interior clear panel                           | 196.65       | 613.7        | 851.66     | \$454.30    | 34.8%        | 5.5     |           |
| 4       | MO Kansas City | with exterior low-e panel                           | 183.32       | 554.29       | 776.49     | \$529.47    | 40.5%        | 4.7     | 2.6       |
| 4       | MO Kansas City | with interior low-e panel                           | 191.4        | 507.95       | 741.97     | \$563.99    | 43.2%        | 4.0     | 2.3       |
| 4       | MO Kansas City | with exterior solar-E panel                         | 157.66       | 603.14       | 794.03     | \$511.93    | 39.2%        | 4.9     | 3.2       |
| 4       | MO Kansas City | Wood frame, double pane                             | 208.16       | 721.68       | 975.19     |             |              |         |           |
| 4       | MO Kansas City | with exterior clear panel                           | 191.9        | 615.31       | 846.7      | \$128.49    | 13.2%        | 17.6    |           |
| 4       | MO Kansas City | with interior clear panel                           | 194.73       | 590.3        | 826.14     | \$149.05    | 15.3%        | 16.9    |           |
| 4       | MO Kansas City | with exterior low-e panel                           | 178.16       | 548.89       | 764.73     | \$210.46    | 21.6%        | 11.9    | 3.1       |
| 4       | MO Kansas City | with interior low-e panel                           | 187.66       | 511.54       | 740.31     | \$234.88    | 24.1%        | 9.6     | 3.0       |
| 4       | MO Kansas City | with exterior solar-E panel                         | 154.03       | 595.32       | 781.56     | \$193.63    | 19.9%        | 13.0    | 3.9       |
| 4       | MO Kansas City | Metal frame, double pane                            | 204.12       | 871.49       | 1116.42    |             |              |         |           |
| 4       | MO Kansas City | with exterior clear panel                           | 196.95       | 673.31       | 909.85     | \$206.57    | 18.5%        | 10.9    |           |
| 4       | MO Kansas City | with interior clear panel                           | 193.82       | 646.96       | 880.17     | \$236.25    | 21.2%        | 10.6    |           |
| 4       | MO Kansas City | with exterior low-e panel                           | 182.51       | 582.05       | 802.74     | \$313.68    | 28.1%        | 8.0     | 2.4       |
| 4       | MO Kansas City | with interior low-e panel                           | 186.14       | 551.32       | 777.46     | \$338.96    | 30.4%        | 6.7     | 2.5       |
| 4       | MO Kansas City | with exterior solar-E panel                         | 157.56       | 630.64       | 820.82     | \$295.60    | 26.5%        | 8.5     | 2.9       |
| 4       | MO Kansas City | with exterior clear panel, worst case mounting      | 193.82       | 745.28       | 977.48     | \$138.94    | 12.4%        | 16.2    |           |
| 4       | MO Kansas City | with exterior low-e panel, worst case mounting      | 179.78       | 689.92       | 906.16     | \$210.26    | 18.8%        | 11.9    |           |
| 4       | MO Kansas City | with exterior solar-E panel, worst case mounting    | 158.97       | 732.48       | 921.65     | \$194.77    | 17.4%        | 12.9    |           |
| 4       | NC Raleigh     | Wood frame, single pane                             | 289.66       | 692.69       | 977.27     |             |              |         |           |
| 4       | NC Raleigh     | with exterior clear panel                           | 263.95       | 417.9        | 679.48     | \$297.79    | 30.5%        | 7.6     |           |
| 4       | NC Raleigh     | with interior clear panel                           | 263.3        | 402.96       | 663.89     | \$313.38    | 32.1%        | 8.0     |           |
| 4       | NC Raleigh     | with exterior low-e panel                           | 249.7        | 361.33       | 607.89     | \$369.38    | 37.8%        | 6.8     | 3.6       |
| 4       | NC Raleigh     | with interior low-e panel                           | 258.88       | 326.04       | 584.48     | \$392.79    | 40.2%        | 5.7     | 3.2       |
| 4       | NC Raleigh     | with exterior solar-E panel                         | 223.13       | 406.11       | 615.63     | \$361.64    | 37.0%        | 6.9     | 4.0       |
| 4       | NC Raleigh     | Wood frame, double pane                             | 274.86       | 476.71       | 749.41     |             |              |         |           |
| 4       | NC Raleigh     | with exterior clear panel                           | 258.12       | 405.98       | 660.1      | \$89.31     | 11.9%        | 25.3    |           |
| 4       | NC Raleigh     | with interior clear panel                           | 261.36       | 387.43       | 645.87     | \$103.54    | 13.8%        | 24.3    |           |
| 4       | NC Raleigh     | with exterior low-e panel                           | 244.3        | 358.49       | 598.47     | \$150.94    | 20.1%        | 16.6    | 4.1       |
| 4       | NC Raleigh     | with interior low-e panel                           | 254.88       | 329.27       | 582.21     | \$167.20    | 22.3%        | 13.5    | 4.0       |
| 4       | NC Raleigh     | with exterior solar-E panel                         | 219.35       | 401.77       | 606.75     | \$142.66    | 19.0%        | 17.6    | 4.8       |
| 4       | NC Raleigh     | Metal frame, double pane                            | 269.68       | 590.16       | 850.87     |             |              |         |           |
| 4       | NC Raleigh     | with exterior clear panel                           | 263.3        | 447.55       | 706.43     | \$144.44    | 17.0%        | 15.6    |           |
| 4       | NC Raleigh     | with exterior clear panel                           | 260.06       | 429.47       | 685        | \$165.87    | 19.5%        | 15.1    |           |
| 4       | NC Raleigh     | with interior clear panel with exterior low-e panel | 248.72       | 382.32       | 626.62     | \$224.25    | 26.4%        | 11.2    | 3.2       |
| 4       | NC Raleigh     | with interior low-e panel                           | 253.15       | 359.29       | 609.63     | \$241.24    | 28.4%        | 9.4     | 3.4       |
| 4       | NC Raleigh     | with exterior solar-E panel                         | 222.91       | 427.39       | 635.4      | \$215.47    | 25.3%        | 11.7    | 3.6       |
| 4       | NC Raleigh     | with exterior clear panel, worst case mounting      | 259.42       | 502.31       | 753.41     | \$97.46     | 11.5%        | 23.2    |           |
| 4       | NC Raleigh     | with exterior low-e panel, worst case mounting      | 245.81       | 463.98       | 700.07     | \$150.80    | 17.7%        | 16.7    |           |
| 4       | NC Raleigh     | with exterior solar-E panel, worst case mounting    | 223.88       | 505.18       | 710.7      | \$140.17    | 16.5%        | 17.9    |           |

| Climate Zone | Location      | Window  | HVAC         | Whole H | ouse Cooling | Whole Ho | use Heating |      |      | % source energy savings |
|--------------|---------------|---|--------------|---------|--------------|----------|-------------|------|------|-------------------------|
| 3            | GA Atlanta    | Wood frame, single pane                         | Furnace / AC | 2670    | kWh          | 49       | MBtu        | 84.2 | MBtu |                         |
| 3            | GA Atlanta    | with exterior clear panel                       | Furnace / AC | 2417    | kWh          | 29.2     | MBtu        | 59.6 | MBtu | 29.1%                   |
| 3            | GA Atlanta    | with interior clear panel                       | Furnace / AC | 2416    | kWh          | 28.1     | MBtu        | 58.4 | MBtu | 30.6%                   |
| 3            | GA Atlanta    | with exterior low-e panel                       | Furnace / AC | 2268    | kWh          | 25.2     | MBtu        | 53.6 | MBtu | 36.4%                   |
| 3            | GA Atlanta    | with interior low-e panel                       | Furnace / AC | 2396    | kWh          | 22.5     | MBtu        | 52.1 | MBtu | 38.1%                   |
| 3            | GA Atlanta    | with exterior solar-E panel                     | Furnace / AC | 1897    | kWh          | 28.8     | MBtu        | 53.2 | MBtu | 36.8%                   |
| 3            | GA Atlanta    | Wood frame, double pane                         | Furnace / AC | 2534    | kWh          | 33.3     | MBtu        | 65.5 | MBtu |                         |
| 3            | GA Atlanta    | with exterior clear panel                       | Furnace / AC | 2344    | kWh          | 28.4     | MBtu        | 57.9 | MBtu | 11.5%                   |
| 3            | GA Atlanta    | with interior clear panel                       | Furnace / AC | 2394    | kWh          | 27       | MBtu        | 57.0 | MBtu | 13.0%                   |
| 3            | GA Atlanta    | with exterior low-e panel                       | Furnace / AC | 2196    | kWh          | 25.1     | MBtu        | 52.6 | MBtu | 19.6%                   |
| 3            | GA Atlanta    | with interior low-e panel                       | Furnace / AC | 2339    | kWh          | 22.8     | MBtu        | 51.8 | MBtu | 20.9%                   |
| 3            | GA Atlanta    | with exterior solar-E panel                     | Furnace / AC | 1851    | kWh          | 28.6     | MBtu        | 52.5 | MBtu | 19.8%                   |
| 3            | GA Atlanta    | Metal frame, double pane                        | Furnace / AC | 2437    | kWh          | 41.8     | MBtu        | 73.6 | MBtu |                         |
| 3            | GA Atlanta    | with exterior clear panel                       | Furnace / AC | 2395    | kWh          | 31.4     | MBtu        | 61.8 | MBtu | 16.1%                   |
| 3            | GA Atlanta    | with interior clear panel                       | Furnace / AC | 2362    | kWh          | 30.1     | MBtu        | 60.0 | MBtu | 18.5%                   |
| 3            | GA Atlanta    | with exterior low-e panel                       | Furnace / AC | 2248    | kWh          | 26.7     | MBtu        | 55.0 | MBtu | 25.3%                   |
| 3            | GA Atlanta    | with interior low-e panel                       | Furnace / AC | 2310    | kWh          | 25       | MBtu        | 53.8 | MBtu | 26.9%                   |
| 3            | GA Atlanta    | with exterior solar-E panel                     | Furnace / AC | 1891    | kWh          | 30.5     | MBtu        | 55.0 | MBtu | 25.3%                   |
| 3            | GA Atlanta    | with exterior clear panel, worst case mounting  | Furnace / AC | 2332    | kWh          | 35.5     | MBtu        | 65.5 | MBtu | 11.0%                   |
| 3            | GA Atlanta    | with exterior low-e panel, worst case mounting  | Furnace / AC | 2173    | kWh          | 32.8     | MBtu        | 60.8 | MBtu | 17.5%                   |
| 3            | GA Atlanta    | with exterior solar-E panel, worst case mountin | Furnace / AC | 1882    | kWh          | 36.2     | MBtu        | 61.1 | MBtu | 17.0%                   |
| 3            | TX Fort Worth | Wood frame, single pane                         | Furnace / AC | 4526    | kWh          | 40.2     | MBtu        | 95.9 | MBtu |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Furnace / AC | 3911    | kWh          | 22.9     | MBtu        | 69.9 | MBtu | 27.1%                   |
| 3            | TX Fort Worth | with interior clear panel                       | Furnace / AC | 3893    | kWh          | 21.9     | MBtu        | 68.6 | MBtu | 28.4%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Furnace / AC | 3639    | kWh          | 19.6     | MBtu        | 63.2 | MBtu | 34.1%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Furnace / AC | 3788    | kWh          | 17.3     | MBtu        | 62.4 | MBtu | 34.9%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Furnace / AC | 3173    | kWh          | 22.8     | MBtu        | 61.3 | MBtu | 36.0%                   |
| 3            | TX Fort Worth | Wood frame, double pane                         | Furnace / AC | 4139    | kWh          | 26.5     | MBtu        | 76.5 | MBtu |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Furnace / AC | 3811    | kWh          | 22.3     | MBtu        | 68.1 | MBtu | 10.9%                   |
| 3            | TX Fort Worth | with interior clear panel                       | Furnace / AC | 3860    | kWh          | 21.1     | MBtu        | 67.4 | MBtu | 11.9%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Furnace / AC | 3545    | kWh          | 19.5     | MBtu        | 62.0 | MBtu | 18.9%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Furnace / AC | 3719    | kWh          | 17.6     | MBtu        | 61.9 | MBtu | 19.0%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Furnace / AC | 3099    | kWh          | 22.7     | MBtu        | 60.4 | MBtu | 21.0%                   |
| 3            | TX Fort Worth | Metal frame, double pane                        | Furnace / AC | 4085    | kWh          | 33.7     | MBtu        | 83.7 | MBtu |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Furnace / AC | 3916    | kWh          | 24.8     | MBtu        | 72.0 | MBtu | 13.9%                   |
| 3            | TX Fort Worth | with interior clear panel                       | Furnace / AC | 3847    | kWh          | 23.7     | MBtu        | 70.1 | MBtu | 16.3%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Furnace / AC | 3633    | kWh          | 20.9     | MBtu        | 64.5 | MBtu | 22.9%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Furnace / AC | 3693    | kWh          | 19.4     | MBtu        | 63.6 | MBtu | 24.0%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Furnace / AC | 3174    | kWh          | 24.2     | MBtu        | 62.9 | MBtu | 24.9%                   |
| 3            | TX Fort Worth | with exterior clear panel, worst case mounting  | Furnace / AC | 3864    | kWh          | 28.3     | MBtu        | 75.3 | MBtu | 10.1%                   |
| 3            | TX Fort Worth | with exterior low-e panel, worst case mounting  | Furnace / AC | 3599    | kWh          | 26.1     | MBtu        | 69.8 | MBtu | 16.6%                   |
| 3            | TX Fort Worth | with exterior solar-E panel, worst case mountin | Furnace / AC | 3213    | kWh          | 29.1     | MBtu        | 68.7 | MBtu | 18.0%                   |

| Climate | Location      | Window   | Cooling Cost | <b>Heating Cost</b> | Total Cost | Energy cost | % energy     | Simple  | Payback   |
|---------|---------------|--|--------------|---------------------|------------|-------------|--------------|---------|-----------|
| Zone    |               |  | (\$)         | (\$)                | (\$)       | savings     | cost savings | payback | for low-e |
| 3       | GA Atlanta    | Wood frame, single pane                          | 319.44       | 752.61              | 1046.31    |             |              |         |           |
| 3       | GA Atlanta    | with exterior clear panel                        | 296.56       | 448.5               | 714.37     | \$331.94    | 31.7%        | 6.8     |           |
| 3       | GA Atlanta    | with interior clear panel                        | 295.79       | 431.65              | 697.41     | \$348.90    | 33.3%        | 7.2     |           |
| 3       | GA Atlanta    | with exterior low-e panel                        | 282.26       | 387                 | 636.48     | \$409.83    | 39.2%        | 6.1     | 3.3       |
| 3       | GA Atlanta    | with interior low-e panel                        | 293.15       | 345.64              | 609.2      | \$437.11    | 41.8%        | 5.2     | 2.9       |
| 3       | GA Atlanta    | with exterior solar-E panel                      | 251.68       | 443.41              | 652.08     | \$394.23    | 37.7%        | 6.4     | 4.1       |
| 3       | GA Atlanta    | Wood frame, double pane                          | 306.9        | 512.13              | 790.87     |             |              |         |           |
| 3       | GA Atlanta    | with exterior clear panel                        | 290.4        | 436.17              | 694.01     | \$96.86     | 12.2%        | 23.3    |           |
| 3       | GA Atlanta    | with interior clear panel                        | 294.14       | 415.1               | 678.44     | \$112.43    | 14.2%        | 22.3    |           |
| 3       | GA Atlanta    | with exterior low-e panel                        | 276.32       | 385.59              | 627.15     | \$163.72    | 20.7%        | 15.3    | 3.8       |
| 3       | GA Atlanta    | with interior low-e panel                        | 288.31       | 350.61              | 607.9      | \$182.97    | 23.1%        | 12.3    | 3.6       |
| 3       | GA Atlanta    | with exterior solar-E panel                      | 247.61       | 439.92              | 643.53     | \$147.34    | 18.6%        | 17.0    | 5.1       |
| 3       | GA Atlanta    | Metal frame, double pane                         | 300.19       | 641.88              | 909.95     |             |              |         |           |
| 3       | GA Atlanta    | with exterior clear panel                        | 295.35       | 482.59              | 746.04     | \$163.91    | 18.0%        | 13.8    |           |
| 3       | GA Atlanta    | with interior clear panel                        | 292.27       | 462.82              | 722.64     | \$187.31    | 20.6%        | 13.4    |           |
| 3       | GA Atlanta    | with exterior low-e panel                        | 281.38       | 410.92              | 658.2      | \$251.75    | 27.7%        | 10.0    | 2.9       |
| 3       | GA Atlanta    | with interior low-e panel                        | 286.55       | 383.82              | 637.92     | \$272.03    | 29.9%        | 8.3     | 3.0       |
| 3       | GA Atlanta    | with exterior solar-E panel                      | 251.35       | 468.29              | 676.3      | \$233.65    | 25.7%        | 10.8    | 3.7       |
| 3       | GA Atlanta    | with exterior clear panel, worst case mounting   | 290.84       | 545.65              | 802.17     | \$107.78    | 11.8%        | 20.9    |           |
| 3       | GA Atlanta    | with exterior low-e panel, worst case mounting   | 276.43       | 504.6               | 743.63     | \$166.32    | 18.3%        | 15.1    |           |
| 3       | GA Atlanta    | with exterior solar-E panel, worst case mounting | 251.13       | 556.72              | 763.74     | \$146.21    | 16.1%        | 17.2    |           |
| 3       | TX Fort Worth | Wood frame, single pane                          | 506.77       | 428.25              | 926.11     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                        | 454.3        | 243.84              | 674.05     | \$252.06    | 27.2%        | 9.0     |           |
| 3       | TX Fort Worth | with interior clear panel                        | 452.32       | 233.7               | 661.93     | \$264.18    | 28.5%        | 9.5     |           |
| 3       | TX Fort Worth | with exterior low-e panel                        | 430.1        | 208.7               | 608.99     | \$317.12    | 34.2%        | 7.9     | 3.9       |
| 3       | TX Fort Worth | with interior low-e panel                        | 438.9        | 184.69              | 601.37     | \$324.74    | 35.1%        | 6.9     | 4.2       |
| 3       | TX Fort Worth | with exterior solar-E panel                      | 389.84       | 243.27              | 592.3      | \$333.81    | 36.0%        | 7.5     | 3.1       |
| 3       | TX Fort Worth | Wood frame, double pane                          | 473.44       | 281.95              | 737.24     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                        | 445.94       | 237.07              | 656.28     | \$80.96     | 11.0%        | 27.9    |           |
| 3       | TX Fort Worth | with interior clear panel                        | 450.01       | 224.35              | 648.95     | \$88.29     | 12.0%        | 28.4    |           |
| 3       | TX Fort Worth | with exterior low-e panel                        | 422.29       | 208.14              | 598.09     | \$139.15    | 18.9%        | 18.1    | 4.4       |
| 3       | TX Fort Worth | with interior low-e panel                        | 433.73       | 187.2               | 596.29     | \$140.95    | 19.1%        | 16.0    | 4.8       |
| 3       | TX Fort Worth | with exterior solar-E panel                      | 384.12       | 241.32              | 582.21     | \$155.03    | 21.0%        | 16.2    | 3.4       |
| 3       | TX Fort Worth | Metal frame, double pane                         | 471.35       | 359.18              | 808.53     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                        | 455.51       | 264.11              | 694.87     | \$113.66    | 14.1%        | 19.9    |           |
| 3       | TX Fort Worth | with interior clear panel                        | 449.46       | 252.17              | 675.34     | \$133.19    | 16.5%        | 18.9    |           |
| 3       | TX Fort Worth | with exterior low-e panel                        | 430.1        | 222.96              | 622.59     | \$185.94    | 23.0%        | 13.5    | 3.5       |
| 3       | TX Fort Worth | with interior low-e panel                        | 435.6        | 206.56              | 612.79     | \$195.74    | 24.2%        | 11.5    | 4.1       |
| 3       | TX Fort Worth | with exterior solar-E panel                      | 390.83       | 257.73              | 606.87     | \$201.66    | 24.9%        | 12.5    | 2.9       |
| 3       | TX Fort Worth | with exterior clear panel, worst case mounting   | 452.32       | 301.24              | 726.28     | \$82.25     | 10.2%        | 27.4    |           |
| 3       | TX Fort Worth | with exterior low-e panel, worst case mounting   | 428.12       | 277.95              | 673.84     | \$134.69    | 16.7%        | 18.6    |           |
| 3       | TX Fort Worth | with exterior solar-E panel, worst case mounting | 395.01       | 309.63              | 663.06     | \$145.47    | 18.0%        | 17.3    |           |

| Climate Zone | Location      | Window  | HVAC           | Whole I | House Cooling | Whole Ho | use Heating | Source | e Energy | % source energy savings |
|--------------|---------------|---|----------------|---------|---------------|----------|-------------|--------|----------|-------------------------|
| 3            | TX Fort Worth | Wood frame, single pane                         | Heat pump / AC | 4526    | kWh           | 3079     | kWh         | 87.3   | MBtu     |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Heat pump / AC |         | kWh           | 1856     | kWh         | 66.2   | MBtu     | 24.2%                   |
| 3            | TX Fort Worth | with interior clear panel                       | Heat pump / AC |         | kWh           | 1788     | kWh         | 65.2   | MBtu     | 25.3%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Heat pump / AC | 3639    | kWh           | 1603     | kWh         | 60.2   | MBtu     | 31.1%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Heat pump / AC | 3788    | kWh           | 1455     | kWh         | 60.2   | MBtu     | 31.1%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Heat pump / AC |         | kWh           | 1777     | kWh         | 56.8   | MBtu     | 34.9%                   |
| 3            | TX Fort Worth | Wood frame, double pane                         | Heat pump / AC | 4139    | kWh           | 2125     | kWh         | 71.9   | MBtu     |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Heat pump / AC |         | kWh           | 1802     | kWh         | 64.4   | MBtu     | 10.4%                   |
| 3            | TX Fort Worth | with interior clear panel                       | Heat pump / AC | 3860    | kWh           | 1725     | kWh         | 64.1   | MBtu     | 10.8%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Heat pump / AC |         | kWh           | 1591     | kWh         | 59.0   | MBtu     | 18.0%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Heat pump / AC |         | kWh           | 1468     | kWh         | 59.6   | MBtu     | 17.2%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Heat pump / AC |         | kWh           | 1757     | kWh         | 55.8   | MBtu     | 22.5%                   |
| 3            | TX Fort Worth | Metal frame, double pane                        | Heat pump / AC |         | kWh           | 2603     | kWh         | 76.8   | MBtu     |                         |
| 3            | TX Fort Worth | with exterior clear panel                       | Heat pump / AC | 3916    | kWh           | 1991     | kWh         | 67.8   | MBtu     | 11.7%                   |
| 3            | TX Fort Worth | with interior clear panel                       | Heat pump / AC | 3847    | kWh           | 1905     | kWh         | 66.0   | MBtu     | 14.0%                   |
| 3            | TX Fort Worth | with exterior low-e panel                       | Heat pump / AC |         | kWh           | 1693     | kWh         | 61.2   | MBtu     | 20.4%                   |
| 3            | TX Fort Worth | with interior low-e panel                       | Heat pump / AC | 3693    | kWh           | 1594     | kWh         | 60.7   | MBtu     | 20.9%                   |
| 3            | TX Fort Worth | with exterior solar-E panel                     | Heat pump / AC |         | kWh           | 1868     | kWh         | 57.9   | MBtu     | 24.6%                   |
| 3            | TX Fort Worth | with exterior clear panel, worst case mounting  | Heat pump / AC | 3864    | kWh           | 2219     | kWh         | 69.8   | MBtu     | 9.0%                    |
| 3            | TX Fort Worth | with exterior low-e panel, worst case mounting  | Heat pump / AC | 3599    | kWh           | 2044     | kWh         | 64.8   | MBtu     | 15.6%                   |
| 3            | TX Fort Worth | with exterior solar-E panel, worst case mountin | Heat pump / AC |         | kWh           | 2199     | kWh         | 62.1   | MBtu     | 19.1%                   |
| 2            | AZ Phoenix    | Wood frame, single pane                         | Heat pump / AC | 7873    | kWh           | 948      | kWh         | 101.3  | MBtu     |                         |
| 2            | AZ Phoenix    | with exterior clear panel                       | Heat pump / AC |         | kWh           | 477      | kWh         | 82.5   | MBtu     | 18.6%                   |
| 2            | AZ Phoenix    | with interior clear panel                       | Heat pump / AC |         | kWh           | 453      | kWh         | 81.8   | MBtu     | 19.2%                   |
| 2            | AZ Phoenix    | with exterior low-e panel                       | Heat pump / AC |         | kWh           | 375      | kWh         | 75.5   | MBtu     | 25.5%                   |
| 2            | AZ Phoenix    | with interior low-e panel                       | Heat pump / AC |         | kWh           | 320      | kWh         | 76.7   | MBtu     | 24.2%                   |
| 2            | AZ Phoenix    | with exterior solar-E panel                     | Heat pump / AC |         | kWh           | 450      | kWh         | 68.9   | MBtu     | 32.0%                   |
| 2            | AZ Phoenix    | Wood frame, double pane                         | Heat pump / AC |         | kWh           | 572      | kWh         | 88.0   | MBtu     |                         |
| 2            | AZ Phoenix    | with exterior clear panel                       | Heat pump / AC |         | kWh           | 457      | kWh         | 80.5   | MBtu     | 8.5%                    |
| 2            | AZ Phoenix    | with interior clear panel                       | Heat pump / AC | 6608    | kWh           | 424      | kWh         | 80.7   | MBtu     | 8.2%                    |
| 2            | AZ Phoenix    | with exterior low-e panel                       | Heat pump / AC | 6042    | kWh           | 370      | kWh         | 73.6   | MBtu     | 16.3%                   |
| 2            | AZ Phoenix    | with interior low-e panel                       | Heat pump / AC |         | kWh           | 324      | kWh         | 75.7   | MBtu     | 14.0%                   |
| 2            | AZ Phoenix    | with exterior solar-E panel                     | Heat pump / AC |         | kWh           | 444      | kWh         | 67.6   | MBtu     | 23.2%                   |
| 2            | AZ Phoenix    | Metal frame, double pane                        | Heat pump / AC | 7305    | kWh           | 804      | kWh         | 93.1   | MBtu     |                         |
| 2            | AZ Phoenix    | with exterior clear panel                       | Heat pump / AC |         | kWh           | 550      | kWh         | 85.4   | MBtu     | 8.3%                    |
| 2            | AZ Phoenix    | with interior clear panel                       | Heat pump / AC |         | kWh           | 517      | kWh         | 83.6   | MBtu     | 10.2%                   |
| 2            | AZ Phoenix    | with exterior low-e panel                       | Heat pump / AC |         | kWh           | 408      | kWh         | 76.1   | MBtu     | 18.2%                   |
| 2            | AZ Phoenix    | with interior low-e panel                       | Heat pump / AC |         | kWh           | 372      | kWh         | 76.6   | MBtu     | 17.7%                   |
| 2            | AZ Phoenix    | with exterior solar-E panel                     | Heat pump / AC |         | kWh           | 487      | kWh         | 69.8   | MBtu     | 25.0%                   |
| 2            | AZ Phoenix    | with exterior clear panel, worst case mounting  | Heat pump / AC |         | kWh           | 646      | kWh         | 86.7   | MBtu     | 6.9%                    |
| 2            | AZ Phoenix    | with exterior low-e panel, worst case mounting  | Heat pump / AC |         | kWh           | 549      | kWh         | 78.6   | MBtu     | 15.6%                   |
| 2            | AZ Phoenix    | with exterior solar-E panel, worst case mountin | Heat pump / AC |         | kWh           | 624      | kWh         | 73.5   | MBtu     | 21.0%                   |

| Climate | Location      | Window   | Cooling Cost | <b>Heating Cost</b> | Total Cost | Energy cost | % energy     | Simple  | Payback   |
|---------|---------------|--|--------------|---------------------|------------|-------------|--------------|---------|-----------|
| Zone    |               |  | (\$)         | (\$)                | (\$)       | savings     | cost savings | payback | for low-e |
| 3       | TX Fort Worth | Wood frame, single pane                          | 506.77       | 338.69              | 836.55     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                        | 454.3        | 204.16              | 634.37     | \$202.18    | 24.2%        | 11.2    |           |
| 3       | TX Fort Worth | with interior clear panel                        | 452.32       | 196.68              | 624.91     | \$211.64    | 25.3%        | 11.9    |           |
| 3       | TX Fort Worth | with exterior low-e panel                        | 430.1        | 176.33              | 576.62     | \$259.93    | 31.1%        | 9.7     | 4.4       |
| 3       | TX Fort Worth | with interior low-e panel                        | 438.9        | 160.05              | 576.73     | \$259.82    | 31.1%        | 8.7     | 5.3       |
| 3       | TX Fort Worth | with exterior solar-E panel                      | 389.84       | 195.47              | 544.5      | \$292.05    | 34.9%        | 8.6     | 2.8       |
| 3       | TX Fort Worth | Wood frame, double pane                          | 473.44       | 233.75              | 689.04     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                        | 445.94       | 198.22              | 617.43     | \$71.61     | 10.4%        | 31.5    |           |
| 3       | TX Fort Worth | with interior clear panel                        | 450.01       | 189.75              | 614.35     | \$74.69     | 10.8%        | 33.6    |           |
| 3       | TX Fort Worth | with exterior low-e panel                        | 422.29       | 175.01              | 564.96     | \$124.08    | 18.0%        | 20.2    | 4.9       |
| 3       | TX Fort Worth | with interior low-e panel                        | 433.73       | 161.48              | 570.57     | \$118.47    | 17.2%        | 19.0    | 5.8       |
| 3       | TX Fort Worth | with exterior solar-E panel                      | 384.12       | 193.27              | 534.16     | \$154.88    | 22.5%        | 16.2    | 3.1       |
| 3       | TX Fort Worth | Metal frame, double pane                         | 471.35       | 286.33              | 735.68     |             |              |         |           |
| 3       | TX Fort Worth | with exterior clear panel                        | 455.51       | 219.01              | 649.77     | \$85.91     | 11.7%        | 26.3    |           |
| 3       | TX Fort Worth | with interior clear panel                        | 449.46       | 209.55              | 632.72     | \$102.96    | 14.0%        | 24.4    |           |
| 3       | TX Fort Worth | with exterior low-e panel                        | 430.1        | 186.23              | 585.86     | \$149.82    | 20.4%        | 16.8    | 4.0       |
| 3       | TX Fort Worth | with interior low-e panel                        | 435.6        | 175.34              | 581.57     | \$154.11    | 20.9%        | 14.6    | 5.0       |
| 3       | TX Fort Worth | with exterior solar-E panel                      | 390.83       | 205.48              | 554.62     | \$181.06    | 24.6%        | 13.9    | 2.7       |
| 3       | TX Fort Worth | with exterior clear panel, worst case mounting   | 452.32       | 244.09              | 669.13     | \$66.55     | 9.0%         | 33.9    |           |
| 3       | TX Fort Worth | with exterior low-e panel, worst case mounting   | 428.12       | 224.84              | 620.73     | \$114.95    | 15.6%        | 21.9    |           |
| 3       | TX Fort Worth | with exterior solar-E panel, worst case mounting | 395.01       | 241.89              | 595.32     | \$140.36    | 19.1%        | 17.9    |           |
| 2       | AZ Phoenix    | Wood frame, single pane                          | 961.86       | 107.12              | 996.77     |             |              |         |           |
| 2       | AZ Phoenix    | with exterior clear panel                        | 857.78       | 53.9                | 811.79     | \$184.98    | 18.6%        | 12.2    |           |
| 2       | AZ Phoenix    | with interior clear panel                        | 854.17       | 51.19               | 805.24     | \$191.53    | 19.2%        | 13.1    |           |
| 2       | AZ Phoenix    | with exterior low-e panel                        | 808.74       | 42.37               | 742.63     | \$254.14    | 25.5%        | 9.9     | 3.7       |
| 2       | AZ Phoenix    | with interior low-e panel                        | 824.33       | 36.16               | 755.18     | \$241.59    | 24.2%        | 9.3     | 5.1       |
| 2       | AZ Phoenix    | with exterior solar-E panel                      | 749.64       | 50.85               | 678.23     | \$318.54    | 32.0%        | 7.9     | 1.9       |
| 2       | AZ Phoenix    | Wood frame, double pane                          | 893.04       | 64.64               | 865.7      |             |              |         |           |
| 2       | AZ Phoenix    | with exterior clear panel                        | 844.11       | 51.64               | 791.79     | \$73.91     | 8.5%         | 30.5    |           |
| 2       | AZ Phoenix    | with interior clear panel                        | 849.31       | 47.91               | 794.61     | \$71.09     | 8.2%         | 35.3    |           |
| 2       | AZ Phoenix    | with exterior low-e panel                        | 795.75       | 41.81               | 724.56     | \$141.14    | 16.3%        | 17.8    | 3.8       |
| 2       | AZ Phoenix    | with interior low-e panel                        | 816.42       | 36.61               | 744.89     | \$120.81    | 14.0%        | 18.7    | 5.1       |
| 2       | AZ Phoenix    | with exterior solar-E panel                      | 740.04       | 50.17               | 665.12     | \$200.58    | 23.2%        | 12.5    | 2.0       |
| 2       | AZ Phoenix    | Metal frame, double pane                         | 905.81       | 90.85               | 916.31     |             |              |         |           |
| 2       | AZ Phoenix    | with exterior clear panel                        | 866.6        | 62.15               | 840.49     | \$75.82     | 8.3%         | 29.8    |           |
| 2       | AZ Phoenix    | with interior clear panel                        | 855.52       | 58.42               | 823.2      | \$93.11     | 10.2%        | 27.0    |           |
| 2       | AZ Phoenix    | with exterior low-e panel                        | 812.58       | 46.1                | 749.3      | \$167.01    | 18.2%        | 15.0    | 2.8       |
| 2       | AZ Phoenix    | with interior low-e panel                        | 819.14       | 42.04               | 753.71     | \$162.60    | 17.7%        | 13.9    | 3.7       |
| 2       | AZ Phoenix    | with exterior solar-E panel                      | 754.73       | 55.03               | 687.38     | \$228.93    | 25.0%        | 11.0    | 1.7       |
| 2       | AZ Phoenix    | with exterior clear panel, worst case mounting   | 869.08       | 73                  | 853.04     | \$63.27     | 6.9%         | 35.7    |           |
| 2       | AZ Phoenix    | with exterior low-e panel, worst case mounting   | 822.3        | 62.04               | 773.83     | \$142.48    | 15.5%        | 17.6    |           |
| 2       | AZ Phoenix    | with exterior solar-E panel, worst case mounting | 773.03       | 70.51               | 723.54     | \$192.77    | 21.0%        | 13.0    |           |

| Climate Zone | Location        | Window  | HVAC           | Whole I | House Cooling | Whole Ho | use Heating | Source | e Energy | % source energy savings |
|--------------|-----------------|---|----------------|---------|---------------|----------|-------------|--------|----------|-------------------------|
| 2            | FL Jacksonville | Wood frame, single pane                         | Heat pump / AC | 4599    | kWh           | 1504     | kWh         | 70.1   | MBtu     |                         |
| 2            | FL Jacksonville | with exterior clear panel                       | Heat pump / AC | 4022    | kWh           | 823      | kWh         | 55.6   | MBtu     | 20.6%                   |
| 2            | FL Jacksonville | with interior clear panel                       | Heat pump / AC | 4004    | kWh           | 786      | kWh         | 55.0   | MBtu     | 21.5%                   |
| 2            | FL Jacksonville | with exterior low-e panel                       | Heat pump / AC | 3774    | kWh           | 680      | kWh         | 51.1   | MBtu     | 27.0%                   |
|              | FL Jacksonville | with interior low-e panel                       | Heat pump / AC | 3947    | kWh           | 594      | kWh         | 52.1   | MBtu     | 25.6%                   |
| 2            | FL Jacksonville | with exterior solar-E panel                     | Heat pump / AC | 3274    | kWh           | 804      | kWh         | 46.8   | MBtu     | 33.2%                   |
|              | FL Jacksonville | Wood frame, double pane                         | Heat pump / AC | 4234    | kWh           | 968      | kWh         | 59.7   | MBtu     |                         |
| 2            | FL Jacksonville | with exterior clear panel                       | Heat pump / AC | 3918    | kWh           | 798      | kWh         | 54.1   | MBtu     | 9.3%                    |
|              | FL Jacksonville | with interior clear panel                       | Heat pump / AC | 3975    | kWh           | 749      | kWh         | 54.2   | MBtu     | 9.2%                    |
| 2            | FL Jacksonville | with exterior low-e panel                       | Heat pump / AC | 3673    | kWh           | 674      | kWh         | 49.9   | MBtu     | 16.4%                   |
| 2            | FL Jacksonville | with interior low-e panel                       | Heat pump / AC | 3866    | kWh           | 602      | kWh         | 51.3   | MBtu     | 14.1%                   |
| 2            | FL Jacksonville | with exterior solar-E panel                     | Heat pump / AC | 3202    | kWh           | 794      | kWh         | 45.9   | MBtu     | 23.2%                   |
| 2            | FL Jacksonville | Metal frame, double pane                        | Heat pump / AC | 4143    | kWh           | 1255     | kWh         | 62.0   | MBtu     |                         |
| 2            | FL Jacksonville | with exterior clear panel                       | Heat pump / AC | 4005    | kWh           | 900      | kWh         | 56.3   | MBtu     | 9.1%                    |
| 2            | FL Jacksonville | with interior clear panel                       | Heat pump / AC | 3938    | kWh           | 855      | kWh         | 55.0   | MBtu     | 11.2%                   |
| 2            | FL Jacksonville | with exterior low-e panel                       | Heat pump / AC | 3753    | kWh           | 735      | kWh         | 51.5   | MBtu     | 16.9%                   |
| 2            | FL Jacksonville | with interior low-e panel                       | Heat pump / AC | 3826    | kWh           | 675      | kWh         | 51.7   | MBtu     | 16.6%                   |
| 2            | FL Jacksonville | with exterior solar-E panel                     | Heat pump / AC | 3269    | kWh           | 857      | kWh         | 47.4   | MBtu     | 23.6%                   |
|              | FL Jacksonville | with exterior clear panel, worst case mounting  | Heat pump / AC | 3928    | kWh           | 1039     | kWh         | 57.0   | MBtu     | 8.0%                    |
| 2            | FL Jacksonville | with exterior low-e panel, worst case mounting  | Heat pump / AC | 3679    | kWh           | 940      | kWh         | 53.0   | MBtu     | 14.4%                   |
| 2            | FL Jacksonville | with exterior solar-E panel, worst case mountin | Heat pump / AC | 3281    | kWh           | 1052     | kWh         | 49.8   | MBtu     | 19.7%                   |
| 2            | TX Houston      | Wood frame, single pane                         | Furnace / AC   | 4865    | kWh           | 25.1     | MBtu        | 83.3   | MBtu     |                         |
| 2            | TX Houston      | with exterior clear panel                       | Furnace / AC   | 4236    | kWh           | 14.1     | MBtu        | 64.0   | MBtu     | 23.1%                   |
| 2            | TX Houston      | with interior clear panel                       | Furnace / AC   | 4218    | kWh           | 13.5     | MBtu        | 63.2   | MBtu     | 24.1%                   |
| 2            | TX Houston      | with exterior low-e panel                       | Furnace / AC   | 3976    | kWh           | 11.8     | MBtu        | 58.5   | MBtu     | 29.7%                   |
| 2            | TX Houston      | with interior low-e panel                       | Furnace / AC   | 4145    | kWh           | 10.4     | MBtu        | 58.9   | MBtu     | 29.2%                   |
| 2            | TX Houston      | with exterior solar-E panel                     | Furnace / AC   | 3461    | kWh           | 13.6     | MBtu        | 54.6   | MBtu     | 34.4%                   |
| 2            | TX Houston      | Wood frame, double pane                         | Furnace / AC   | 4475    | kWh           | 16.4     | MBtu        | 69.3   | MBtu     |                         |
| 2            | TX Houston      | with exterior clear panel                       | Furnace / AC   | 4132    | kWh           | 13.6     | MBtu        | 62.3   | MBtu     | 10.1%                   |
| 2            | TX Houston      | with interior clear panel                       | Furnace / AC   | 4185    | kWh           | 12.9     | MBtu        | 62.1   | MBtu     | 10.3%                   |
| 2            | TX Houston      | with exterior low-e panel                       | Furnace / AC   | 3874    | kWh           | 11.7     | MBtu        | 57.3   | MBtu     | 17.4%                   |
| 2            | TX Houston      | with interior low-e panel                       | Furnace / AC   | 4071    | kWh           | 10.6     | MBtu        | 58.3   | MBtu     | 15.8%                   |
| 2            | TX Houston      | with exterior solar-E panel                     | Furnace / AC   | 3391    | kWh           | 13.4     | MBtu        | 53.6   | MBtu     | 22.7%                   |
| 2            | TX Houston      | Metal frame, double pane                        | Furnace / AC   | 4380    | kWh           | 21       | MBtu        | 73.2   | MBtu     |                         |
| 2            | TX Houston      | with exterior clear panel                       | Furnace / AC   | 4230    | kWh           | 15.3     | MBtu        | 65.3   | MBtu     | 10.9%                   |
| 2            | TX Houston      | with interior clear panel                       | Furnace / AC   | 4160    | kWh           | 14.5     | MBtu        | 63.6   | MBtu     | 13.1%                   |
| 2            | TX Houston      | with exterior low-e panel                       | Furnace / AC   | 3959    | kWh           | 12.6     | MBtu        | 59.2   | MBtu     | 19.1%                   |
| 2            | TX Houston      | with interior low-e panel                       | Furnace / AC   | 4031    | kWh           | 11.7     | MBtu        | 59.1   | MBtu     | 19.3%                   |
| 2            | TX Houston      | with exterior solar-E panel                     | Furnace / AC   | 3460    | kWh           | 14.4     | MBtu        | 55.5   | MBtu     | 24.3%                   |
| 2            | TX Houston      | with exterior clear panel, worst case mounting  | Furnace / AC   | 4156    | kWh           | 17.4     | MBtu        | 66.7   | MBtu     | 8.9%                    |
| 2            | TX Houston      | with exterior low-e panel, worst case mounting  | Furnace / AC   | 3892    | kWh           | 15.9     | MBtu        | 62.1   | MBtu     | 15.3%                   |
| 2            | TX Houston      | with exterior solar-E panel, worst case mountin | Furnace / AC   | 3480    | kWh           | 17.5     | MBtu        | 59.1   | MBtu     | 19.3%                   |

| Climate | Location        | Window   | Cooling Cost | <b>Heating Cost</b> | Total Cost | Energy cost | % energy     | Simple  | Payback   |
|---------|-----------------|--|--------------|---------------------|------------|-------------|--------------|---------|-----------|
| Zone    |                 |  | (\$)         | (\$)                | (\$)       | savings     | cost savings | payback | for low-e |
| 2       | FL Jacksonville | Wood frame, single pane                          | 555.34       | 172.96              | 701.85     |             |              |         |           |
| 2       | FL Jacksonville | with exterior clear panel                        | 503.59       | 94.65               | 557.18     | \$144.67    | 20.6%        | 15.6    |           |
| 2       | FL Jacksonville | with interior clear panel                        | 501.75       | 90.39               | 550.85     | \$151.00    | 21.5%        | 16.6    |           |
| 2       | FL Jacksonville | with exterior low-e panel                        | 479.67       | 78.2                | 512.21     | \$189.64    | 27.0%        | 13.2    | 5.7       |
| 2       | FL Jacksonville | with interior low-e panel                        | 494.96       | 68.31               | 522.22     | \$179.63    | 25.6%        | 12.6    | 8.9       |
| 2       | FL Jacksonville | with exterior solar-E panel                      | 434.93       | 92.46               | 468.97     | \$232.88    | 33.2%        | 10.8    | 2.9       |
| 2       | FL Jacksonville | Wood frame, double pane                          | 523.6        | 111.32              | 598.23     |             |              |         |           |
| 2       | FL Jacksonville | with exterior clear panel                        | 494.5        | 91.77               | 542.34     | \$55.89     | 9.3%         | 40.4    |           |
| 2       | FL Jacksonville | with interior clear panel                        | 498.87       | 86.14               | 543.27     | \$54.96     | 9.2%         | 45.7    |           |
| 2       | FL Jacksonville | with exterior low-e panel                        | 471.62       | 77.51               | 499.91     | \$98.32     | 16.4%        | 25.5    | 6.0       |
| 2       | FL Jacksonville | with interior low-e panel                        | 488.52       | 69.23               | 513.82     | \$84.41     | 14.1%        | 26.7    | 8.7       |
| 2       | FL Jacksonville | with exterior solar-E panel                      | 429.07       | 91.31               | 459.54     | \$138.69    | 23.2%        | 18.1    | 3.1       |
| 2       | FL Jacksonville | Metal frame, double pane                         | 516.47       | 144.33              | 620.78     |             |              |         |           |
| 2       | FL Jacksonville | with exterior clear panel                        | 503.13       | 103.5               | 564.08     | \$56.70     | 9.1%         | 39.8    |           |
| 2       | FL Jacksonville | with interior clear panel                        | 497.26       | 98.33               | 551.2      | \$69.58     | 11.2%        | 36.1    |           |
| 2       | FL Jacksonville | with exterior low-e panel                        | 479.32       | 84.53               | 516.13     | \$104.65    | 16.9%        | 24.0    | 5.3       |
| 2       | FL Jacksonville | with interior low-e panel                        | 485.76       | 77.63               | 517.62     | \$103.16    | 16.6%        | 21.9    | 7.6       |
| 2       | FL Jacksonville | with exterior solar-E panel                      | 435.05       | 98.56               | 474.5      | \$146.28    | 23.6%        | 17.2    | 2.8       |
| 2       | FL Jacksonville | with exterior clear panel, worst case mounting   | 497.61       | 119.49              | 571.21     | \$49.57     | 8.0%         | 45.5    |           |
| 2       | FL Jacksonville | with exterior low-e panel, worst case mounting   | 474.61       | 108.1               | 531.19     | \$89.59     | 14.4%        | 28.0    |           |
| 2       | FL Jacksonville | with exterior solar-E panel, worst case mounting | 437.58       | 120.98              | 498.3      | \$122.48    | 19.7%        | 20.5    |           |
| 2       | TX Houston      | Wood frame, single pane                          | 543.95       | 267.73              | 802.88     |             |              |         |           |
| 2       | TX Houston      | with exterior clear panel                        | 490.49       | 149.64              | 615.6      | \$187.28    | 23.3%        | 12.1    |           |
| 2       | TX Houston      | with interior clear panel                        | 488.07       | 143.31              | 607.29     | \$195.59    | 24.4%        | 12.8    |           |
| 2       | TX Houston      | with exterior low-e panel                        | 466.95       | 125.82              | 563.18     | \$239.70    | 29.9%        | 10.5    | 4.9       |
| 2       | TX Houston      | with interior low-e panel                        | 480.81       | 111.02              | 566.97     | \$235.91    | 29.4%        | 9.6     | 6.3       |
| 2       | TX Houston      | with exterior solar-E panel                      | 422.29       | 144.65              | 525.36     | \$277.52    | 34.6%        | 9.1     | 2.8       |
| 2       | TX Houston      | Wood frame, double pane                          | 511.06       | 174.6               | 666.85     |             |              |         |           |
| 2       | TX Houston      | with exterior clear panel                        | 481.58       | 144.77              | 599.29     | \$67.56     | 10.1%        | 33.4    |           |
| 2       | TX Houston      | with interior clear panel                        | 485.65       | 136.96              | 597.31     | \$69.54     | 10.4%        | 36.1    |           |
| 2       | TX Houston      | with exterior low-e panel                        | 458.04       | 124.83              | 550.97     | \$115.88    | 17.4%        | 21.7    | 5.3       |
| 2       | TX Houston      | with interior low-e panel                        | 474.87       | 112.44              | 560.25     | \$106.60    | 16.0%        | 21.2    | 6.9       |
| 2       | TX Houston      | with exterior solar-E panel                      | 416.13       | 143.06              | 516.07     | \$150.78    | 22.6%        | 16.7    | 3.1       |
| 2       | TX Houston      | Metal frame, double pane                         | 504.79       | 223.32              | 705.12     |             |              |         |           |
| 2       | TX Houston      | with exterior clear panel                        | 490.27       | 162.47              | 627.77     | \$77.35     | 11.0%        | 29.2    |           |
| 2       | TX Houston      | with interior clear panel                        | 484.11       | 154.74              | 612.34     | \$92.78     | 13.2%        | 27.1    |           |
| 2       | TX Houston      | with exterior low-e panel                        | 466.07       | 134.46              | 569.95     | \$135.17    | 19.2%        | 18.6    | 4.4       |
| 2       | TX Houston      | with interior low-e panel                        | 471.9        | 124.78              | 568.19     | \$136.93    | 19.4%        | 16.5    | 5.8       |
| 2       | TX Houston      | with exterior solar-E panel                      | 422.4        | 153.65              | 534.25     | \$170.87    | 24.2%        | 14.7    | 2.7       |
| 2       | TX Houston      | with exterior clear panel, worst case mounting   | 485.32       | 185.61              | 642.77     | \$62.35     | 8.8%         | 36.2    |           |
| 2       | TX Houston      | with exterior low-e panel, worst case mounting   | 461.67       | 168.86              | 596.98     | \$108.14    | 15.3%        | 23.2    |           |
| 2       | TX Houston      | with exterior solar-E panel, worst case mounting | 424.93       | 186.81              | 569.61     | \$135.51    | 19.2%        | 18.5    |           |

| Climate Zone | Location   | Window  | HVAC           | Whole H | ouse Cooling | Whole Hou | use Heating | Source | Energy | % source energy savings |
|--------------|------------|---|----------------|---------|--------------|-----------|-------------|--------|--------|-------------------------|
| 2            | TX Houston | Wood frame, single pane                         | Heat pump / AC | 4865    | kWh          | 2035      | kWh         | 79.2   | MBtu   |                         |
| 2            | TX Houston | with exterior clear panel                       | Heat pump / AC |         | kWh          | 1214      | kWh         | 62.6   | MBtu   | 21.0%                   |
| 2            | TX Houston | with interior clear panel                       | Heat pump / AC | 4218    | kWh          | 1168      | kWh         | 61.8   | MBtu   | 21.9%                   |
| 2            | TX Houston | with exterior low-e panel                       | Heat pump / AC | 3976    | kWh          | 1034      | kWh         | 57.5   | MBtu   | 27.4%                   |
| 2            | TX Houston | with interior low-e panel                       | Heat pump / AC | 4145    | kWh          | 941       | kWh         | 58.4   | MBtu   | 26.3%                   |
| 2            | TX Houston | with exterior solar-E panel                     | Heat pump / AC | 3461    | kWh          | 1131      | kWh         | 52.7   | MBtu   | 33.4%                   |
| 2            | TX Houston | Wood frame, double pane                         | Heat pump / AC | 4475    | kWh          | 1400      | kWh         | 67.5   | MBtu   |                         |
| 2            | TX Houston | with exterior clear panel                       | Heat pump / AC | 4132    | kWh          | 1174      | kWh         | 60.9   | MBtu   | 9.7%                    |
| 2            | TX Houston | with interior clear panel                       | Heat pump / AC |         | kWh          | 1124      | kWh         | 61.0   | MBtu   | 9.6%                    |
| 2            | TX Houston | with exterior low-e panel                       | Heat pump / AC | 3874    | kWh          | 1020      | kWh         | 56.2   | MBtu   | 16.7%                   |
| 2            | TX Houston | with interior low-e panel                       | Heat pump / AC | 4071    | kWh          | 947       | kWh         | 57.6   | MBtu   | 14.6%                   |
| 2            | TX Houston | with exterior solar-E panel                     | Heat pump / AC | 3391    | kWh          | 1117      | kWh         | 51.8   | MBtu   | 23.3%                   |
| 2            | TX Houston | Metal frame, double pane                        | Heat pump / AC |         | kWh          | 1714      | kWh         | 70.0   | MBtu   |                         |
| 2            | TX Houston | with exterior clear panel                       | Heat pump / AC | 4230    | kWh          | 1301      | kWh         | 63.5   | MBtu   | 9.2%                    |
| 2            | TX Houston | with interior clear panel                       | Heat pump / AC | 4160    | kWh          | 1245      | kWh         | 62.1   | MBtu   | 11.3%                   |
| 2            | TX Houston | with exterior low-e panel                       | Heat pump / AC | 3959    | kWh          | 1091      | kWh         | 58.0   | MBtu   | 17.1%                   |
| 2            | TX Houston | with interior low-e panel                       | Heat pump / AC | 4031    | kWh          | 1030      | kWh         | 58.1   | MBtu   | 17.0%                   |
| 2            | TX Houston | with exterior solar-E panel                     | Heat pump / AC | 3460    | kWh          | 1191      | kWh         | 53.4   | MBtu   | 23.7%                   |
| 2            | TX Houston | with exterior clear panel, worst case mounting  | Heat pump / AC |         | kWh          | 1453      | kWh         | 64.4   | MBtu   | 8.0%                    |
| 2            | TX Houston | with exterior low-e panel, worst case mounting  | Heat pump / AC | 3892    | kWh          | 1322      | kWh         | 59.9   | MBtu   | 14.4%                   |
| 2            | TX Houston | with exterior solar-E panel, worst case mountin | Heat pump / AC | 3480    | kWh          | 1413      | kWh         | 56.2   | MBtu   | 19.7%                   |
| 1            | FL Miami   | Wood frame, single pane                         | Heat pump / AC | 7514    | kWh          | 60        | kWh         | 87.0   | MBtu   |                         |
| 1            | FL Miami   | with exterior clear panel                       | Heat pump / AC |         | kWh          | 18        | kWh         | 76.3   | MBtu   | 12.3%                   |
| 1            | FL Miami   | with interior clear panel                       | Heat pump / AC | 6589    | kWh          | 16        | kWh         | 75.8   | MBtu   | 12.8%                   |
| 1            | FL Miami   | with exterior low-e panel                       | Heat pump / AC | 6265    | kWh          | 11        | kWh         | 72.1   | MBtu   | 17.1%                   |
| 1            | FL Miami   | with interior low-e panel                       | Heat pump / AC | 6489    | kWh          | 8         | kWh         | 74.6   | MBtu   | 14.2%                   |
| 1            | FL Miami   | with exterior solar-E panel                     | Heat pump / AC | 5527    | kWh          | 14        | kWh         | 63.6   | MBtu   | 26.8%                   |
| 1            | FL Miami   | Wood frame, double pane                         | Heat pump / AC | 6968    | kWh          | 24        | kWh         | 80.3   | MBtu   |                         |
| 1            | FL Miami   | with exterior clear panel                       | Heat pump / AC |         | kWh          | 16        | kWh         | 74.6   | MBtu   | 7.0%                    |
| 1            | FL Miami   | with interior clear panel                       | Heat pump / AC |         | kWh          | 14        | kWh         | 75.4   | MBtu   | 6.1%                    |
| 1            | FL Miami   | with exterior low-e panel                       | Heat pump / AC | 6120    | kWh          | 11        | kWh         | 70.4   | MBtu   | 12.3%                   |
| 1            | FL Miami   | with interior low-e panel                       | Heat pump / AC | 6388    | kWh          | 8         | kWh         | 73.4   | MBtu   | 8.5%                    |
| 1            | FL Miami   | with exterior solar-E panel                     | Heat pump / AC | 5423    | kWh          | 14        | kWh         | 62.4   | MBtu   | 22.2%                   |
| 1            | FL Miami   | Metal frame, double pane                        | Heat pump / AC | 6829    | kWh          | 40        | kWh         | 78.9   | MBtu   |                         |
| 1            | FL Miami   | with exterior clear panel                       | Heat pump / AC | 6612    | kWh          | 21        | kWh         | 76.2   | MBtu   | 3.4%                    |
| 1            | FL Miami   | with interior clear panel                       | Heat pump / AC |         | kWh          | 19        | kWh         | 75.0   | MBtu   | 4.9%                    |
| 1            | FL Miami   | with exterior low-e panel                       | Heat pump / AC |         | kWh          | 13        | kWh         | 71.8   | MBtu   | 9.0%                    |
| 1            | FL Miami   | with interior low-e panel                       | Heat pump / AC |         | kWh          | 11        | kWh         | 72.9   | MBtu   | 7.6%                    |
| 1            | FL Miami   | with exterior solar-E panel                     | Heat pump / AC |         | kWh          | 16        | kWh         | 63.6   | MBtu   | 19.3%                   |
| 1            | FL Miami   | with exterior clear panel, worst case mounting  | Heat pump / AC |         | kWh          | 27        | kWh         | 75.0   | MBtu   | 4.9%                    |
| 1            | FL Miami   | with exterior low-e panel, worst case mounting  | Heat pump / AC | 6141    | kWh          | 21        | kWh         | 70.8   | MBtu   | 10.3%                   |
| 1            | FL Miami   | with exterior solar-E panel, worst case mountin | Heat pump / AC | 5538    | kWh          | 26        | kWh         | 63.9   | MBtu   | 19.0%                   |

| Climate | Location   | Window   | Cooling Cost | <b>Heating Cost</b> | Total Cost | Energy cost | % energy     | Simple  | Payback   |
|---------|------------|--|--------------|---------------------|------------|-------------|--------------|---------|-----------|
| Zone    |            |  | (\$)         | (\$)                | (\$)       | savings     | cost savings | payback | for low-e |
| 2       | TX Houston | Wood frame, single pane                          | 543.95       | 223.85              | 759        |             |              |         |           |
| 2       | TX Houston | with exterior clear panel                        | 490.49       | 133.54              | 599.5      | \$159.50    | 21.0%        | 14.1    |           |
| 2       | TX Houston | with interior clear panel                        | 488.07       | 128.48              | 592.46     | \$166.54    | 21.9%        | 15.1    |           |
| 2       | TX Houston | with exterior low-e panel                        | 466.95       | 113.74              | 551.1      | \$207.90    | 27.4%        | 12.1    | 5.3       |
| 2       | TX Houston | with interior low-e panel                        | 480.81       | 103.51              | 559.46     | \$199.54    | 26.3%        | 11.3    | 7.7       |
| 2       | TX Houston | with exterior solar-E panel                      | 422.29       | 124.41              | 505.12     | \$253.88    | 33.4%        | 9.9     | 2.7       |
| 2       | TX Houston | Wood frame, double pane                          | 511.06       | 154                 | 646.25     |             |              |         |           |
| 2       | TX Houston | with exterior clear panel                        | 481.58       | 129.14              | 583.66     | \$62.59     | 9.7%         | 36.1    |           |
| 2       | TX Houston | with interior clear panel                        | 485.65       | 123.64              | 583.99     | \$62.26     | 9.6%         | 40.3    |           |
| 2       | TX Houston | with exterior low-e panel                        | 458.15       | 112.2               | 538.34     | \$107.91    | 16.7%        | 23.3    | 5.6       |
| 2       | TX Houston | with interior low-e panel                        | 474.87       | 104.17              | 551.98     | \$94.27     | 14.6%        | 23.9    | 8.0       |
| 2       | TX Houston | with exterior solar-E panel                      | 416.13       | 122.87              | 495.88     | \$150.37    | 23.3%        | 16.7    | 2.9       |
| 2       | TX Houston | Metal frame, double pane                         | 504.79       | 188.54              | 670.34     |             |              |         |           |
| 2       | TX Houston | with exterior clear panel                        | 490.27       | 143.11              | 608.41     | \$61.93     | 9.2%         | 36.4    |           |
| 2       | TX Houston | with interior clear panel                        | 484.11       | 136.95              | 594.55     | \$75.79     | 11.3%        | 33.1    |           |
| 2       | TX Houston | with exterior low-e panel                        | 466.07       | 120.01              | 555.5      | \$114.84    | 17.1%        | 21.9    | 4.8       |
| 2       | TX Houston | with interior low-e panel                        | 471.9        | 113.3               | 556.71     | \$113.63    | 17.0%        | 19.9    | 6.7       |
| 2       | TX Houston | with exterior solar-E panel                      | 422.4        | 131.01              | 511.61     | \$158.73    | 23.7%        | 15.8    | 2.6       |
| 2       | TX Houston | with exterior clear panel, worst case mounting   | 485.32       | 159.83              | 616.99     | \$53.35     | 8.0%         | 42.3    |           |
| 2       | TX Houston | with exterior low-e panel, worst case mounting   | 461.67       | 145.42              | 573.54     | \$96.80     | 14.4%        | 25.9    |           |
| 2       | TX Houston | with exterior solar-E panel, worst case mounting | 424.93       | 155.43              | 538.23     | \$132.11    | 19.7%        | 19.0    |           |
| 1       | FL Miami   | Wood frame, single pane                          | 874.12       | 6.9                 | 871.01     |             |              |         |           |
| 1       | FL Miami   | with exterior clear panel                        | 795.8        | 2.07                | 764.18     | \$106.83    | 12.3%        | 21.1    |           |
| 1       | FL Miami   | with interior clear panel                        | 792.35       | 1.84                | 759.58     | \$111.43    | 12.8%        | 22.5    |           |
| 1       | FL Miami   | with exterior low-e panel                        | 761.88       | 1.27                | 721.75     | \$149.26    | 17.1%        | 16.8    | 6.0       |
| 1       | FL Miami   | with interior low-e panel                        | 781.66       | 0.92                | 747.16     | \$123.85    | 14.2%        | 18.2    | 20.5      |
| 1       | FL Miami   | with exterior solar-E panel                      | 695.87       | 1.61                | 637.22     | \$233.79    | 26.8%        | 10.7    | 2.0       |
| 1       | FL Miami   | Wood frame, double pane                          | 827.2        | 2.76                | 804.08     |             |              |         |           |
| 1       | FL Miami   | with exterior clear panel                        | 783.5        | 1.84                | 747.62     | \$56.46     | 7.0%         | 40.0    |           |
| 1       | FL Miami   | with interior clear panel                        | 789.13       | 1.61                | 754.86     | \$49.22     | 6.1%         | 51.0    |           |
| 1       | FL Miami   | with exterior low-e panel                        | 749.46       | 1.27                | 705.07     | \$99.01     | 12.3%        | 25.4    | 6.0       |
| 1       | FL Miami   | with interior low-e panel                        | 773.26       | 0.92                | 735.54     | \$68.54     | 8.5%         | 32.9    | 13.2      |
| 1       | FL Miami   | with exterior solar-E panel                      | 686.78       | 1.61                | 625.26     | \$178.82    | 22.2%        | 14.0    | 2.1       |
| 1       | FL Miami   | Metal frame, double pane                         | 816.5        | 4.6                 | 789.94     |             |              |         |           |
| 1       | FL Miami   | with exterior clear panel                        | 795.92       | 2.42                | 762.8      | \$27.14     | 3.4%         | 83.2    |           |
| 1       | FL Miami   | with interior clear panel                        | 786.83       | 2.19                | 750.84     | \$39.10     | 4.9%         | 64.2    |           |
| 1       | FL Miami   | with exterior low-e panel                        | 760.5        | 1.5                 | 719.1      | \$70.84     | 9.0%         | 35.5    | 5.8       |
| 1       | FL Miami   | with interior low-e panel                        | 769.35       | 1.27                | 730.14     | \$59.80     | 7.6%         | 37.7    | 12.3      |
| 1       | FL Miami   | with exterior solar-E panel                      | 695.98       | 1.84                | 637.22     | \$152.72    | 19.3%        | 16.4    | 2.0       |
| 1       | FL Miami   | with exterior clear panel, worst case mounting   | 788.33       | 3.11                | 751.42     | \$38.52     | 4.9%         | 58.6    |           |
| 1       | FL Miami   | with exterior low-e panel, worst case mounting   | 753.71       | 2.42                | 708.64     | \$81.30     | 10.3%        | 30.9    |           |
| 1       | FL Miami   | with exterior solar-E panel, worst case mounting | 697.82       | 2.99                | 639.86     | \$150.08    | 19.0%        | 16.7    |           |



Energy Efficiency & Renewable Energy

EERE Information Center 1-877-EERE-INF (1-877-337-3463) www.eere.energy.gov/informationcenter

PNNL-22864 • September 2013

Printed with a renewable-source ink on paper containing at least 50% wastepaper, including 10% post-consumer waste.